

# QUINHAGAK STREET

## Reconstruction



### FINAL DESIGN STUDY REPORT

NOVEMBER 2023

MOA PM&E Project No. 21-13



*Prepared for:*  
Municipality of Anchorage  
Project Management &  
Engineering Department  
4700 Elmore Road  
Anchorage, AK 99507

*Prepared by:*



CRW Engineering Group, Inc.  
3940 Arctic Blvd. Suite 300  
Anchorage, AK 99503

## Executive Summary

### I. Introduction

The Municipality of Anchorage Project Management and Engineering Department (MOA PM&E) has contracted with CRW Engineering Group, Inc. (CRW) to provide professional services to develop and evaluate alternatives to upgrade Quinhagak Street from E. Dowling Road to Askeland Drive (see [FIGURE 1](#) in the main body for project location and vicinity map). The purpose of the project is to upgrade Quinhagak Street to meet current MOA Design Criteria for a local roadway. The roadway conditions are very poor and include significant rutting, cracking, and heaving along the pavement and curb and gutters. These conditions result in ponding in the roadway, rough driving conditions, and frequent maintenance.

Improvements are expected to include:

- Road structural section
- Asphalt pavement and curbs and gutters
- Storm drain system infrastructure
- Pedestrian facilities
- Street lighting
- Signage

The project is currently funded through the draft design study phase only. Additional funding will be necessary to complete design and construction of the project.

Stakeholder comments were solicited using the Context Sensitive Solutions (CSS) process through the following venues:

- Project Website and Interactive Project Map
- Direct Mailings (3) and Electronic Newsletters (8)
- Project Questionnaire
- Abbott Loop Community Council Meeting Presentations (2)
- Public Open House Meetings (2)
- Agency Coordination Meetings


The Design Study Report (DSR) evaluates existing and future conditions and a range of conceptual design alternatives. Preliminary recommended improvements are summarized below.

### II. Recommended Improvements

To achieve the project goals, meet the requirements of the MOA Design Criteria Manual (DCM) and Anchorage Municipal Code (AMC) Title 21, and based on comments received from public, agency, and business stakeholders the recommended improvements for the project are as follows:

## A. Roadway Cross Section

The preferred roadway cross section is Alternative 3 (see typical section below) and includes two 11-foot wide travel lanes with 3.5-foot wide shoulders (33 feet total width from BOC), and a single 5-foot wide sidewalk with a 3-foot wide concrete buffer on the east side of the roadway. The buffer will be eliminated along Parcels 2 and 3 to improve sight distance of sidewalk users due to the fence with slats on property. Type 2 (rolled) curb and gutter is proposed on the west side and Type 1 (barrier) curb and gutter is proposed on the east side of the roadway. This alternative matches the existing curb type on the west side of the roadway, but barrier curb is proposed on the east side of the roadway where the sidewalk is proposed. Since the project is a local road, no roadway traffic markings are proposed along the project corridor.



*Preferred Roadway Typical Section*

## B. Design and Posted Speed Limit

It is proposed that the posted speed limit for Quinhagak Street remain at 25 mph. A Design speed of 30 mph is proposed.

## C. Roadway Horizontal and Vertical Alignment

The proposed roadway cross section will be centered within the ROW from Askeland Drive to Station 19+25. To avoid the proposed curb and gutter conflicting with existing water valves along Quinhagak Street beginning at Station 19+25 the horizontal alignment will shift to the east by 3.5 feet and will continue along the same alignment until E. Dowling Road. The proposed profile for

Quinhagak Street will generally match the existing grade but will force a high point south of E. Dowling Road and increase the grades in this area to a minimum of 0.65%.

#### **D. Intersections:**

The existing stop signs within the project limits are proposed to remain as currently installed with stop control on E. 63<sup>rd</sup> Avenue, E. 64<sup>th</sup> Avenue, on the east side of Askeland Drive and on Quinhagak Street at E. Dowling Road.

#### **E. Traffic Calming**

Based upon the 85<sup>th</sup> percentile speeds and in coordination with the MOA Traffic Engineering Department, no traffic calming features are proposed for this project.

#### **F. Landscaping**

Since Quinhagak Street is a local road no specific landscaping is proposed as part of the project improvements.

#### **G. Drainage**

The preferred drainage design is the Alternative 3 single subdrain system and consists of the following drainage improvements:

- Replace the aging Quinhagak Street & Askeland Drive storm drain system to align with the new roadway improvements.
- Install a single subdrain down the center of Quinhagak Street to mitigate the effects of high groundwater.
- Install catch basins at roadway low points and other areas to alleviate ponding issues.
- Provide positive roadway drainage to minimize ponding.
- Provide water quality treatment for storm runoff.
- Extend footing drain services to property line of each parcel along the project corridor except for parcels that currently have on-site storm drain systems (Parcels 4, 5, & 12).

#### **H. Lighting**

A continuous LED lighting system, consistent with current MOA standards will be installed along the roadway. Power for the new lighting system will come from an existing Type 1A Load Center on E. 63rd Ave, east of the intersection with Quinhagak Street.

#### **I. Project Costs**

Following is a summary of estimated project costs for the entire project for the Alternative 3 preferred alternative:

*Summary of Estimated Project Costs*

<b>Category</b>	<b>Alternative 3 (preferred)</b>
Design & Management Total (estimated)	\$938,000
ROW Acquisition Total	\$21,000
Utility Relocation (15% Contingency) Total	\$757,000
<b><i>A. Design, ROW Acquisition, Utility Relocation</i></b>	<b><i>\$1,716,000</i></b>
<u>Construction</u>	
Roadway Improvements	\$2,417,000
Drainage Improvements	\$782,000
Illumination Improvements	\$216,000
<i>Construction Subtotal</i>	<i>\$3,415,000</i>
<i>Construction Contingency (15%)</i>	<i>\$512,000</i>
<i>Construction Management / Inspection / Testing</i>	<i>\$352,000</i>
<b><i>B. Total Estimated Construction Cost (rounded)</i></b>	<b><i>\$4,279,000</i></b>
<b><i>C. Overhead / Grant Accounting</i></b>	<b><i>\$1,058,000</i></b>
<b><i>Total Estimated Project Cost (A + B + C)</i></b>	<b><i>\$7,053,000</i></b>

## Table of Contents

I.	Introduction .....	1
A.	Project Purpose and Goals .....	1
B.	Project Approach .....	1
C.	Evaluation Factors.....	2
II.	Existing Conditions .....	4
A.	Previous Plans .....	4
B.	Planned Area Development .....	4
C.	Project Area Context .....	5
D.	Roadway Characteristics and Function .....	7
E.	Environmental Constraints .....	9
F.	Lighting.....	9
G.	Landscaping.....	9
H.	Utilities .....	9
I.	Right-of-Way (ROW) and Easements .....	11
J.	Nonconformities .....	11
III.	Existing Drainage Conditions & Analysis .....	13
A.	Existing Conditions.....	13
B.	Hydrologic and Hydraulic Analysis.....	17
IV.	Geotechnical Analysis .....	20
A.	Existing Conditions.....	20
B.	Recommendations .....	21
V.	Traffic and Safety Analysis .....	23
A.	Existing Traffic Volumes and Operations .....	23
B.	Traffic Volumes .....	23
C.	Traffic Characteristics.....	24
D.	Speeds .....	24
E.	Collision Data .....	25
F.	Side Street Intersections/Access Control.....	25
G.	Level of Service Analysis .....	26
H.	All-Way Stop Analysis.....	26
I.	Sight Distance Analysis.....	27
J.	Parking Study .....	28
K.	Traffic Calming .....	28

VI.	Design Criteria and Standards.....	29
A.	Project Design Standards .....	29
B.	Design Criteria Summary .....	29
C.	Specific Design Criteria.....	32
VII.	General Design Considerations .....	37
A.	Complete Streets .....	37
B.	Right-of-Way Acquisition .....	37
C.	Mailboxes.....	38
D.	Lighting.....	38
E.	Landscaping.....	40
VIII.	Roadway Design Alternatives.....	41
A.	Design Challenges .....	41
B.	Roadway Alternative Cross Sections.....	43
C.	Horizontal Alignment .....	45
D.	Vertical Alignment .....	45
E.	Posted Speed Limit.....	45
IX.	Drainage Improvements & Design Alternatives.....	46
A.	Hydrologic and Hydraulic Model Results .....	46
B.	Drainage Design Alternatives.....	47
C.	Proposed Drainage Improvements .....	49
X.	Right-of-Way Impacts.....	51
XI.	Utility Impacts .....	52
XII.	Permitting and Agency Approvals.....	53
XIII.	Quantity and Cost Estimates.....	54
XIV.	Stakeholder Coordination/Public Involvement.....	55
A.	Stakeholders .....	55
B.	Stakeholder Involvement Activities .....	55
C.	Project Website.....	57
D.	Project Questionnaire .....	57
E.	Agency Stakeholder Meeting .....	57
F.	Community Council Meetings.....	57
G.	Public Open Houses .....	57
H.	Summary of Public Comments Received .....	58
XV.	Recommended Improvements .....	59
A.	Roadway Cross Section .....	59

B.	Design and Posted Speed Limit.....	59
C.	Roadway Horizontal and Vertical Alignment .....	59
D.	Intersections: .....	59
E.	Traffic Calming .....	59
F.	Landscaping.....	60
G.	Drainage .....	60
H.	Lighting.....	60
XVI.	Proposed Variances from Design Criteria Manual .....	61
A.	AMC Title 21.....	61
B.	MOA DCM .....	61

## List of Figures

---

Figure 1 - Project Location & Vicinity Map .....	3
Figure 2 - Project Area Zoning.....	6
Figure 3 - Existing Storm Drain System Map.....	19
Figure 4 - Proposed Typical Sections .....	44

## List of Tables

---

Table 1 - Summary of Nonconforming Uses .....	12
Table 2 - Traffic Data Summary.....	23
Table 3 - AADT Traffic Data .....	24
Table 4 - Existing and Future Traffic Characteristics.....	24
Table 5 - Observed Speeds.....	25
Table 6 - Project Area Collision History: 2014-2021 .....	25
Table 7 – Quinhagak Street at E. 64 <sup>th</sup> Avenue All-Way Stop Analysis.....	27
Table 8 - Design Criteria Summary.....	30
Table 9 - Illuminance for Intersections (MOA DCM Table 5-5) .....	39
Table 10 - Estimated Right-of-Way Easements / Permits .....	51
Table 11 - Summary of Estimated Project Costs .....	54
Table 12 - List of Stakeholders .....	55
Table 13 - Stakeholder Coordination/Public Involvement Events .....	56

## Appendices

---

Appendix A:	Existing Utilities Drawings
Appendix B:	Roadway Plan & Profile Drawings
Appendix C:	Storm Drain Plan & Profile Drawings
Appendix D:	CCTV Pipeline Inspection Report from MOA Street Maintenance Department
Appendix E:	Storm Drain Modeling Data
Appendix F:	Geotechnical Report
Appendix G:	Traffic Data and Reports
Appendix H:	Easement Spreadsheets
Appendix I:	Intersection Departure Sight Triangles
Appendix J:	Project Cost Estimates
Appendix K:	Public Involvement
Appendix L:	Summary of Driveway Grades
Appendix M:	Business List
Appendix N:	Final Technical Memorandum
Appendix O:	Draft DSR Review Comments and Responses

## I. Introduction

The Municipality of Anchorage Project Management and Engineering Department (MOA PM&E) has contracted with CRW Engineering Group, Inc. (CRW) to provide professional services to develop and evaluate alternatives to upgrade Quinhagak Street from E. Dowling Road to Askeland Drive (see [FIGURE 1](#) for project location and vicinity map). Alternatives developed for analysis will follow Complete Streets design methodologies to balance corridor improvements for all users, including motorists, bicyclists, pedestrians, and persons with disabilities, while minimizing impacts to existing residences and businesses in the project area.

In addition to CRW, the project team includes Huddle AK (public involvement).

### A. Project Purpose and Goals

The purpose of the project is to upgrade Quinhagak Street from E. Dowling Road to Askeland Drive to meet current MOA Design Criteria for a local roadway. Quinhagak Street was constructed in 1983 and has reached the end of its useful life. The roadway conditions are very poor and include significant rutting, cracking, and heaving along the pavement and curb and gutters. These conditions result in ponding in the roadway, rough driving conditions, and frequent maintenance. The purpose of this project is to extend the life of the street by providing a stable roadway subgrade to correct the surface irregularities, improve drainage, and decrease maintenance.



*Poor roadway conditions along Quinhagak Street  
require regular attention from MOA Street Maintenance*

Improvements are expected to include the following new features:

- Roadway structural section
- Asphalt pavement and curbs and gutters
- Storm drain system infrastructure
- Pedestrian facilities
- Street lighting
- Signage

### B. Project Approach

Prior to beginning this Design Study Report (DSR), the project team submitted a Technical Memorandum to MOA PM&E, Street Maintenance Department, Traffic Engineering Department which outlined the conceptual roadway design elements. The Technical Memorandum intended to gain concurrence from the MOA Departments on the design elements before presenting the concepts to the public.

A meeting was held on September 9, 2022, with PM&E, Traffic Engineering, and Street Maintenance to discuss the conceptual roadway design elements. The Draft Technical Memorandum was submitted for their review and comment on October 13, 2022. The Draft Technical Memorandum was updated based upon review comments received. In coordination with PM&E, an additional typical section (Alternative 3) was included in the Final Technical Memorandum. The MOA Departments were notified of this additional typical section Alternative 3 on November 14, 2022, and were asked to provide comments on it or provide any outstanding review comments on the Draft Technical Memorandum by November 18, 2022. No comments regarding the Alternative 3 typical section were received. See [APPENDIX N](#) for the Final Technical Memorandum.

Following the Technical Memorandum and concurrence on the conceptual roadway design elements, the project team organized multiple meetings with the public to identify and document issues and concerns that could potentially be addressed as part of this project. A survey questionnaire was also previously assembled and sent out to the public to gather feedback. Public survey questionnaire and meetings included (see [SECTION XIV](#) for a full summary of Stakeholder Coordination/Public Involvement):

- Survey Questionnaire (mailed/emailed in June 2022)
- Community Council Meeting #1 (October 20, 2022)
- Public Open House #1 (November 3, 2022)

Comments from these meetings were used to identify project issues and concerns with improvements along the corridor. Documents and figures presented to the public and input and comments received from stakeholders can be found in [APPENDIX K](#).

### **C. Evaluation Factors**

The DSR will consider the following factors during the evaluation of improvements for the project corridor.

- Stakeholder input and needs
- Conditions of existing area
- Neighborhood connectivity
- Previous planning and design documents
- Traffic volumes and crash history
- Vehicle speeds and on-street parking
- Intersection and driveway sight distances
- Area drainage patterns and infrastructure
- Right-of-Way (ROW) restrictions
- Adjacent neighborhood and property owner impacts
- Utility relocation requirements
- Project costs




Figure 1 - Project Location & Vicinity Map

## **II. Existing Conditions**

Quinhagak Street is a local road that spans from E. Dowling Road (north) to Askeland Drive (south). The existing roadway abuts 14 parcels consisting of primarily industrial/commercial parcels from E. Dowling Road to E. 64<sup>th</sup> Avenue. Residential parcels extend from E. 64<sup>th</sup> Avenue to Askeland Drive.

### **A. Previous Plans**

#### **1) Anchorage 2040 Land Use Plan (MOA - 2017)**

The Anchorage 2040 Land Use Plan (2040 LUP) is a visual guide for growth and development in the Anchorage Bowl and is aligned with the visions and goals of the Anchorage 2020 Plan. The 2040 LUP incorporates the adopted neighborhood and district plans, public facility plans, and recent analysis into a land use amendment element of the Anchorage 2020 Plan. The 2040 LUP features policies and strategies and a land use plan map, which recommends future land development patterns and shows where land uses may occur within the Anchorage Bowl to accommodate future growth.

Map 1-2 in the 2040 Plan identifies the project area as an area of little growth. Specific policies from the 2040 Plan that are directly related to this project are listed below:

- Policy 6.2: Provide new or upgraded pedestrian and local/collector street connections in centers and commercial corridors to improve access to and from surrounding neighborhoods.
- Policy 6.3: Adopt and execute a Complete Streets policy to design streets to serve all users including pedestrians, transit riders, and bicyclists, and align the design and scale of streets to be compatible with compact, accessible, and walkable land use patterns.
- Policy 8.2: Provide new and improved trails, greenbelts, and other pedestrian facilities as alternative travel ways connecting open spaces, neighborhoods, and centers.

#### **2) Little Campbell Creek Watershed Plan (MOA – 2007)**

The Little Campbell Creek Watershed Plan was prepared to guide development in the Little Campbell Creek Watershed and recommends policies and objectives that are most beneficial to the whole watershed. General overall goals of the plan include improving water quality and managing the quantity of water discharged during storm events. No specific recommendations near/within the project area are included in the plan.

### **B. Planned Area Development**

No planned area development adjacent to the project limits is known currently.

## C. Project Area Context

### 1) Community Council

The project area is within the boundaries of the Abbott Loop Community Council (ALCC). The ALCC currently ranks the Quinhagak Street Reconstruction project as the fifth highest improvement project priority in their boundary limits.

### 2) Zoning and Land Use

Adjacent properties along Quinhagak Street from E. Dowling Road to E. 64th Avenue are zoned as Class A I-1 (Light Industrial). Adjacent industrial/commercial properties include a strip mall with multiple businesses, a church, a used car lot, fenced yards, and other businesses. There is one residential single-family parcel located mid-block along this segment, Parcel 15. Quinhagak Street from E. 64th Avenue to Askeland Drive is a local residential road, and the adjacent properties are zoned Class A R-5 (Low-Density Residential). Adjacent properties have mobile homes on the parcels. See [FIGURE 2](#) for area zoning.

- I-1 (Light Industrial) is intended primarily for public and private light and general manufacturing, processing, service, storage, wholesale, and distribution operations along with other uses that support and/or are compatible with industrial uses. Business-industrial parks and single-commodity bulk retail sales and building supply stores and services are allowed. Many commercial uses are also permitted and/or conditionally allowed, with some limitations on the more intensive customer retail, community service, and commercial employment establishments, to reduce land use and traffic conflicts, promote efficient use of industrial lands, and encourage the location of intensive commercial activities in commercial centers. This district is applied in areas designated as industrial/commercial by the comprehensive plan.
- R-5 (Mixed Residential) is intended primarily for single- and two-family residential areas with gross densities up to five dwelling units per acre. Mobile homes on individual lots are allowed in this district.

Future land use designations as outlined in the 2040 LUP along Quinhagak Street include “Light Industrial Commercial” from E. Dowling Road to E. 64<sup>th</sup> Avenue and “Single-Family and Two-Family” from E. 64<sup>th</sup> Avenue to Askeland Drive.

- Light Industrial Commercial - This area provides for multi-sector employment in an industrial setting. It gives priority to light industrial production distribution and repair (PDR) uses.
- Single-Family and Two-Family - This designation provides for a variety of low-density urban/suburban residential neighborhoods. Most areas have well-developed infrastructure, public water and sewer, and municipal services.




Figure 2 - Project Area Zoning

### 3) Schools

Project area students are within the following Anchorage School District (ASD) boundaries:

- Tudor Elementary School
- Wendler Middle School
- East High School

The following ASD alternative schools are within 0.35 miles of the project limits:

- Northern Lights ABC School K-8 is located at the southeast corner of the E. Dowling Road and Lake Otis Parkway intersection.
- Rilke Schule German Charter School of Arts & Sciences is located east of Meadow Street and south of E. 64<sup>th</sup> Avenue.
- Polaris K-12 School is located north of E. 64<sup>th</sup> Avenue at the far west end of E. 64<sup>th</sup> Avenue before the Seward Highway.

Transportation is typically provided by ASD for students who live more than 1.5 miles from their neighborhood school. Students who live within 1.5 miles of their neighborhood school are within the designated walking boundary; although, other factors also influence if a safe walking route to school can be established, such as street crossing requirements, presence of pedestrian facilities, maintenance of pedestrian facilities, lighting, etc.

The project area is outside of the designated walking boundary for all the non-alternative ASD schools listed above. No published walking routes are provided for the ASD alternative schools listed above. Based upon feedback from residents, many parents drop off/pick up their children at the Rilke Schule Charter School and at the Polaris K-12 School.

There are no ASD bus stops within the project limits.

### 4) Public and Religious Institutions

There are no public institutions within the project limits. Faith Presbyterian Church (Parcel 1) is located as the southeast quadrant of the Quinhagak Street and E. Dowling Road intersection.

### 5) Businesses

There are several businesses within the project limits. A list of businesses is included in APPENDIX M.

## D. Roadway Characteristics and Function

### 1) Facility Description

Quinhagak Street is a local road that spans 1,470 feet from E. Dowling Road (north) to Askeland Drive (south). There are four side streets within the project corridor, inclusive of E. Dowling Road and Askeland Drive. Of these, three are three-way intersections (E. Dowling Road, E. 63rd Avenue, and Askeland Drive) and one is a four-way intersection (E. 64th Avenue). Stop signs are

located on E. 63rd Avenue, on E. 64th Avenue, on the east side of Askeland Drive, and on Quinhagak Street at E. Dowling Road.

Quinhagak Street is approximately 36 feet wide measured to back of curb (32 feet of pavement). Type 2 (rolled) curb and gutter is installed along the entire length of the project limits except for a short section (approximately 90 feet) of Type 1 (barrier) curb & gutter is installed south of E. Dowling Road. On-street parking is allowed throughout the project limits even though space is limited in some locations due to some full frontage driveways. The posted road speed limit is 25 miles per hour (mph).

The existing roadway grades in the project area are moderate, between approximately 1%-4% except for just south of E. Dowling Road where the grades are very flat, between 0.1%-0.6%. The roadway is generally graded to drain from north to south but there is a forced low point located approximately 600 feet south of E. Dowling Road.

## **2) Roadway Functional Classification**

The functional classification affects the basic design criteria including design speed, number of lanes, lane and shoulder width, right-of-way (ROW) width, distance between intersections, and alignment. The most current version of the Official Streets & Highways Plan (OS&HP) lists Quinhagak Street as a local road. Per the MOA Design Criteria Manual (DCM) Quinhagak Street is a secondary (local) industrial/commercial street from E. Dowling Road to E. 64<sup>th</sup> Avenue and a secondary (local) urban residential street from E. 64<sup>th</sup> Avenue to Askeland Drive.

## **3) Pedestrian and Bicyclist Facilities**

There are no pedestrian or bicyclist facilities present along Quinhagak Street. There is an approximately 8.5-foot-wide asphalt pathway that runs east-west on the south side of E. Dowling Road that crosses Quinhagak Street.

## **4) Condition of Facilities**

The existing conditions of the roadway pavement along the project alignment includes significant pavement degradation including transverse and longitudinal asphalt cracks and potholes. Pavement repairs are present in multiple locations along the alignment and the roadway requires routine maintenance. Many of the existing curbs are heaving which doesn't allow surface drainage to effectively drain, and during spring break up or large rain events these areas form large ponds in the roadway.



*Flat grades & heaved curbs result in ponding at the Quinhagak Street & E. 63<sup>rd</sup> Avenue intersection*



*Significant pavement degradation with recent repairs along Quinhagak Street*

## **E. Environmental Constraints**

### **1) Wetlands/Creeks/Flood Plain**

There are no mapped wetlands, creeks, flood plains or other water bodies along the project corridor based on MOA Watershed Management Services (WMS) Wetland Mapping data.

### **2) Contaminated Sites**

According to the Alaska Department of Environmental Conservation (ADEC) Contaminated Sites Program Database, there are no active contaminated sites within 500 feet of the project area. The nearest active contaminated site is located at the northeast quadrant of the E. Dowling Road and Lake Otis Parkway intersection and is approximately 1,000 feet from the project area.

## **F. Lighting**

The only two MOA-owned roadway lights near Quinhagak Street are on the east side at the intersections of E. 64th Avenue and Askeland Drive but there are no roadway lights directly on Quinhagak Street. The Alaska Department of Transportation (ADOT) owns roadway lights on the north side of E. Dowling Road.

## **G. Landscaping**

The landscaping along Quinhagak Street generally consists of owner maintained lawn areas and natural mature trees. A privately owned landscaping bed west of Parcel 1 and some boulders west of Parcel 6 extend into the right-of-way (ROW). Multiple parcels (Parcels 4, 5, and 12) have landscaping beds and trees that are installed up to the ROW and a few of the landscaping beds slightly extend into the ROW.

## **H. Utilities**

Existing utilities within the project area include water, sanitary sewer, storm drain, electric, telephone, cable television, fiber optic, and natural gas (See [APPENDIX A](#) for the layout, size, and type of existing utilities in the project area). The location of utilities in the project planning documents and drawings are based on utility company facility maps and utility company locates.

## **1) Water**

The project area is primarily served by a public piped water system owned and operated by Anchorage Water & Wastewater Utility (AWWU). The water main along Quinhagak Street is 12 inches in diameter, ductile iron (DI) pipe from Askeland Drive to E. 63<sup>rd</sup> Avenue. An 8-inch DI water main extends from the E. 64<sup>th</sup> Avenue & Quinhagak Street intersection to E. Dowling Road. Water mains are present at all the side streets and T-intersections within the project area. The depth of the burial of the water mains on Quinhagak Street are generally 8-10 feet below ground surface. Water service lines, hydrants, valves, key boxes, and other water appurtenances are located throughout the project area. AWWU has not indicated any water improvement plans within the project area.

The only parcel served by a private well is Parcel 15.

## **2) Sanitary Sewer**

The project area is also served by a public piped sanitary sewer system owned and operated by AWWU. The gravity sanitary sewer main along Quinhagak Street is 8 inches in diameter and made of DI pipe. It extends from Askeland Drive to approximately 130 feet south of E. Dowling Road. Sanitary sewer mains are present at all the side streets and T-intersections within the project area. Sanitary sewer service lines, manholes, and other appurtenances are present throughout the project area. AWWU has not indicated any sewer improvement plans within the project area.

## **3) Storm Drain**

See SECTION III: EXISTING DRAINAGE CONDITIONS & ANALYSIS for summary of the existing storm drain facilities in the project area.

## **4) Electric**

Chugach Electric Association (CEA) owns and operates overhead (OH) and underground (UG) electric lines, junction boxes, padmount transformers, and utility poles in the project area. An OH 3-phase electric line crosses Quinhagak Street on the south side of E. 64<sup>th</sup> Avenue. An UG 3-phase 4 wire primary conductor is located on the east side of Quinhagak Street from the north side of Parcel 4 to just south of E. Dowling Road where it crosses Quinhagak Street and extends to the west. A padmount transformer along this UG segment is located south of Parcel 1. Transmission OH lines cross Quinhagak Street on the south side of E. Dowling Road. CEA has not indicated any future extension or improvement plans within the project area.

## **5) Telephone**

Alaska Communications (ACS) owns and operates OH and UG telephone and fiber optic lines in the project area. ACS has an OH telephone line crossing Quinhagak Street on the south side of E. 64<sup>th</sup> Avenue and an UG telephone line crossing on the north side of E. 64<sup>th</sup> Avenue. ACS has UG telephone and fiber optic lines that cross Quinhagak Street on the south side of E. Dowling Road. ACS serves most properties along Quinhagak Street from OH and UG lines along the back side of the properties. ACS has not indicated any future extension or improvement plans within

the project area. ACS has not indicated any future extension or improvement plans within the project area.

#### **6) Cable Television**

General Communications, Inc. (GCI) owns and operates UG and OH cable television (cable) and fiber optic lines, underground vaults and pedestals within the project area. An UG cable line is installed on the east side of Quinhagak Street from Askeland Drive to E. 63<sup>rd</sup> Avenue. Multiple UG cable lines are installed on the west side of Quinhagak Street from E. 64<sup>th</sup> Avenue to E. Dowling Road. GCI's lines cross Quinhagak Street as follows: UG & OH cable crossing on the south side of E. 64<sup>th</sup> Avenue and OH cable/fiber optic crossing on the south side of E. Dowling Road. GCI serves some properties along Quinhagak Street along the back side of the properties. GCI has not indicated any future extension or improvement plans within the project area.

#### **7) Natural Gas**

ENSTAR Natural Gas (ENSTAR) owns and operates natural gas facilities within the project area. Natural gas mains along Quinhagak Street include 2-inch diameter plastic mains extending from Askeland Drive to E. 64<sup>th</sup> Avenue on the west side and from E. 63<sup>rd</sup> Avenue to E. Dowling Road on the east side. Numerous services cross Quinhagak Street providing natural gas service to parcels along the project area. A 12-inch diameter pressurized transmission gas main crosses Quinhagak Street on the north side of E. 64<sup>th</sup> Avenue. ENSTAR has not indicated any future extension or improvement plans within the project area.

### **I. Right-of-Way (ROW) and Easements**

The existing ROW for Quinhagak Street is 60 feet wide. Existing easements on private properties vary in width and include: telephone and electric, visual enhancement, aerial telecommunication and electric, anchor, and utility.

### **J. Nonconformities**

MOA Code of Ordinances Title 21.13 defines “nonconformities” as legal uses, structures, lots, or signs established prior to the effective date of the current title, or future amendments to the current title, that don't conform to the requirements of the current title. The acknowledgement and relief granted to existing property, land uses, and structures are intended to minimize negative economic effects on development that was lawfully established prior to the current title. In all cases, the burden of establishing the existence of a legal nonconformity is solely the responsibility of the owner of the nonconformity. Verification of nonconforming status can be requested by the owner or on behalf of the owner by submitting a Nonconforming Determination application along with supporting documentation to the MOA Planning Department for a determination.

Improvements made to the structure or lot that require a permit from MOA Building Safety may require dedicating a portion of the construction cost to bring the affected areas towards compliance with current codes. However, if improvements do not require a permit, the area is not subject to upgrading to current standards. For example, per current code, improvements to lots that place fills

(including pavement) less than 1 foot in depth, on natural terrain with a slope flatter than 5H:1V, and do not obstruct drainage courses do not require a building safety permit.

One parcel along the project corridor has previously established nonconforming status. TABLE 1 below provides a summary of the parcel and the relevant nonconformities (see FIGURE 1 for the location of the parcel). This parcel and potentially other parcels along the project limits may have additional nonconforming features associated with the lots that have not yet established nonconforming status, including:

- Driveway widths exceed two-fifths of the frontage of the lot.
- Parking and maneuvering not entirely located on property.
- Vehicles not able to enter abutting street in forward.

Depending on the preferred design, these additional nonconformities may need to be established to construct the proposed project improvements and not negatively impact current development. Since the MOA is making improvements to the ROW with this project, the project team will work with the owners of the lots to gain approval from them to submit a Nonconforming Determination application on their part if required. The MOA Planning Department will review the application and determine whether a property has valid nonconformities. Once the nonconforming uses have been established, the design team will work with the MOA Traffic Engineering Department to provide the safest possible roadway design.

*Table 1 - Summary of Nonconforming Uses*

Parcel No.	Year of Nonconforming Status Determination	Nonconformity
11	2019	<ul style="list-style-type: none"><li>• The driveway entrance at Quinhagak Street is in excess of 40% of the lot's frontage is considered conforming.</li><li>• The lack of parking lot perimeter and site enhancement landscaping is considered conforming.</li></ul>

### III. Existing Drainage Conditions & Analysis

Several piped storm drain systems have been installed along the project corridor and connecting side streets. However, much of the existing drainage infrastructure is ineffective due to the poor condition of the road, grades, and curb and gutter. High groundwater levels and seasonal freezing have also created several roadway issues within the project area including widespread cracking, ponding, and potholes resulting in deteriorating roadway surfaces. Additionally, most of the piped systems in place were installed in the 1980s and are nearing the end of their design life. One of the primary goals of this project is to help mitigate the effects of the high groundwater issues. These improvements, along with upgrades to improve surface drainage, will extend the life of the proposed road and pedestrian improvements.

There are two (piped) storm drain subsystems located within the project limits; herein referred to as the Quinhagak Street system, which is a part of the E. 64<sup>th</sup> Avenue system and the Askeland Drive system, all of which are part of the greater Meadow Street Park System that outfalls into North Fork Little Campbell Creek in Meadow Street Park. These two systems convey stormwater runoff from the project corridor and surrounding areas and will be discussed in further detail below.



To properly evaluate the infrastructure currently in place, an assessment of the existing storm drain piping was conducted for specific pipe runs in the project area to determine its overall condition. Additionally, a hydrologic and hydraulic analysis was performed to determine if the existing piping is adequately sized to meet current MOA design criteria.

*Widespread ponding & ineffective catch basin at the Quinhagak Street and E. 64<sup>th</sup> Avenue intersection*

The information gathered from the condition assessment and the drainage analysis will be used to develop the proposed storm drain system. The proposed drainage improvements are discussed in SECTION IX.

#### A. Existing Conditions

##### 1) Contributing Drainage Areas

The drainage basins (catchments) that contribute stormwater runoff to the project area were delineated using several methods, including topographical mapping, aerial photography, parcel boundaries, and MOA Watershed Management's hydrography geodatabase (HGDB). Based on HGDB data, the project is contained within the Lower North Fork Little Campbell Creek sub-watershed boundary. Refer to FIGURE 1, APPENDIX E which illustrates the project location and watershed boundaries within the Anchorage area.

The larger scale sub-watershed identified from HGDB mapping was refined into individual drainage catchments near the project area to more accurately represent the surface drainage and hydraulic properties anticipated within the project corridor. Sixteen catchments were delineated for the existing conditions assessment of the E. 64<sup>th</sup> Avenue and Askeland Drive systems. See [FIGURE 4, APPENDIX E](#) for the refined catchment areas.

The contributing catchments are characterized primarily by light industrial/commercial properties along Quinhagak Street with low density residential south of E. 64<sup>th</sup> Avenue (approximately ¼ acre lots). The industrial/commercial areas increase the impervious surface area (roofs, driveways, and parking lots) throughout the project area, resulting in increased runoff. The majority of stormwater runoff from these catchments is generally directed toward the adjacent roadways, where it is conveyed by predominantly Type 2 (rolled) curb and gutter to the piped storm drain systems. These conveyance systems are described in more detail below.

## **2) Storm Drain Conveyance Systems**

The following provides a description of the existing storm drain conveyance systems within the project area and systems adjacent to the project area that influence drainage. The drainage systems described below are owned and maintained by MOA or the Alaska Department of Transportation and Public Facilities (DOT&PF). All drainage systems described below south of E. Dowling Road are owned by the MOA. See [FIGURE 3](#) below for an Existing Storm Drain System Map.

### **a) Quinhagak Street System**

The Quinhagak Street branch of the E. 64<sup>th</sup> Avenue storm drain system (described below) extends north from the E. 64<sup>th</sup> Avenue/Quinhagak Street intersection and terminates approximately 375 feet south of E. Dowling Road. Surface runoff from the properties adjacent to Quinhagak Street, E. 63<sup>rd</sup> Avenue, Tuttle Place, and a short segment of Lake Otis Parkway are all conveyed through the Quinhagak Street storm drain and into the E. 64<sup>th</sup> Avenue system. The Quinhagak Street storm drain was installed in 1983 and consists of a 12-inch corrugated metal pipe (CMP) main line, with 10-inch CMP catch basin leads. A newer section of storm drain was installed along E. 63<sup>rd</sup> Avenue that extends approximately 350 feet east of the Quinhagak Street/E. 63<sup>rd</sup> Avenue intersection (installation date unknown). The E. 63<sup>rd</sup> Avenue storm drain consists of an 18-inch corrugated polyethylene pipe (CPEP) main line with a 12-inch CPEP connection that appears to serve a private property to the north. Other private storm drain systems connect to storm drain structures on Quinhagak Street.

Surface flow is generally conveyed by curb and gutter (predominantly Type 2) from north to south along Quinhagak Street and east to west along E. 63<sup>rd</sup> Avenue. Catch basin inlets are located within the curb and gutter to intercept the stormwater runoff and direct it into the piped systems described above. The furthest extents of surface runoff captured within the Quinhagak Street system are from the north end of Tuttle Place and Lake Otis Parkway north of E. 63<sup>rd</sup> Avenue.

b) Askeland Drive System

The project corridor includes a segment of the upstream end of the Askeland Drive storm drain system. The existing storm drain network within the project area collects flows from Quinhagak Street south of E. 64<sup>th</sup> Avenue and the adjacent residential homes. Runoff is collected via curb and gutter and directs flow southwest towards the system outfall. There is a Type I storm drain manhole in the center of the Quinhagak Street/Askeland Drive intersection that is connected to two 10-inch CMP catch basin leads and an 18-inch CMP main line that extends west along Askeland Drive. There is also an existing 10-inch CMP subdrain and cleanout installed in the cul-de-sac east of the project that is connected to the same manhole.

c) E. 64<sup>th</sup> Avenue System

The E. 64<sup>th</sup> Avenue storm drain system is extensive and located entirely outside of the project corridor except for the infrastructure at the intersection of Quinhagak Street. It was constructed in the late 1980s and extends underground from its confluence with the Askeland Drive system north of Meadow Street Park (25 feet upstream of the OGS inlet) to the north to E. 64<sup>th</sup> Avenue. From there it continues east along E. 64<sup>th</sup> Avenue to Lake Otis Parkway, collecting flows from E. 64<sup>th</sup> Avenue, Burlwood Street (with connecting systems from E. Dowling Road, Dow Place, E. 59<sup>th</sup> Avenue, and Petersburg Street north of E. Dowling Road), Petersburg Street south of E. Dowling Road, and Quinhagak Street. Once the system reaches Lake Otis Parkway, it splits north and south, extending approximately 3,700 feet to the north and 900 feet to the south along Lake Otis Parkway with several connecting sub-systems.

Upstream of Quinhagak Street, the primary trunk lines are constructed of 36- and 42-inch CMP. Downstream of Quinhagak Street, the trunk line is constructed of 57-inch (span) by 38-inch (rise) corrugated metal pipe arch (CMPA) and 64-inch (span) by 43-inch (rise) CMPA.

### **3) Water Quality Treatment**

Based on available storm drain record drawings, survey, and HGDB data, water quality treatment is not being provided for the Quinhagak Street or Askeland Drive systems directly. However, treatment is provided downstream on a broader level by an OGS located directly upstream of two large sedimentation basins north of Meadow Street Park. The OGS serves as pre-treatment for runoff prior to discharging into the interconnected sedimentation basins. Sedimentation basins are designed to detain sediment-laden stormwater runoff, allowing sediment to settle out before the runoff exits the facility. Runoff within the sedimentation basins eventually flows into North Fork Little Campbell Creek.

### **4) Storm Drain Condition Assessment**

In September 2022, MOA Street Maintenance inspected segments of the existing storm drain system using a closed-circuit television (CCTV) camera along E. 63<sup>rd</sup> Avenue, E. 64<sup>th</sup> Avenue, and

Askeland Drive. For the complete CCTV Pipeline Inspection Report provided by MOA Street Maintenance, refer to [APPENDIX D](#). Below is a summary of the inspection findings.

Two CPEP pipes (MOA ID #3890 & 38981) were inspected along E. 63<sup>rd</sup> Avenue. These pipes appeared to be in fair to good condition. Minor joint infiltration and pipe deformation were noted at multiple locations.

Two CMP pipes (MOA ID #26756 & 33051) were inspected along E. 64<sup>th</sup> Avenue. These pipes appeared to be in good condition, with noted joint separations, light infiltration, and pipe deformation in several locations. One of the joint separations is in the flow line obstructing flow.

Three CMP pipes (MOA ID #10529, 19737 & 26454) were inspected along Askeland Drive. Each inspection attempt was abandoned due to the presence of heavy deposits and sediments in each pipe, prohibiting the inspection equipment from advancing. A broken/separated pipe joint in pipe 10529 was identified with soil visible and entering the pipe.

It was also noted in the report that the pipes downstream of those inspected were visibly surcharged during a surface manhole assessment done previously, and that the further you proceeded downstream the more surcharged the system was.

## 5) Drainage Concerns

Significant ponding occurs throughout the project limits after rain events and spring break up due to flat grades and heaving curb and gutter. Runoff cannot effectively drain to the existing curb inlets along the roadway in these conditions, resulting in roadway degradation such as potholes, cracking, and pavement failure over time. In addition to the roadway surface issues, the groundwater in the project area is high. High groundwater causes seasonal freeze/thaw issues in the roadway subbase that exacerbates the issues listed above.



*Heaving curb & gutter and ponding along Quinhagak Street (looking south)*

The CCTV Pipeline Inspection Report ([APPENDIX D](#)) prepared by MOA Street Maintenance identified several issues with the pipes inspected. This was anticipated as most of the pipe and connecting storm drain structures in the project limits were installed in the 1980s and are nearing the end of its design life. In addition to the aging infrastructure, the existing E. 64<sup>th</sup> Avenue and Askeland Drive systems have a history of surcharging and/or are influenced by backwater, and these conditions worsen as you proceed further downstream as noted above. The surcharging/backwater conditions were confirmed in some of the images and notes provided in the Street Maintenance report.

## B. Hydrologic and Hydraulic Analysis

A hydrologic and hydraulic (drainage) model was developed to analyze the existing and proposed conditions for the project corridor and contributing areas. The methodology and key input parameters required to prepare this drainage model are described below.

### 1) Design Storm Depth and Distribution

The design storm distribution used for this drainage analysis is based on the Anchorage and Eagle River 24-hour storm duration provided in Appendix D of the Anchorage Stormwater Manual (ASM). The base design storm depth values are per ASM Table 4.2-1 (MOA Design Storm Depths) and are as follows:

- Water Quality Treatment: 90th Percentile, 24-hour – 0.52-inches.
- Conveyance Design and Peak Flow Control: 10-year, 24-hour – 2.28-inches.
- Project Flood Bypass: 100-year, 24-hour – 3.59-inches.

The 10-year, 24-hour design storm event was used to evaluate the conveyance capacity of the existing storm drain systems and if they are adequately sized. The proposed storm drain system will utilize the same storm event to size the piped system.

### 2) Orographic Factor

The mountainous geography around the Anchorage Bowl has a pronounced and generally predictable impact on the precipitation amounts along the mountain fronts. Generally speaking, the closer you are to mountainous terrain, the more precipitation is predicted. This is known as the orographic effect. To account for this from a hydrologic standpoint, an orographic factor is applied to the base design storm values listed above based on the location of the project area to account for the increased intensity.

Based on project location, a *1.08 orographic factor* was applied to the base design storm volumes. Refer to [FIGURE 3](#), [APPENDIX E](#).

### 3) Model Information

The Soil Conservation Service (SCS) TR-55 method was used for this drainage analysis. The drainage analysis was developed using 2023 Autodesk Storm and Sanitary Analysis (SSA) computer software. This software allows the user to analyze the stormwater runoff response from the project area and calculate data such as peak flow at specific (design) points in the system, evaluate pipe sizing, and identify problem areas such as flooding and surcharged pipes.

Precipitation losses were estimated using the SCS Curve Numbers based on land cover type, slope, and the hydrologic soil group for the project area. *Soil Type B* was used for this drainage analysis based on Web Soil Survey (WSS) mapping developed by the United States Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS). Refer to [FIGURE 2](#), [APPENDIX E](#) for a map showing the project area and the soil groups in the surrounding area.

The time of concentration ( $T_c$ ) was calculated for each contributing catchment using the SCS TR-55 method. Time of concentration is defined as the time for runoff to travel from the hydraulically most distant point of the watershed to a design point or point of interest.

The input parameters for the existing storm drain piping systems included in the model were based on surveyed data, record drawings, and information from the condition assessment report. These parameters included information like pipe size, type, inverts, and slopes.

#### **4) Model Results**

A total of 16 contributing catchments were delineated and evaluated for runoff response for the existing condition drainage model. These catchments were delineated based on the inlet structures that surface runoff will be conveyed to. The peak stormwater runoff of each catchment and the peak discharge leaving the project corridor (at specific locations) during the 10-year, 24-hour design storm event is shown on [FIGURE 4, APPENDIX E](#).

The drainage model results indicate that the existing storm drain is adequately sized on Askeland Drive and is undersized in numerous locations along Quinhagak Street. The entire Quinhagak Street system surcharges during the design storm event and backwaters into the E. 63<sup>rd</sup> Avenue system causing the E. 63<sup>rd</sup> Avenue system to also surcharge. Surcharged pipes are identified in [FIGURE 4, APPENDIX E](#). Peak flows during the simulated storm cause pipes to surcharge and manholes to overtop, flowing into the roadway at select locations.

The SSA software does not account for the peak flows associated with the overtopping conditions described above and therefore makes it appear that the peak flows in each piped system are relatively low. While this is true to a point, in that the surcharged pipes have exceeded their design capacity and will allow no additional flow through, the overtopping flows will continue to flow down gradient to the next available inlet, conveyance, or low-lying area, potentially inundating that system or area as well. These conditions should be considered when comparing the existing system capacity with the proposed system capacity.

It should be noted that the E. 64<sup>th</sup> Avenue system and the Askeland Drive system were not modeled except for catchments within the project area due to the limited scope of this analysis. As such, the effects of any potential backwater and/or surcharge of these systems was not incorporated into the drainage model. While these effects are unknown, it is likely that this would negatively impact the Quinhagak Street and E. 63<sup>rd</sup> Avenue systems, compounding the surcharging and overtopping issues identified in these systems during peak storm events.

Complete drainage modeling results and input parameters for the existing drainage systems and contributing areas described above are provided in [APPENDIX E](#). For reference, the naming convention used for the storm drain pipes and structures in this modeling analysis uses the identification numbers as presented in the MOA Stormwater Asset online GIS mapping tool.




Figure 3 - Existing Storm Drain System Map

## IV. Geotechnical Analysis

### A. Existing Conditions

CRW conducted a geotechnical investigation for the Quinhagak Street Reconstruction project, which consisted of reviewing existing historic borehole logs and completing a field investigation in the project area.

#### 1) Historic Bore Logs

CRW consulted the online MOA Soil Boring App to evaluate historical borings in the project area. Fourteen historic boreholes were in the project limits. Historical boreholes generally matched information obtained in our field investigation. This included a 2 to 5-foot layer of granular fill, followed by a section of silty sand and clayey silt.

#### 2) CRW Field Investigation

CRW's geotechnical field investigation was conducted in May 2022; the Final Geotechnical Report was published in January 2023 and can be found in [APPENDIX E](#). The investigation included drilling and sampling six borings along Quinhagak Street. Three piezometers were installed to monitor groundwater levels.

Based on the recovered samples, the existing pavement along Quinhagak Street when encountered ranged from 1.5 to 3.0 inches. The subsurface conditions observed within the existing road prism generally consisted of 5 to 6 feet of granular fill composed of poorly graded gravel with sand and silt or poorly graded sand with gravel and silt, decreasing in thickness from north to south. The granular fill was underlain by up to 4 feet of silty sand or sand with silt, decreasing in thickness from north to south and was not observed in BH-06. Beneath the granular fill layer, 6 to 10 feet of silty lean clay was observed increasing in thickness from north to south.

The fines content ranged between 2 and 10 percent in the granular fill, and its frost susceptibility was estimated to be non-frost susceptible (NFS) to class F-2. The silty sand/sand with silt had fines content from 20 to 50 percent and the silty lean clay had fines content of 90 to 100 percent and was estimated to be frost class F-4.

The groundwater table was observed during drilling at depths ranging from 1 to 10 feet below ground surface (BGS), with one boring not encountering groundwater. Subsequent groundwater measurements varied between 2 to 5.6 feet BGS.

Photoionization detector (PID) readings were collected for each sample during the field investigation per the DCM to screen for potential contaminants. Standard practice in the MOA is to consider soil samples with PID readings of 20 parts per million (ppm) or higher potentially contaminated. No samples screened during this investigation exceeded this limit, and no visual or olfactory evidence of contamination was observed.

See the Geotechnical Report for detailed soil boring and laboratory testing information.

## B. Recommendations

CRW has developed a recommended road structural section based on the current MOA DCM as outlined in Chapter 1 Streets, Section 1.10 Road Structural Fill Design. The DCM recommends two methods for frost considerations in the structural section design: the Complete Protection Method and the Limited Subgrade Frost Penetration Method. The structural section design uses the latter method, which seeks to reduce the freezing impacts to a specified percentage of the structural section into the subgrade.

The analysis uses the default Anchorage climate parameters with typical soil parameters for classified fill and native soils. The recommended structural section is shown in FIGURE 4 in SECTION VIII as follows:

- 2 inches of asphalt concrete pavement (Class E)
- 2 inches of leveling course
- 16 inches of MOA Type II-A classified material
- 2 inches of rigid board insulation (R-4.5 per inch minimum)
- 24 inches of MOA Type II classified material
- Separation geotextile

The thickness of the recommended section totals 46 inches.

During the Draft DSR it was determined that an additional 2 inches of asphalt concrete pavement should be installed due to the significant amount of truck traffic along Quinhagak Street. The revised structural section is as follows and still totals to 46 inches:

- **2 inches of asphalt concrete pavement (Class D)**
- 2 inches of asphalt concrete pavement (Class E)
- 2 inches of leveling course
- 16 inches of MOA Type II-A classified material
- 2 inches of rigid board insulation (R-4.5 per inch minimum)
- **22 inches of MOA Type II classified material**
- Separation geotextile

Board insulation is recommended to extend a minimum of 4 feet beyond the back of the curb when no sidewalk is present. When sidewalk is present, the insulation should extend one foot minimum beyond the back of the sidewalks; however, the sidewalk will not perform as well as the curb.

Longitudinal transitions between insulated and non-insulated sections should include extending the insulation 8 to 12 feet into the non-insulated section, reducing the insulation thickness along the extension to minimize the possibility of differential heave. The insulation can be tapered from an R-value of 9 to an R-value of 4.5 in the transition zone. The subgrade transition should be tapered at a 10 horizontal to 1 vertical (H:V) slope, if construction distances permit, but should not be steeper than 5H:1V.

A geotextile should be used for separation between the structural section and the existing subgrade. Geotextile should be placed on top of the existing soils prior to placement of classified fill and insulation and extended up the sides of the excavation.

Any existing fill that meets MOA Type II and Type II-A classified fill gradations can be reused as classified fill in the roadway structural section. It is anticipated that the majority of existing fill and native soils along Quinhagak Street contain frost susceptible material and will not meet MOA Type II and II-A classification.

Incorporation of subdrains into the design of the structural section is recommended to help mitigate against the effects of high ground water levels. High groundwater levels, or groundwater that reaches the pavement structural section, can collect in the structural section and impact the overall road performance. Subdrains will mitigate against water infiltration in the structural section and improve overall road performance. The depth of subdrain installation should be below the roadway structural section for optimal performance.

Edge drains should be placed at the outer edges of the structural section as shown in FIGURE 4 in SECTION VIII and consist of a geotextile wrapped perforated pipe with a minimum O.D. of 10 inches. Construction should be per MASS. Roadway subgrade should be sloped with a minimum of 2 percent towards subdrains to assist with drainage. Termination of the subdrains should be to the drainage system manholes or suitable outfalls. Subdrains should be hydraulically sized and consider potential icing issues.

Should edge drains not be feasible or to save construction costs, an alternate would be a perforated drain placed in a shallow trench near the center of the structural section. As such, an alternate drainage option is a perforated center subdrain as shown in FIGURE 3 in APPENDIX F consisting of a geotextile-wrapped perforated pipe with a minimum O.D. of 18 inches. The use of a center subdrain may result in poorer structural section performance over time compared to the used of edge drains. The center subdrain should be constructed per MASS. Roadway subgrade should be sloped with a minimum of 2 percent towards the subdrain to assist with drainage. Termination of the subdrain should be to the drainage system manholes or suitable outfalls. Subdrains should be hydraulic sized and consider potential icing issues.

For the driven pile light pole foundations, they should be installed to a minimum of 25 feet BGS due to the presence of fine-grained soils starting around 10 feet BGS.

## V. Traffic and Safety Analysis

### A. Existing Traffic Volumes and Operations

Existing traffic data was gathered from the MOA for the project area. Additionally, new traffic data was gathered by CRW and MOA during development of the Draft DSR. The following table summarizes traffic data used for this study, see [APPENDIX G](#) for the detailed traffic data.

*Table 2 - Traffic Data Summary*

Location	Date	Speed	Volume (Link counts)	Intersection Volume
Quinhagak Street and E. Dowling Road	8/10/2016			X
*Quinhagak Street North of E. 64 <sup>th</sup> Avenue	7/14/2022 -7/19/2022	X	X	
Quinhagak Street and E. 64 <sup>th</sup> Avenue	11/17/2022			X

\*E. Dowling Road at Seward Highway was in construction during speed/volume study which may have skewed traffic data.

### B. Traffic Volumes

The existing annual average daily traffic (AADT) volume was determined using the volume data (link counts) taken during November of 2022. Seasonal adjustments were factored into the AADT using the nearest permanent Alaska Department of Transportation and Public Facilities (ADOT&PF) traffic recorder located on Lake Otis Parkway at E. 74<sup>th</sup> Avenue.

The Anchorage Metropolitan Area Transportation Solutions (AMATS) travel demand model includes forecasted future daily traffic volumes for higher volume roadways. The model does not include future traffic volumes for Quinhagak Street. Although much of the project area is built out, traffic volumes on the roadways are anticipated to increase slightly as the local population grows. Much of the traffic on these roadways is destination based and will increase as the population rises. There are undeveloped parcels (Parcels 2, 13, and 14) that, when developed, are also expected to contribute to the projected traffic volumes (See [FIGURE 1](#) for parcel numbers). Local population rates were obtained from the Anchorage 2040 Land Use Plan which estimates population growth between 0.3% and 1.1% with a 0.8% annual growth rate. A 0.8% growth rate was used to determine traffic volumes in the anticipated construction year (2026) and the design year (2046).

The following table summarizes AADT for Quinhagak Street.

*Table 3 - AADT Traffic Data*

Roadway	2026 Daily Traffic Volumes <sup>1</sup>	2046 Projected Daily Traffic Volumes <sup>1</sup>
Quinhagak Street	1536	1802

1. Annual Growth Rate of 0.8% Source: Anchorage Land Use Plan 2040.

### C. Traffic Characteristics

Quinhagak Street exhibits different traffic characteristics in the project area and has been separated into two separate segments for traffic analysis as follows:

- 1) **E. Dowling Road to E. 64<sup>th</sup> Avenue** is primarily industrial/commercial, and most parcels are built out or being utilized except Parcels 2, 13, and 14 are vacant land. Parcels in this area are zoned I-1 (Light Industrial).
- 2) **E. 64<sup>th</sup> Avenue to Askeland Drive** is local residential, and all adjacent parcels are built out. Parcels in this area are zoned R-5 (Low-Density Residential).

Development and zoning in the project area is not anticipated to change substantially and traffic characteristics are expected to remain relatively consistent for the life of the project. Future development of Parcels 2, 13, and 14 may increase traffic volumes in the area. There are no known plans of development for these parcels currently.

Design hour volume (DHV) represents traffic volumes during the peak hour and was estimated using the 30<sup>th</sup> Highest Hour of the closest permanent traffic recorder. Directional distribution (DD), representing the distribution of traffic during the peak hour, was estimated using available link counts and turning movement counts. Peak Hour Factors (PHF) are a measure of the uniformity of the traffic and used to convert volumes to 15 minute increments for operations analysis. PHF for each segment were determined using available link counts and turning movement counts.

Traffic data for each segment is summarized in the following table.

*Table 4 - Existing and Future Traffic Characteristics*

Location	DHV	DD	PHF
Quinhagak Street – E. Dowling Road to E. 64 <sup>th</sup> Avenue	12.0%	55/45	.70
Quinhagak Street – E. 64 <sup>th</sup> Avenue to Askeland Drive	12.0%	75/25	.75

### D. Speeds

The current posted speed limit for Quinhagak Street is 25 miles per hour (mph). The traffic speed analyses conducted by CRW in July of 2022 recorded the 85<sup>th</sup> percentile speed as shown in the following table:

*Table 5 - Observed Speeds*

Roadway	Date	85 <sup>th</sup> Percentile Speed	
		Northbound	Southbound
Quinhagak Street	7/14/2022 - 7/19/2022	29 mph	27 mph

The 85<sup>th</sup> percentile speed is the speed at which 85 percent of the drivers are driving at or below and is typically used to determine a reasonable posted speed limit for a given roadway. The remaining 15 percent of drivers whose speed is above the 85<sup>th</sup> percentile are the minority and considered to be exceeding the reasonable speed. Posted speed limits are often set at or near the 85<sup>th</sup> percentile speed.

The roadway may be considered eligible for installation of traffic calming measures if the observed 85<sup>th</sup> percentile speeds exceed the posted speed limit by more than 6 mph. The 85<sup>th</sup> percentile speeds along Quinhagak Street are 2-4 mph higher than the posted speed limit. Based upon the 85<sup>th</sup> percentile speeds and in coordination with the MOA Traffic Engineering Department, no traffic calming features are proposed for this project.

## E. Collision Data

Collision Data from the MOA was reviewed for the project area between 2014 and 2021. A total of 4 collisions were reported within the project corridor on Quinhagak Street and the cross streets: E. 63<sup>rd</sup> Avenue and E. 64<sup>th</sup> Avenue during this time frame. A summary of these collisions, including their locations and characteristics, are provided in TABLE 6 below and included in APPENDIX G.

*Table 6 - Project Area Collision History: 2014-2021*

Intersection	Collision Type							Total Collisions*
	Angle	Side-Swipe	Rear End	Head On	Fixed Object	Ped/ Bike	Parked Vehicle	
E. 63 <sup>rd</sup> Avenue	1	0	0	0	0	0	0	1
E. 64 <sup>th</sup> Avenue	1	1	0	1	0	0	0	3

*\*No fatalities were reported in the collision data.*

Based upon the low number of collisions during the 7-year period, it appears that the collisions do not follow an identifiable pattern and the intersections are currently functioning in a safe manner.

## F. Side Street Intersections/Access Control

The intersection of Quinhagak Street with E. Dowling Road is a channelized intersection with left turns from Quinhagak Street onto E. Dowling Road prohibited. This intersection is a “minor street stop controlled” intersection with Quinhagak Street being the stop-controlled approach. Two streets

intersect Quinhagak Street in the project area. E. 63<sup>rd</sup> Avenue is a tee intersection with stop control on E. 63<sup>rd</sup> Avenue and E. 64<sup>th</sup> Avenue is a four-way intersection with stop control on E. 64<sup>th</sup> Avenue. The intersection of Quinhagak Street with Askeland Drive is a tee intersection with stop control on only the east side of the intersection. Quinhagak Street access is as follows:

**1) E. Dowling Road to E. 64<sup>th</sup> Avenue**

This segment has twelve commercial driveways and one residential driveway. Parcels 1 and 11 have wide access and parking areas across the full site frontage. These configurations make access and circulation unclear to drivers and increase conflict points between vehicles utilizing the driveways and the street traffic.

**2) E. 64<sup>th</sup> Avenue to Askeland Drive**

This segment has two residential driveways. One of the residential driveways is a secondary driveway that accesses the back side of Parcel 6 and appears to be used to park the owner's motorhome. The parked motorhome extends into the ROW by several feet.

The proposed design will incorporate MOA driveway access standards wherever possible to improve the safety and operations of the corridor.

**G. Level of Service Analysis**

A Level of Service (LOS) analysis was performed in accordance with the Transportation Research Board's Highway Capacity Manual, 2010 for the E. 64<sup>th</sup> Avenue and Quinhagak Street intersection. The analysis used Trafficware Synchro (Version 11) software. The MOA intersection operation standard for urban areas allows a minimum LOS D during the design year. LOS analysis was not completed for Quinhagak Street at the intersection of E. Dowling Road because proposed roadway improvements do not extend through the intersection.

**1) Quinhagak Street and E. 64<sup>th</sup> Avenue**

The intersection of Quinhagak Street and E. 64<sup>th</sup> Avenue is stop controlled on E. 64<sup>th</sup> Avenue. There is currently one approach lane in each direction. LOS was determined for both the construction year (2026) and the design year (2046). In 2026, the EB approach will operate at a LOS of B with a delay of 10.3 secs. The overall intersection will operate at a LOS of A. In the design year (2046), the intersection will continue to operate at a LOS of A and the eastbound approach operating at a LOS B with a delay of 10.8 sec. Existing traffic volumes were also reviewed to determine if the stop signs should be moved to Quinhagak Street. However, since traffic volumes on Quinhagak Street are higher than E. 64<sup>th</sup> Avenue it is recommended that Quinhagak Street remain as the major unstopped movement.

**H. All-Way Stop Analysis**

An all-way stop analysis based on current conditions was performed at the Quinhagak Street and E. 64<sup>th</sup> Avenue intersection utilizing recommendations from the latest edition of the Manual of Uniform Traffic Control Devices (MUTCD) guidelines. E. 64<sup>th</sup> Avenue is two-way stop controlled

currently, but this intersection was analyzed for all-way stop warrants due to comments from the public. Quinhagak Street is considered the major street at the intersection with E. 64<sup>th</sup> Avenue.

The MUTCD provides warrants for when an all-way stop should be considered at an intersection. Applicable warrants for the intersections Quinhagak Street:

- **Crash rate:** five or more crashes in a 12-month period that are susceptible to correction by installation of a multi-way stop.
- **Intersection Volume:** (must meet *both* of the following conditions):
  - The combined minimum vehicular volume from the major street approaches averages at least 300 vehicles per hour for any eight hours during an average day.
  - The combined minimum vehicular volume from the minor street approaches averages at least 200 vehicles per hour for the same eight hours.
- **Combination:** Where no single criterion is established but 80% of their minimum values for the crash rate and major and minor intersection volumes are met.

The MUTCD also allows the option of installing an all-way stop on residential streets of similar classification where installing the all-way stop will improve the traffic operations of the intersection.

The E. 64<sup>th</sup> Avenue intersection was analyzed to determine if it met the criteria for an all-way stop.

- Seven years of crashes were reviewed to determine the number of crashes in the highest year.
- Existing intersection count data was reviewed to determine the eight highest hours of vehicular volumes for the intersection.

Results of the analysis are summarized in TABLE 7 below. The intersection does not currently meet the warrants for an all-way stop. It should be noted that the highest hour corresponded to the AM Peak Hour with the nearby school Polaris K-12 School start time.

*Table 7 – Quinhagak Street at E. 64<sup>th</sup> Avenue All-Way Stop Analysis*

Intersection	Crashes in a 12 month period	Crash Warrant Met?	Highest Hour Int. Volume		Intersection Warrant Met?	Combined Warrant Met?
			Major	Minor		
E. 64 <sup>th</sup> Avenue	1	No	188	150	No	No

## I. Sight Distance Analysis

Adequate sight distance is necessary at intersections to allow the driver of a stopped vehicle at a minor road a sufficient view of the intersecting main roadway to decide when to enter or cross the main roadway. If the available sight distance for a minor-road vehicle is at least equal to the required stopping sight distance of the major road vehicle, then drivers have sufficient sight distance to anticipate and avoid collisions. However, in some cases, a major-road vehicle may need to stop or slow to accommodate the maneuver from the minor-road vehicle. Therefore, to provide safe traffic

operations, intersection departure sight distances should exceed stopping sight distances along the major road.

The intersection departure sight triangles, per requirements of the DCM, have been drawn at each intersection within the project area to determine any potential issues; see [APPENDIX I](#) for intersection departure sight triangles. Features that hinder the sight triangle should be removed or reset to be outside of the intersection departure sight triangles where feasible. The only items that are within the sight triangles are privately owned boulders on the east side of Quinhagak Street south of E. 64<sup>th</sup> Avenue. The boulders will be placed on property and outside of the sight triangles as part of the proposed improvements. New light poles will also be located outside the sight triangles where feasible.

## **J. Parking Study**

A parking study was conducted to document the current use of on-street parking for consideration in the design of the proposed improvements. Parked vehicles within the adjacent parking lots were also noted during the study to assess available off-street parking. The parking study was based on observations from four separate site visits. Site visits were organized to include one weekday afternoon/evening and one weekend afternoon/evening and took place on Thursday, July 14, 2022 and Saturday, July 16, 2022 (see [APPENDIX G](#) for the parking study memorandum). During the parking study only one car was observed parked on the roadway near Askeland Drive. The adjacent parking lots in the industrial/commercial zone north of E. 64<sup>th</sup> Avenue appeared to have sufficient parking on their private lots. Based upon the parking study results there is not a significant demand for on-street parking along the roadway. The greatest demand for on-street parking is closer to Askeland Drive within the low-density residential zoning area.

## **K. Traffic Calming**

Based upon the 85<sup>th</sup> percentile speeds and in coordination with the MOA Traffic Engineering Department, no traffic calming features are proposed for this project.

If speeding is a concern upon completion of the project, appropriate traffic calming measures could be installed if approved by the MOA Traffic Engineering Department.

## VI. Design Criteria and Standards

Project design criteria are based on the roadway characteristics, functional classification, and road or facility ownership. The roadway is owned and maintained by the MOA.

### A. Project Design Standards

The PM&E Design Criteria Manual (DCM) provides detailed design criteria for the development of roadways and infrastructure within the MOA. The documents listed below provide additional design guidance, standards and requirements for this project.

- AMATS Non-Motorized Plan, 2021, AMATS
- Anchorage Pedestrian Plan (APP), 2007, MOA.
- Anchorage Bicycle Plan, 2010, MOA.
- Official Streets and Highways Plan (OS&HP), 2014, MOA.
- Anchorage Bowl 2020 Comprehensive Plan, 2001, MOA.
- Anchorage 2040 Land Use Plan, 2017, MOA.
- 2035 Metropolitan Transportation Plan (MTP), 2015, AMATS.
- 2040 Metropolitan Transportation Plan (MTP), 2020, AMATS.
- Anchorage Stormwater Manual (ASM), 2017, MOA.
- Neighborhood Traffic Calming Policy Manual, 2016, MOA Traffic.
- Roadside Design Guide (RDG), 4th Edition, 2011, American Association of State Highway and Transportation Officials (AASHTO).
- A Policy on Geometric Design of Highways and Streets, 7th Edition (AASHTOGB), 2018, AASHTO.
- Manual on Uniform Traffic Control Devices (MUTCD), 2009 with Revisions 1 and 2, Federal Highway Administration (FHWA).
- Municipality of Anchorage Standard Specifications, 2015, MOA.
- Alaska DOT&PF Preconstruction Manual (PCM), 2019, ADOT&PF.
- Alaska Traffic Manual (ATM), 2015, ADOT&PF.
- Proposed Accessibility Guidelines for Pedestrians in Public Right-of-Way (PROWAG), 2011, United States Access Board.
- Anchorage Municipal Code Title 21 – Land Use Planning.
- A Strategy for Developing Context Sensitive Transportation Projects, 2008, MOA.
- AWWU Design and Construction Practices Manual, 2018, AWWU.

### B. Design Criteria Summary

A summary of roadway design criteria pertinent to this project can be found in [TABLE 8](#) below. Potential deviations from design criteria are described in [SECTION XVI](#). Detailed lighting design criteria is discussed in [SECTION VII. D](#).

Table 8 - Design Criteria Summary

	Criteria	Design Standard Value		Reference
		E. Dowling Road to E. 64 <sup>th</sup> Avenue	E. 64 <sup>th</sup> Avenue to Askeland Dr.	
Traffic Data	Functional Classification	Secondary Street: Urban Residential	Secondary Street: Industrial/Commercial	OSH&P
	AADT – 2026	1,536 vpd		Assumed Growth
	AADT – 2045	3,200 vpd		Assumed Growth
	Design Vehicle	WB-50		DCM 6.4 B
	Design Structural Loading	HS 20		
	Design Speed	30 mph		DCM Table 1-6
	Posted Speed	25 mph		DCM 1.5.E
Horizontal Alignment	Stopping Sight Distance, Min	200 ft		DCM Figure 1-20
	Clear Sight Triangle Length	335 ft		DCM Figure 1-19
Vertical Alignment	Vertical Grade, Maximum	6.0%		DCM 1.9.D.2.b
	Vertical Grade, Minimum	0.5% for street with curb and gutter		DCM 1.9.D.2.a
	Vertical Curve K-Value, Min Crest Curve	19		DCM Figure 1-16
	Vertical Curve K-Value, Min Sag Curve	37		DCM Figure 1-17
Cross Section	Street width (measured to back of curb)	40 ft (if 2 parking lanes are required) 33 ft (if no parking lanes are required)	38 ft (if 2 parking lanes are required) 31 ft (if no parking lanes are required)	DCM Tables 1-5 & 1-6
	Number of Travel Lanes	2		DCM Tables 1-5 & 1-6
	Number of Parking Lanes	2		DCM Tables 1-5 & 1-6
	Shoulder Width (No Parking Lane)	3.5 ft		DCM Tables 1-5 & 1-6
	Curb & Gutter	Type 2 (DCM) Type 1 or Type 2 if warranted (Title 21)		DCM Figure 1-13 Title 21.08.050.G
	Side slopes	2H:1V maximum		DCM 1.9.D.5

	Criteria	Design Standard Value		Reference
		E. Dowling Road to E. 64 <sup>th</sup> Avenue	E. 64 <sup>th</sup> Avenue to Askeland Dr.	
Cross Section	Clear Zone	12 feet minimum		See <a href="#">SECTION VI.C.4</a> )
	Sidewalk Requirements & Width	Both sides of roadway if connecting to existing sidewalk on both ends, 5 ft min One side of roadway, 5 ft min if not connecting to existing sidewalks on both ends	Both sides of roadway, 5 ft min	Title 21.07.060.E.2.b
	Sidewalk Separation from Back of Curb	7 ft (for collectors and higher classification)		DCM 4.2 H
Inter-sections & Driveways	Curb Return Radii at Side Streets	20 ft (local/local)* 30 ft (local/collector or arterial)* 40 ft (arterial/arterial) *The above specified curb radii shall be increased in areas zoned commercial or industrial to the next higher classification.		DCM Figure 1-22
	Driveway width: up to 7-plex	14 – 20 ft; (28 ft with restrictions)		MOA Driveway Standards 11/3/21
	Driveway width: commercial or ≥ 8-plex	24 – 34 ft		MOA Driveway Standards 11/3/21
	Max driveway grade: residential	± 12%		MOA Driveway Standards 11/3/21
	Max driveway grade: commercial, ≥ 8-plex	± 8%		MOA Driveway Standards 11/3/21
	Landing grade/length: residential	± 2% for 12 ft		MOA Driveway Standards 11/3/21
	Landing grade/length: commercial, ≥ 8-plex	± 2% for 20 ft ± 2% for 30 ft for semi-tractors or trailers		MOA Driveway Standards 11/3/21

## C. Specific Design Criteria

The appropriate street section is determined by traffic volumes and land use. The DCM classifies Quinhagak Street as a secondary (local) industrial/commercial street from E. Dowling Road to E. 64<sup>th</sup> Avenue and a secondary (local) urban residential street from E. 64<sup>th</sup> Avenue to Askeland Drive. Secondary streets typically have lower design volumes and often provide direct access to adjacent lots. Based on Anchorage Municipal Code (AMC) Title 21 Land Use Zoning, Quinhagak Street is a Class A “urban” street. Urban streets are required to include a paved surface, curb and gutter, sidewalks or trails, street lights, traffic control devices, street signs, landscaping, and storm drains.

### 1) Design Speed

The design speed governs various geometric features of the roadway and should be a logical speed with respect to anticipated speed limit, topography, and functional classification of the roadway. The design speed affects the length of sight distance available along the roadway’s horizontal alignment and vertical profile, particularly at intersecting roadways and pedestrian facilities. As design speeds increase, longer sight distances are required to provide more reaction time and braking distance to respond to roadway obstacles.

The DCM requires a secondary (local) industrial/commercial street with parking allowed on the street have a design speed of 30 mph. For a secondary (local) urban residential street with more than 1,000 Average Daily Traffic (ADT) the DCM requires a design speed of 30 mph. Generally, the posted speed limit should be 5-10 mph less than the design speed.

### 2) Accessibility Guidelines

The current requirements for accessibility in the MOA ROW are based on the Americans with Disabilities Act (ADA). The project uses guidelines published in Proposed Accessibility Guidelines for Pedestrian Facilities in Public Right-of-Way, July 26, 2011 (ADA Guidelines) by the United States Access Board. A summary of some of the ADA design criteria pertinent to the project is provided below:

- R302.3 – The continuous clear width of pedestrian access routes shall be 4.0 feet minimum.
- R302.4 – Where the clear width of pedestrian access routes is less than 5.0 feet, passing spaces shall be provided at intervals of 200 feet maximum.
- R302.5 – Where pedestrian access routes are contained within a street or highway right-of-way, the grade of pedestrian access routes shall not exceed the general grade established for the adjacent street or highway.
- R302.5.1 – Where pedestrian access routes are contained within pedestrian street crossings, the running grade of the pedestrian access route shall be 5% maximum.
- R302.6 – The cross slope of pedestrian access routes shall be 2% maximum.
- R304.3 – Parallel curb ramps shall include a turning space with minimum dimensions of 4.0 feet x 4.0 feet at the bottom of the ramp.
- R304.3.2 – The running slope of the curb ramp shall be in-line with the direction of sidewalk travel and shall be 5% minimum and 8.33% maximum but shall not require the

ramp length to exceed 15.0 feet maximum. The running slope of the turning space shall be 2% maximum in any direction.

- R304.5.1 – The clear width of curb ramp runs and turning spaces shall be 4.0 feet minimum.
- R304.5.2 – Grade breaks at the top and bottom of curb ramp runs shall be perpendicular to the direction of the ramp run.
- R304.5.3 – The cross slope of curb ramps and turning spaces shall be 2% maximum.

The Public Rights-of-Way Accessibility Guidelines recognize that it is not always possible for altered elements (reconstruction of existing facilities) to fully comply with new construction requirements because of existing physical constraints. The guidelines state:

*Where existing physical constraints make it impractical for altered elements, spaces, or facilities to fully comply with new construction requirements, compliance is required to the extent practicable within the scope of the project. Existing physical constraints include, but are not limited to, underlying terrain, right-of-way availability, underground structures, adjacent developed facilities, drainage, or the presence of a notable natural or historic feature.*

All elements included in the project that cannot meet the requirements of ADA due to technical infeasibility should be documented.

### **3) Roadway Cross Section**

Per DCM Table 1-5, secondary (local) industrial/commercial streets with parking allowed on the street should have a street width of 40 feet (measured from back of curb) with 2 travel lanes, 2 parking lanes, and curb and gutter. The travel lane width is 11 feet and the parking lane width is 7 feet. If a parking lane is not provided due to adequate off-street parking, shoulders should be provided with typical widths of 3.5 feet and a total back of curb (BOC) width of 33 feet. Per the DCM 1.5.G, pedestrian facilities shall be provided as specified in AMC Title 21 for local streets. Per AMC Title 21.07.060.E.2.b states that sidewalks shall be installed on both sides of local streets. In industrial/commercial zoning districts though, a sidewalk shall be installed on one side of all local streets, and on both sides of local streets if the new sidewalks would connect to existing sidewalks on both ends and the needed length is no greater than one quarter mile.

Per the DCM, secondary (local) urban residential streets with over 1,000 ADT and houses located on both sides of the roadway should have a street width of 38 feet (measured from back of curb) with 2 travel lanes, 2 parking lanes, and curb and gutter. The typical lane width for a local residential street is 10 or 11 feet depending on existing and forecasted neighborhood densities, zoning, and traffic volumes; the parking lane width is 7 feet. If a parking lane is not provided, shoulders should be provided with typical widths of 3.5 feet for a total BOC width of 31 feet. Per the DCM 1.5.G, pedestrian facilities shall be provided as specified in AMC Title 21 for local streets. Per AMC Title 21.07.060.E.2.b 5-foot wide sidewalks shall be provided on both sides of a local street in Class A zoning districts.

It is preferable for the sidewalks to be separated from the roadway to provide pedestrian comfort and safety, increase intersection sight distances, and provide room for snow storage however separation is not required for a local roadway. A clear area of 7 feet beyond the back of curb is required for snow storage. The sidewalk can be considered as part of the snow storage area. Roadway sections with narrow shoulders provide little room for snow storage on the street and require snow to be temporarily plowed behind the curb. This may impede pedestrian passage on an attached sidewalk and/or buffer area during major snow events until the snow is cleared.

DCM curb type for secondary (local) streets is required to be Type 2 (rolled) curb and gutter. AMC Title 21.08.050.G requires curb and gutters to be in accordance with the DCM but shall be Type 1 (barrier) except for the following exceptions:

- 1). Curb and gutter within the arc of a residential scale cul-de-sac may be Type 2 (rolled) curb and gutter.
- 2). Type 2 (rolled) curb and gutter may be provided for residential minor streets as defined in Subsection 21.08.050.D.1.a.i.
  - i.) that do not require installation of sidewalks per Section 21.08.050.H; or
  - ii.) when the pedestrian facilities will be separated from the curb by a minimum of 3 feet; or
  - iii.) if the Municipal Traffic Engineer determines that strict adherence to Type 1 curb is not expected to improve walkability or is not achievable based on documentation to include topography, developmental lot size, anticipated driveway spacing, and dimensional standards.
    - a) AMC Title 21.08.050.D.1.a.i. states residential minor states have the sole purpose of providing frontage for service and access to individual lots. These streets carry only traffic having either an origin or a destination on the street itself, and include cul-de-sacs or small loops carrying 500 average daily trips.

#### **4) Roadway Clear Zone and Horizontal Offset**

The DCM defines the roadway clear zone to be:

*...the total roadside border area, starting at the edge of the traveled way, available for safe use by errant vehicles. The desired width of the clear zone is dependent on the traffic volume, design speed, and roadside geometry.*

The DCM references AASHTO's Roadside Design Guide (RDG) for rural conditions (i.e. no curb and gutter) but it is unclear as to the applicability of the clear zone concept to curbed urban roadways. In 2011, FHWA published on their website the following guidance regarding clear zone along curbed roadways:

*Since curbs are now generally recognized as having no significant containment or redirection capability, clear zone should be based on traffic volumes and speeds, both without and with a curb.*

The recommended clear zone width is a function of the design speed, traffic volume, functional classification of the roadway, and the side slope of the roadway. The clear zone required for a urban roadway with a design speed of <40 mph and an ADT of 1,500 to 6,000 is 12 to 14 feet, with a foreslope of 6H:1V or flatter.

However, the AASHTOGB, similar to the DCM, recognizes the impracticability of constructing a full clear zone in urban areas in accordance with the RDG.

*Where establishing a full-width clear zone in an urban area is not practical due to right-of-way constraints, consideration should be given to establishing a reduced clear zone or incorporating as many clear zone concepts as practical, such as removing roadside objects or making them crashworthy.*

The typical minimum roadway cross section for a local road with a sidewalk will meet the minimum clear zone width of 12 feet specified in the RDG (3.5-foot wide shoulder + 2-foot wide curb + 5-foot wide sidewalk + 1.5-foot wide sidewalk shoulder = 12 feet).

## **5) Landscaping**

Quinhagak Street is classified as a local road, therefore there are no specific design requirements for landscaping defined within the DCM. However, landscape work for this project will meet the General Considerations for Landscape Installation and Maintenance in the DCM Section 3.3. If new landscaping is installed it will also meet the guidelines for tree and shrub placement in sight triangles found in the DCM and Title 21.

## **6) Storm Drain**

A summary of the pertinent storm drain design criteria per the Anchorage Stormwater Manual (ASM) is provided below:

- Storm drain pipes shall be corrugated polyethylene pipe (CPEP) due to corrosion issues in Anchorage area.
- Minimum diameter of main storm/subdrain pipe is 12 inches.
- Minimum diameter of catch basin leads and subdrain only pipe is 10 inches.
- Minimum pipe slope is 0.30%.
- The storm drain system shall not be surcharged during the design storm event.
- At the design flow, minimum pipe flow velocity is two feet per second (fps). Maximum pipe flow velocity is 13 fps.
- Minimum depth of cover over a gravity storm drain pipe without thaw protection is four feet.
- Insulation is required for pipes if the depth of cover is less than four feet. If storm drain pipe is located under a roadway structural section and insulation is included in roadway section, additional insulation for pipe is not required.

- A thaw system is required if the depth of cover is less than three feet.
- Maximum manhole spacing is 300 feet.
- Minimum invert elevation difference across a manhole is 0.05 feet

## VII. General Design Considerations

### A. Complete Streets

A complete streets network is a roadway network that is safe, comfortable, and convenient for users of all ages and abilities and all modes of transportation. Complete streets should provide facilities that balance the needs of pedestrians, bicyclists, transit users, motorists, and movement of goods. A network-based complete streets approach recognizes that, while all roadway users need to be accommodated within a given neighborhood or corridor, no single street can accommodate and prioritize all transportation users at all times. Through a network-based approach, MOA can designate priority streets for a given mode to create a high quality experience for those users, while providing a high-quality facility for other modes on parallel but equally convenient routes.

### B. Right-of-Way Acquisition

A key element for the successful completion of any project is the acquisition of any required ROW, easements, and/or permits required for construction while providing fair and equitable treatment to all affected property owners, tenants, and lessees.

The MOA's process for residential and business acquisitions (partial or full) follows the guidelines addressed in the State of Alaska's *Acquiring Real Property for Federal and Federal-Aid Programs and Projects* brochure, the *Relocation Services for Residential Property* brochure, and the *Relocation Services for Businesses, Farms & Non-Profit Organizations* brochure. Individual parcel's acquisition details are determined on a case-by-case basis and negotiated privately between the MOA and the property owner.

In general, public use easements (PUE) are required in areas where the footprint of the improvements exceeds the ROW. Slope easements (SE) are required for areas where the cut and fill slopes are outside of the ROW and need to be maintained. Drainage easements (DE) are required for drainage facilities installed on private property. Temporary construction permits (TCP) are required on private properties for matching new driveway grades to existing driveway grades, installation of storm drain footing services or water key boxes at the property line, and the relocation, removal or repair of improvements such as mailboxes, curbs, landscaping, fencing, and encroaching structures. Temporary construction easements (TCE) allow contractors temporary access onto private property to construct improvements that are within the ROW but where there is insufficient space within the ROW to conduct the work.

Property owners who have personal improvements in the ROW, such as fences, retaining walls or landscaping boulders, have the option of applying for encroachment permits for the improvements, removing them at their own expense, or allowing the corrective action be incorporated into the project design. Encroachment permits for fences, rock gardens, planters, and decorative retaining walls within the roadway clear zone are usually not granted.

### **C. Mailboxes**

There are no individual or cluster mailboxes located directly on Quinhagak Street within the project limits. Parcel 15 has an individual mailbox for mail delivery located on-property approximately 25 feet west of the property line and it's not anticipated that the project will impact it.

There is also a cluster of individual mailboxes just outside of the project limits located at the southeast quadrant of the Quinhagak Street and Askeland Drive intersection. If the project ends up impacting these mailboxes, it's anticipated that these will be replaced as a cluster of individual mailboxes. Previous communication with the United States Postal Service (USPS) indicates that to change from individual to cluster locking mailboxes the following must occur:

- Every affected resident must agree to the change from individual mailboxes to cluster locking mailboxes. If even one resident doesn't agree, the mailboxes cannot be switched to cluster locking style. To officially make the change in mail service, a signed concurrence from each owner is required.
- MOA is required to purchase the locking cluster mailboxes and install concrete foundations.

From past PM&E project experiences, it is very hard to gain concurrence from all affected residents, thus this project plans to re-install individual mailboxes if impacted. Individual mailboxes can be re-used where feasible. If the existing mailboxes do not meet current postal standards, they will be replaced with new boxes that meet current standards.

### **D. Lighting**

Lighting systems shall be designed to the DCM's Chapter 5 criteria and enhance traffic and pedestrian safety. The properly designed lighting system will:

- Provide the minimum maintained average luminance and illuminance levels specified for roadways, sidewalks, and intersections.
- Provide a uniformity of lighting that does not exceed the maximum ratios specified for roadways, sidewalks, stand-alone pathways, and intersections.
- Minimize construction and maintenance costs.
- Avoid adverse impacts to adjacent properties.
- Reveal hazards to pedestrians and vehicular traffic.

The MOA has retrofitted many existing luminaire poles with luminaires that use LEDs as the light source and new roadway projects with lighting improvements now incorporate LED lighting into the design. The new proposed LED lighting system for this project will be designed to provide the light levels specified in the DCM as summarized below:

#### **1) Roadway (not including intersections):**

For a local roadway with medium pedestrian activity, the DCM recommends a minimum maintained average of 0.7 foot-candles with an average-to-minimum uniformity ratio no greater than 6:1 and a veiling luminance ratio no greater than 0.4.

## 2) Pedestrian Facilities:

It is anticipated that pedestrian activity along the project roadways will be in the medium range per Chapter 5 of the DCM. For adjacent pedestrian facilities within the medium pedestrian volume criteria, the DCM requires a minimum maintained average horizontal illuminance of 0.5 foot-candles with an average-to-minimum uniformity ratio no greater than 4:1 and a minimum vertical illuminance of 0.2 foot-candles.

## 3) Intersections:

For the purpose of lighting intersections, the DCM uses the following roadway classifications based upon the ADT (note these do not apply to standard MOA DCM street classifications):

- Major: over 3,500 ADT
- Collector: 1,500 to 3,500 ADT
- Local: 100 to 1,500 ADT

Below, in TABLE 9, is a summary from the DCM of lighting for intersections. This table will be used to design lighting improvements at the project intersections. Intersection lighting classifications for the project intersections will be Collector/Local based upon the design year ADT as shown in SECTION V.B.

*Table 9 - Illuminance for Intersections (MOA DCM Table 5-5)*

Functional Lighting Classification	Average Maintained Illuminance (medium pedestrian area)	Maximum Uniformity Ratio
Major/Major	2.6	3.0
Major/Collector	2.2	3.0
Major/Local	2.0	3.0
Collector/Collector	1.8	4.0
Collector/Local	1.6	4.0
Local/Local	1.4	6.0

The luminaires will also provide a full cutoff light distribution to reduce the negative effects of casting light on nearby properties (especially residences) and illuminating the night sky. To minimize the trespass of light on adjacent properties and reduce glare, luminaires are to be installed 30 feet above the pavement and fixtures in certain areas should have backlight control optics. The light poles pile foundations will be installed to a minimum depth of 25 feet below ground surface as recommended per the Geotechnical Report.

The existing luminaire poles and light fixtures at the intersections of Quinhagak Street and E. 64<sup>th</sup> Ave and at the intersection of Quinhagak Street and Askeland Drive will be removed. A new continuous lighting system with LED luminaires will be installed to meet minimum illumination requirements. The preliminary lighting design has luminaire poles on the east side of Quinhagak

Street and will have double mast arm poles at the intersections with Askeland Dr., E. 64<sup>th</sup> Ave and E. 63<sup>rd</sup> Ave. Power for the new lighting system will come from an existing Type 1A Load Center on E. 63rd Ave, east of the intersection with Quinhagak Street.

#### **E. Landscaping**

Since Quinhagak Street is a local road no specific landscaping is proposed as part of the project improvements.

## VIII. Roadway Design Alternatives

Roadway plan and profile drawings depicting alternatives for upgrades to the project and the locations of individual parcels can be found in [APPENDIX B](#).

### A. Design Challenges

Some of the significant design challenges associated with the Quinhagak Street project include:

#### 1) Full Frontage Driveways and Parking

The existing rolled (Type 2) curb along Quinhagak Street allows for full frontage access to on-property parking. Parcels 1 and 11 currently utilize the full frontage access to enter onto their property and parking areas. Installation of barrier (Type 1) curb along the roadway would limit property access to driveway curb cut locations and could affect the ability for property owners to access parking lots and spaces.



*Parcel 1 full frontage driveway and parking viewing south on Quinhagak Street*

#### 2) Driveway Grades and Landings

There are 15 existing driveways/access areas along the project corridor. Driveways will need to be reconstructed to match the proposed roadway design grades. The length of driveway improvements will depend on the proposed grade adjustments required at each driveway. Proposed conceptual driveway grades were analyzed for the preferred alternative only and are summarized along with existing grades in [APPENDIX L](#). Proposed conceptual plan view driveway locations and reconstruction limits are shown on the roadway plan and profile drawings in [APPENDIX B](#).

Many driveways do not have the DCM required 2% landings (20-foot-long for commercial properties, 30-foot-long landing for commercial properties with semi-tractors or trailers, and 12-foot-long for residential) and some have relatively steep grades (9-14%) up to the existing parking lots or structures. Proposed improvements will install a pedestrian facility that is ADA compliant (2% max cross slope). Where pedestrian facilities cross driveways, the ADA compliant pedestrian facility will function as a partial driveway landing however providing the DCM required landings would result in significant driveway and parking lot reconstruction on private property. The proposed driveway grades shown in [APPENDIX L](#) reference the grade beyond the proposed pedestrian facility.

### 3) Driveway Curb Returns and Curb Cuts

The existing driveway access along the project corridor includes full frontage unrestricted rolled (Type 2) curb access.

The MOA DCM requires curb returns be installed at driveways accessing commercial structures, including 8-plex residential structures and greater. For driveways to residential structures up to 7-plex, either curb cuts or curb returns can be installed. Curb returns allow for vehicles to travel into/out of driveways at a higher speed. However, curb returns prevent a continuous gutter/concrete flow path for stormwater drainage across the driveway, compared to curb cuts that construct continuous curb and gutter across the driveway. The curb cuts promote positive drainage across the driveways, which will be critical along some sections of the project corridor that have longitudinal roadway grades less than 1%.

Since Type 2 curb is currently installed no curb returns are proposed for commercial properties, instead curb cuts or Type 2 curb are proposed to be installed at all driveways on this project depending on the proposed typical sections. Roadway cross sections are discussed in more detail in the following section.

### 4) Flat Grades

The street grade near E. Dowling Road is very flat, as low as 0.1%. Roadway improvements along this segment require a forced high and low spot to facilitate minimum grades to improve drainage. Matching into the existing driveways may be a challenge with proposed grade changes.

### 5) Fence Slats

There are existing fences with slats on Parcels 2 and 3 along the east side of the roadway that hinder the driveway departure sight distance of proposed sidewalk users by vehicles exiting the driveways, see Parcel 3 driveway gate fence with slats photo below. To mitigate this issue the proposed sidewalk will need to be attached along this segment then the required departure sight distances are achievable.



*Parcel 3 driveway gate with fence slats*

## **B. Roadway Alternative Cross Sections**

To address the challenges above three roadway cross section alternatives were developed in the Final Technical Memorandum in coordination with MOA PM&E, Traffic Engineering and Street Maintenance, see [APPENDIX N](#) for the Final Technical Memorandum and [FIGURE 4](#) below for the three typical section alternatives. Since the project is a local road, no roadway traffic markings are proposed along the project corridor. The typical sections aim to balance the context of the roadway with design criteria and driveway allowances and standards. All alternatives include two 11-foot wide travel lanes with 3.5-foot wide shoulders for a total width measured to back of curb (BOC) equal to 33 feet. Due to the low on-street parking demand no dedicated parking lane is proposed. Since the majority of Quinhagak Street is a secondary (local) industrial/commercial street with low pedestrian activity, a single 5-foot wide sidewalk with a 3-foot wide concrete buffer is proposed on the east side of the roadway. The buffer will be eliminated along Parcels 2 and 3 to improve sight distance of sidewalk users as noted above due to the fence with slats on property. Below is a description of each alternative. Only two alternatives were scoped to be analyzed in depth in the DSR. Based upon approval from PM&E, Alternatives 2 and 3 were analyzed in depth in the DSR.

### **1) Alternative 1 – Not analyzed in depth in DSR**

This alternative includes Type 1 (barrier) curb and gutter proposed on both sides of the roadway. Since only one pedestrian facility is proposed for this project and use of Type 2 rolled curb and gutter was allowed to be used per MOA Traffic Engineering and Street Maintenance feedback which facilitates existing driveways well, this alternative was not chosen to be analyzed in depth in the DSR.

### **2) Alternative 2 – Analyzed in depth in DSR**

This alternative includes Type 2 (rolled) curb and gutter proposed on both sides of the roadway. This alternative matches the existing curb type and allows access to properties on both sides of the roadway but doesn't provide protection for the pedestrians on the proposed east side sidewalk as compared to Type 1 (barrier) curb and gutter.

### **3) Alternative 3 (Preferred) – Analyzed in depth in DSR**

This alternative includes Type 2 (rolled) curb and gutter proposed on the west side and Type 1 (barrier) curb and gutter proposed on the east side of the roadway. This alternative matches the existing curb type on the west side of the roadway, but barrier curb is proposed on the east side of the roadway where the sidewalk is proposed. The barrier curb delineates the sidewalk better and discourages parking on the sidewalk compared to the rolled curb. Parcel access on the east side will utilize driveway curb cuts. Alternative 3 is the preferred alternative since it functions better than Alternative 2 regarding delineating the sidewalk and protecting the sidewalk from vehicles parking on it.




Figure 4 - Proposed Typical Sections

### **C. Horizontal Alignment**

The Quinhagak Street roadway is currently approximately centered on the existing ROW centerline. The goal of the proposed horizontal alignment is to center the proposed overall roadway cross section (measured from back of curb to back of sidewalk) within the ROW to balance improvements and limit impacts to adjacent properties and utilities. The proposed roadway cross section will be centered within the ROW from Askeland Drive to Station 19+25. To avoid the proposed curb and gutter conflicting with existing water valves along Quinhagak Street beginning at Station 19+25 the horizontal alignment will shift to the east by 3.5 feet and will continue along the same alignment until E. Dowling Road. During design development the proposed roadway centerline location may be adjusted.

### **D. Vertical Alignment**

The overall intent of the roadway profile is to maintain adequate grades for drainage along the project corridor while minimizing adverse effects on surrounding driveways, side streets, and infrastructure. The more the proposed roadway grade is changed from the existing grade, the more the cut and fill slopes will impact adjacent properties. Driveways and side streets must also be adjusted to match the new roadway grades. The proposed profile for Quinhagak Street will generally match the existing grade but will force a high point south of E. Dowling Road and increase the grades in this area to a minimum of 0.65%. The proposed conceptual roadway profiles for Alternatives 2 & 3 are shown in [APPENDIX B](#). The side streets are presented for the Alternative 3 (preferred alternative) only. During design development the proposed profile will be iteratively modified in more detail to provide a well-balanced design that minimizes impacts to adjacent properties and provides acceptable driveway grades.

### **E. Posted Speed Limit**

The DCM recommends that the posted speed limit typically be 5-10 mph lower than the design speed. The recommended posted speed limit is 25 mph, 5 mph below the design speed of 30 mph and matches the current posted speed limit.

## IX. Drainage Improvements & Design Alternatives

The CCTV storm drain inspection performed by MOA Street Maintenance ([APPENDIX D](#)) and the drainage analysis discussed in [SECTION III](#) identified several deficiencies in the existing storm drain systems within the project limits, as well as adjacent systems downstream of Quinhagak Street. One of the primary goals for this project is to improve drainage and correct any issues within the project corridor.

The proposed drainage improvements consist of the following:

- Replace and upsize the aging Quinhagak Street and Askeland Drive systems to accommodate the current design storm and align with proposed roadway improvements.
- Install a new subdrain system along length of project corridor to alleviate roadway issues caused by high groundwater levels and extend the life of roadway.
- Install catch basins at designed roadway low points and other areas as necessary to alleviate ponding issues.
- Provide positive roadway drainage to minimize ponding.
- Provide water quality treatment for stormwater runoff.
- Configure proposed subdrain systems to meet separation distance requirements from existing water and sewer mains.
- Provide freeze protection for the proposed subdrain systems if required.
- Install footing drain services to each parcel.

Two storm drain/subdrain system alternatives were developed to address these drainage issues. Each alternative is discussed in more detail in [SECTION IX.B](#) below.

### A. Hydrologic and Hydraulic Model Results

A hydrologic and hydraulic (drainage) model was developed for the proposed stormwater conveyance systems, using the same methodology as outlined for the existing conditions drainage model in [SECTION III.B](#). The purpose of the proposed drainage model is to properly size the new stormwater system and correct any issues identified in the existing system. The two primary systems that will be upgraded are the Quinhagak Street system and the Askeland Drive system. Improvements to adjacent and/or connecting storm drain systems that are outside of the project limits will not be upgraded as part of this project.

A total of 22 contributing catchments were delineated and evaluated for runoff response for the proposed condition. Most contributing catchments within the project boundaries were adjusted to account for the addition of new curb inlets planned along Quinhagak Street.

Peak runoff and pipe flows for the proposed drainage systems are reflected in [FIGURE 5](#), [APPENDIX E](#). The complete SSA modeling report and results can also be found in [APPENDIX E](#). Proposed pipe sizing, type, and configuration for the drainage improvements is described in detail below.

As noted in [SECTION III.A.5](#), the E. 64<sup>th</sup> Avenue and Askeland Drive systems are known to have surcharging and/or backwater effects downstream of the Quinhagak Street system connections.

These conditions are not reflected in the drainage models for the existing or proposed conditions due to limited available information on these conditions and what's causing them.

## **B. Drainage Design Alternatives**

Two drainage design alternatives were developed to address the deficiencies of the existing storm drain system and drainage issues previously identified. Each alternative consists of replacing the existing drainage infrastructure with larger pipe to handle peak design storm flows. Both alternatives consist of installing a subdrain system to mitigate the high groundwater throughout the project corridor to extend the life of the roadway. All proposed subdrain pipe will be perforated corrugated polyethylene pipe (CPEP, Type SP). The primary difference between each alternative is the configuration of the subdrain system as summarized below.

It should be noted that since Alternative 1 for the roadway design was not analyzed in depth for this DSR, no drainage alternative was developed for this alternative.

### **1) Alternative 2 – Dual Subdrain System**

This alternative includes installing subdrain pipe on both sides of Quinhagak Street from E. Dowling Road to Askeland Drive. To accommodate subdrain on both sides of the roadway, the subdrain piping on the west side of the road will serve two functions: 1) subdrain to intercept groundwater and 2) function as the primary conveyance pipe for surface water flows entering the system. The subdrain piping on the east side of the road will be utilized solely as a conduit to intercept groundwater.

The proposed subdrain pipe (main line) on the west side of Quinhagak Street from E. Dowling Road to E. 64<sup>th</sup> Avenue ranges in size from 18- to 30-inches in diameter. This pipe will be located below the west curb line to meet separation distance from the sewer utility and be in accordance with MASS Detail 70-1 (Standard Location for New Utilities). The subdrain pipe on the east side of the road will be located outside of the proposed pedestrian facilities and will be 12-inches in diameter. Type II catch basin manholes will be installed for main line pipe, with connecting catch basins located to the east side of the roadway to intercept curb flow. The Type II catch basin manholes are installed under curb line to collect curb flow, while also providing safer maintenance access through a manhole opening off the roadway. The secondary subdrain on the east side of the roadway will use Type I manholes spaced similar to those of the main line on the west side of the road. Several existing field inlets will also need to be removed and replaced to accommodate the new system. Any existing private storm drain lines connected to structures within the ROW will be reestablished. This segment of the dual subdrain system connects to the existing E. 64<sup>th</sup> Avenue system (described in [SECTION III](#)), which flows towards the west.

A new Type I manhole will be located west of the roadway improvements on E. 63<sup>rd</sup> Avenue to intercept the existing storm drain system that extends to the east. A new 18-inch diameter subdrain pipe will extend from this new manhole and connect to the new Quinhagak Street system on the west side of the road.

The proposed dual subdrain system will extend south along Quinhagak Street from E. 64<sup>th</sup> Avenue to Askeland Drive. The subdrain pipe on the east and west side of the roadway will be 12-inch diameter connected via a combination of Type I manholes and Type II catch basin manholes to intercept curb flow at the intersection. Both pipe systems connect to the existing system on Askeland Drive (described in SECTION III) via separate Type I manholes. A segment of new 18-inch subdrain pipe will replace the existing perforated corrugated metal pipe (CMP) between the new Type I manholes on Askeland Drive. There is a 15-inch CMP stub-out that extends north from the existing manhole at the Quinhagak Street/Askeland Drive intersection that will be removed or abandoned in place.

Alternative 2 is shown on the Storm Drain Plan and Profile sheets (C1.1-C1.3) in APPENDIX C.

## **2) Alternative 3 (Preferred) – Single Subdrain System**

This alternative includes installing a single subdrain pipe down the center of Quinhagak Street from E. Dowling Road to Askeland Drive. Similar to the main line pipe in Alternative 2, this subdrain pipe will function as both a subdrain to intercept groundwater, as well as serve as the primary conveyance pipe for surface flows entering the system.

The proposed subdrain pipe ranges in size from 18- to 30-inches in diameter. This pipe is located between the existing water and sewer mains and is situated to maintain separation distance between these utilities and be in accordance with MASS Detail 70-2 (Location for Existing Utilities). The main line pipe is routed through a combination of Type I and II manholes, with catch basins located on both sides of the roadway to intercept curb flow. As noted for Alternative 2, existing on-site systems will be reconnected to the proposed system. This segment of the single subdrain system connects to the existing E. 64<sup>th</sup> Avenue system (described in SECTION III), similar to Alternative 2.

A new Type I manhole will be installed on E. 63<sup>rd</sup> Avenue, same as Alternative 2, to intercept this existing system and connect to the proposed system on Quinhagak Street via an 18-inch diameter subdrain pipe.

The proposed single subdrain system will extend south along Quinhagak Street from E. 64<sup>th</sup> Avenue to Askeland Drive. The subdrain pipe will be 12-inch diameter located in the center of the roadway between the existing water and sewer mains, connected via a Type I manhole to the north and Type II manhole at the intersection of Askeland Drive and Quinhagak Street. This system connects to the existing system on Askeland Drive (described in SECTION III). New catch basins and leads will be installed at this intersection to accommodate the modified curb returns.

Alternative 3 is the preferred subdrain system alternative. The cost to construct the single subdrain pipe system (Alternative 3) is significantly lower (approximately 28%) than the cost of the dual subdrain pipe system (Alternative 2). This cost savings does not account for the increased utility impact costs associated with Alternative 2, which are far more significant than Alternative 3 given the additional pipe to be installed and the location of existing utilities within the project corridor. In addition to the utility costs, the duration associated with disrupting these utilities is also of consideration.

Alternative 3 is shown on the Storm Drain Plan and Profile sheets (C2.1-C2.3) in APPENDIX C.

The CCTV inspection performed by MOA Street Maintenance revealed heavy deposits and sedimentation in the existing storm drain pipes along Askeland Drive and that the system is not functioning well. Additional coordination with MOA Street Maintenance is anticipated during the design phase to determine the best approach to resolving the current issues in this area.

### **C. Proposed Drainage Improvements**

The following improvements are proposed to address the drainage concerns identified in the DSR:

#### **1) Install New Catch Basins**

The proposed roadway layout adjusts the existing curb line along the entire project corridor. The locations of the existing catch basins will not line up with the proposed curb line. Therefore, these existing catch basins will need to be removed. New catch basins and connecting leads will be installed to match the proposed curb line. Additional catch basins will be added at designed roadway low points and intersections as necessary to alleviate ponding.

#### **2) Minimize Ponding**

The proposed roadway profile is designed to establish high and low points throughout the project corridor. These high and low points, along with a more pronounced roadway crown, will direct roadway runoff more effectively to curb inlets. The curb inlets capture curb flow and direct runoff to the piped storm drain system, eliminating standing water. These improvements will help alleviate ponding issues created by runoff from within the project corridor.

#### **3) Water Quality Treatment**

The new permit requirements referenced in ASM Section 3.B.1 state that stormwater management systems are to provide water quality treatment using Green Infrastructure (GI) whenever feasible. GI treatment techniques include methods such as retention, infiltration, bioretention, evaporation, and/or any combination of these techniques.

In some cases, GI treatment may be determined to be infeasible due to site constraints such as poorly infiltrating soils, high ground water, on-site space constraints, shallow bedrock, etc. For cases where GI treatment is determined to be infeasible, water quality treatment may be provided using traditional gray infrastructure such as an oil and grit separator.

Section 3.3.2.1 of the ASM also states that roadway projects with narrow ROW (60-feet or less) may choose to provide stormwater treatment through either GI or traditional treatment, regardless of site constraints. The ROW width along the Quinhagak Street project corridor is 60-feet.

Due to the limited amount of ROW along the project corridor, high groundwater, and layout of existing utilities, providing water quality treatment through GI is not practical. Therefore, water quality treatment will be provided by an OGS. An OGS is proposed just upstream of the tie-in to the E. 64<sup>th</sup> Ave system to provide water quality treatment for the Quinhagak Street storm drain

system. A bypass manhole will be installed upstream of the OGS for maintenance of the structure.

As noted in SECTION III, MOA maintains one large existing OGS that treats runoff for the entire Meadow Street Park storm drain system, which includes the E 64<sup>th</sup> Avenue system and Askeland Drive subsystems. The OGS is located just upstream of the outfall into two interconnected sedimentation ponds that the North Fork Little Campbell Creek flow through, providing additional water quality treatment for these subsystems.

#### **4) Freeze Protection**

According to ASM Section 5.3.3, the minimum depth of cover over a gravity storm drain pipe without thaw protection is four feet. Insulation is required for pipes with a diameter less than 30-inches if the depth of cover is less than four feet. However, if a storm drain pipe is located under a roadway structural section with insulation, additional insulation for the pipe is not required. A thaw system is required if the depth of the depth of cover is less than three feet.

The roadway structural section includes insulation for this project, so additional insulation will not be required for storm drain that is located between three and four feet of cover. Depth of cover is expected to exceed 3-feet for all new piping, so no thaw systems are anticipated.

#### **5) Footing Drains**

Footing drain services will be extended from the proposed subdrain system to property line of each parcel along the project corridor except for parcels that currently have on-site storm drain systems (Parcels 4, 5 & 12). These parcels are assumed to have footing drains already connected to their on-site system if the site requires them.

The footing drain services consist of a gravity fed 6-inch CPEP pipe that connects to the main subdrain pipe with a tee or saddle and extends to property line. The parcel owner has the option to connect to this pipe and drain/pump any groundwater that may accumulate in their crawl spaces or building foundations.

## X. Right-of-Way Impacts

Preliminary estimated easement and permit requirements are summarized in TABLE 10 below and are detailed in APPENDIX H. The number of estimated easements and permits for each alternative are identical, due to the similarities between the alternatives. As the planning and design of this project progresses, the required easements and temporary construction permits will be refined.

*Table 10 - Estimated Right-of-Way Easements / Permits*

<b>Alternative</b>	<b>Public Use Easements (PUE)</b>	<b>Slope Easements (SE)</b>	<b>Drainage Easements (DE)</b>	<b>Fire Hydrant Easement (FE)</b>	<b>Temporary Construction Easements (TCE)</b>	<b>Temporary Construction Permits (TCP)</b>
2	0	0	5	3	2	23
3	0	0	0	1	2	21

## **XI. Utility Impacts**

When roadway and drainage improvements are made in urban areas, impacts to utilities need to be analyzed. Existing utility facilities are shown in APPENDIX A. For safety, overhead and underground clearances must be maintained.

In the ROW, the Municipality requires a minimum burial depth of 42 inches for buried gas lines, electric cables, fiber optic lines, telephone cables, and cable television lines. For this report, it is assumed that the existing buried facilities in the project area are buried at the minimum depth. As a result, any reduction of cover over existing facilities or impacts from storm drain improvements will require relocation of the facility. In some locations, the structural section excavation will impact utilities. In these locations the utilities will either require relocation or will require support in place for the contractor to work around the utility.

AWWU requires a minimum depth of cover of 10 feet over their water mains and 8 feet over their sewer mains. Changes to the roadway grade along the corridor are minor and are not anticipated to substantially reduce the existing cover over the water and sewer utilities. The assumed roadway cross section includes 2-inches of rigid board insulation which would mitigate some reduction in cover above water and sewer mains.

The utility relocation cost estimates for each Alternative are shown in APPENDIX J.

## **XII. Permitting and Agency Approvals**

Permits and agency approvals for the Quinhagak Street Reconstruction project required for construction of proposed improvements will be limited. Because the roadway is classified as a secondary (local) urban road, it is not necessary to obtain approval of the DSR from the MOA Planning and Zoning Commission or the MOA Urban Design Commission. Anticipated permits and agency approvals required for design include:

- MOA Watershed Management Services Stormwater Plan Approval
- ADEC Approval to Construct Storm Drain Improvements and Separation Waivers (assumed)

Additional permit requirements may be identified as the design develops.

### XIII. Quantity and Cost Estimates

A summary of estimated project costs for the proposed improvements is presented below for each Alternative. A breakdown of the ROW, construction, utility, design and management cost estimates can be found in [APPENDIX J](#).

*Table 11 - Summary of Estimated Project Costs*

Category	Alternative 2	Alternative 3 (Recommended)
Design & Management Total (estimated)	\$941,000	\$938,000
ROW Acquisition Total	\$75,000	\$21,000
Utility Relocation (15% Contingency) Total	\$969,000	\$757,000
<b>A. Design, ROW Acquisition, Utility Relocation</b>	<b>\$1,985,000</b>	<b>\$1,716,000</b>
<u>Construction</u>		
Roadway Improvements	\$2,364,000	\$2,417,000
Drainage Improvements	\$1,003,000	\$782,000
Illumination Improvements	\$216,000	\$216,000
Construction Subtotal	\$3,583,000	\$3,415,000
Construction Contingency (15%)	\$537,000	\$512,000
Construction Management / Inspection / Testing	\$369,000	\$352,000
<b>B. Total Estimated Construction Cost (rounded)</b>	<b>\$4,489,000</b>	<b>\$4,279,000</b>
<b>C. Overhead / Grant Accounting</b>	<b>\$1,142,000</b>	<b>\$1,058,000</b>
<b>Total Estimated Project Cost (A + B + C)</b>	<b>\$7,616,000</b>	<b>\$7,053,000</b>

## XIV. Stakeholder Coordination/Public Involvement

The public involvement for the Quinhagak Street Reconstruction project is following the MOA Context Sensitive Solutions (CSS) process for a local roadway as a general guide for best practices. The goal of the CSS process is to collaborate with all stakeholders to improve the roadway, balance diverse interests, find areas of compromise that address concerns and solicit feedback from stakeholders. A description of public involvement activities is below in [TABLE 13](#). All public involvement documents can be found in [APPENDIX K](#).

### A. Stakeholders

The project team began the public and agency outreach in May of 2022 with the identification of approximately 250 project stakeholders. See [TABLE 12](#) below for list of stakeholders.

*Table 12 - List of Stakeholders*

MOA Agencies	Other
Project Management & Engineering	Area Residents
Traffic Engineering	Area Property Owners & Business Owners
Watershed Management Services	Area Property Managers & Employees
Economic and Community Development	Abbott Loop Community Council
Maintenance and Operations	Alaska Communications Systems (ACS) and GCI
Planning	Chugach Electric
Transit	ENSTAR Natural Gas Company
Parks & Recreation	Senator Joshua Revak
Anchorage Fire & Police Department	Representative Calvin Schrage
Anchorage School District	
Anchorage Assembly Members Felix Rivera, and Meg Zaletel	
Solid Waste Services	
AWWU	

### B. Stakeholder Involvement Activities

A variety of forms of outreach were used to inform, consult, involve, and collaborate with stakeholders including website updates, mailed postcards, e-newsletters, in-person community council updates, a project questionnaire, agency scoping meetings, and a public open house.

[TABLE 13](#) below summarizes each major stakeholder coordination/public involvement event for the duration of the project.

*Table 13 - Stakeholder Coordination/Public Involvement Events*

<b>Date</b>	<b>Activity</b>	<b>Comments</b>
May 2022	Mailing List Developed	Approximately 250 Contacts
May 2022 - Present	Website Development & Maintenance	Launched and Updated at Key Project Milestones
May 2022	Postcard Mailer #1	Introduce Project & Field Work
June 1, 2022	Questionnaire Mailer	Announce Questionnaire
June 1, 2022	E-Newsletter #1	Announce Questionnaire
June 1 – July 1, 2022	Project Questionnaire	Collected Responses for 30 Days
September 9, 2022	Agency Stakeholder Meeting	Meeting with MOA Traffic Engineering Department and MOA Street Maintenance Department
October 20, 2022	Postcard Mailer #2 & E-Newsletter #2	Announce Open House #1
October 20, 2022	Abbott Loop Community Council Meeting #1	Announce Open House #1, Inform Stakeholders, Answer Project Questions, Listen to Comments
October 31, 2022	E-Newsletter #3	Open House #1 Reminder
November 3, 2022	E-Newsletter #4	Open House #1 Reminder Due to Weather and ASD School Closure
November 3, 2022	Public Open House #1	Introduce project, concept cross sections, and receive comments on the concepts, existing conditions, and issues in the project area.
November 8, 2022	E-Newsletter #5	Thank you for attending Open House #1
October 19, 2023	Postcard Mailer #3 & E-Newsletter #6	Announce Open House #2 and announce Draft DSR on website.
October 19, 2023	Abbott Loop Community Council Meeting #2	Announce Open House #2, announce Draft DSR on website, answer project questions and listen to comments.
November 1, 2023	E-Newsletter #7	Open House #2 Reminder
November 2, 2023	Public Open House #2	Present Draft DSR and preferred typical section, Listen to comments.
November 6, 2023	E-Newsletter #8	Thank you for attending Open House #2

### **C. Project Website**

The project website ([www.QuinhagakStreetReconstruction.com](http://www.QuinhagakStreetReconstruction.com)) was developed for ease of project information sharing and soliciting comments from the public. Website content includes a project home page overview, a documents and resources page, project team contact information, a link to provide comments and a link to sign up to receive e-newsletter project updates. The website will continue to be updated with information, meeting details, and documents as the project progresses.

### **D. Project Questionnaire**

A project questionnaire was mailed via the USPS to the project mailing list to gather additional, site specific information from project stakeholders. This tool also allows people to participate who cannot attend meetings in-person. The paper mailer included return postage and a QR code for respondents to fill out the questionnaire online. There were 21 responses to the questionnaire (6 paper, 15 online). A full summary of questions and results can be found in the APPENDIX K.

### **E. Agency Stakeholder Meeting**

The agency stakeholder meeting, held in September 2022, included representatives from MOA Traffic Engineering and Street Maintenance Departments. The purpose of the meeting was to discuss the traffic and parking studies and gain concurrence of the proposed conceptual roadway cross sections to present at the public Open House #1.

### **F. Community Council Meetings**

Project representatives attended the Abbott Loop Community Council (ALCC) meeting on October 20, 2022, to provide a project introduction, announce Open House #1, answer project questions, and listen to stakeholder comments. Project representatives attended the ALCC meeting on October 19, 2023, to provide a project update, announce public Open House #2, and listen to stakeholder comments. The meeting summaries can be found in the APPENDIX K.

### **G. Public Open Houses**

A public open house was held on November 3, 2022, from 5:00 – 7:00 pm. The meeting was held at Polaris K-12 School (6200 Ashwood St.). 8 community members were in attendance (6 people signed in). Open House #1 presented scrolls with aerial images of the existing layout of the project corridor. Attendees had the opportunity to draw and mark up the scrolls with comments regarding known issues or concerns of existing conditions along the project corridor. Displays also included a project timeline, summary of proposed improvements, questionnaire responses, and cross-sections of conceptual designs. Comment sheets were provided for attendees to share written comments. Materials presented at the Open House #1, comments received, and sign-in sheets are included in APPENDIX K in the Open House #1 Meeting Summary.

Public Open House #2 was held on November 2, 2023, from 4:30 – 6:30 pm. The meeting was held at Polaris K-12 School (6200 Ashwood St.). 12 community members were in attendance. At Open House #2 the project team presented scrolls with aerial images of the preferred alternative from the

Draft DSR. Attendees had the opportunity to draw and mark up the scrolls with comments regarding the preferred alternative. Displays also included a project timeline, summary of proposed improvements, questionnaire responses, and a typical section of the preferred alternative. Comment sheets were provided for attendees to share written comments. Materials presented at the Open House #2, comments received, and sign-in sheets are included in APPENDIX K in the Open House #2 Meeting Summary.

#### **H. Summary of Public Comments Received**

Comments were received from individuals through public meetings, community council meetings, and on-line questionnaire responses. Additional comments were recorded on project scrolls and documented in meeting records. All project comments that were received from the beginning of the project through November 20, 2023, are documented in APPENDIX K.

Stakeholders and members of the public will have the continued opportunity to obtain information and provide feedback via the project website, and through direct feedback by phone calls and emails to project staff.

## **XV. Recommended Improvements**

To achieve the project goals, meet the requirements of the DCM and AMC Title 21, and based on comments received from public, agency, and business stakeholders the recommended improvements for the project are as follows:

### **A. Roadway Cross Section**

The preferred roadway cross section is Alternative 3 (see [FIGURE 4](#)) and includes two 11-foot wide travel lanes with 3.5-foot wide shoulders (33 feet total width from BOC), and a single 5-foot wide sidewalk with a 3-foot wide concrete buffer on the east side of the roadway. The buffer will be eliminated along Parcels 2 and 3 to improve sight distance of sidewalk users due to the fence with slats on property. Type 2 (rolled) curb and gutter is proposed on the west side and Type 1 (barrier) curb and gutter is proposed on the east side of the roadway. This alternative matches the existing curb type on the west side of the roadway, but barrier curb is proposed on the east side of the roadway where the sidewalk is proposed. Since the project is a local road, no roadway traffic markings are proposed along the project corridor.

### **B. Design and Posted Speed Limit**

It is proposed that the posted speed limit for Quinhagak Street remain at 25 mph. A Design speed of 30 mph is proposed.

### **C. Roadway Horizontal and Vertical Alignment**

The proposed roadway cross section will be centered within the ROW from Askeland Drive to Station 19+25. To avoid the proposed curb and gutter conflicting with existing water valves along Quinhagak Street beginning at Station 19+25 the horizontal alignment will shift to the east by 3.5 feet and will continue along the same alignment until E. Dowling Road. The proposed profile for Quinhagak Street will generally match the existing grade but will force a high point south of E. Dowling Road and increase the grades in this area to a minimum of 0.65%.

### **D. Intersections:**

The existing stop signs within the project limits are proposed to remain as currently installed with stop control on E. 63<sup>rd</sup> Avenue, E. 64<sup>th</sup> Avenue, on the east side of Askeland Drive and on Quinhagak Street at E. Dowling Road.

### **E. Traffic Calming**

Based upon the 85<sup>th</sup> percentile speeds and in coordination with the MOA Traffic Engineering Department, no traffic calming features are proposed for this project.

## **F. Landscaping**

Since Quinhagak Street is a local road no specific landscaping is proposed as part of the project improvements.

## **G. Drainage**

The preferred drainage design is the Alternative 3 single subdrain system and consists of the following drainage improvements:

- Replace the aging Quinhagak Street & Askeland Drive storm drain system to align with the new roadway improvements.
- Install a single subdrain down the center of Quinhagak Street to mitigate the effects of high groundwater.
- Install catch basins at roadway low points and other areas to alleviate ponding issues.
- Provide positive roadway drainage to minimize ponding.
- Provide water quality treatment for storm runoff.
- Extend footing drain services to property line of each parcel along the project corridor except for parcels that currently have on-site storm drain systems (Parcels 4, 5, & 12).

## **H. Lighting**

A continuous LED lighting system, consistent with current MOA standards will be installed along the roadway. Power for the new lighting system will come from an existing Type 1A Load Center on E. 63rd Ave, east of the intersection with Quinhagak Street.

## **XVI. Proposed Variances from Design Criteria Manual**

### **A. AMC Title 21**

AMC Title 21.08.050.G requires that curb and gutters be in accordance with the DCM and MASS. However, it also states that Curbs shall be of the MASS Curb Type 1 (barrier). AMC Title 21.080.050.G.1 allows for MASS Type 2 (rolled curb) but only for residential minor streets with 500 ADT. Since Quinhagak Street has more than 500 ADT a variance requesting relief from the Type 1 (barrier) curb requirement could be required from the Municipal Traffic Engineer.

### **B. MOA DCM**

The proposed variances from the DCM for this project will be justified and approved under a separate document during the design process. There are several design criteria that may not be able to meet the DCM. Below is a list of potential variances for this project for the preferred alternative. Additional variances may be required as the design progresses:

- Sidewalk Requirements – The DCM Figure 1-13 requires sidewalks on both sides of a local roadway. AMC Title 21 21.070.060.E.2 requires sidewalks on both sides of a local residential roadway but only one sidewalk along industrial/commercial roadways that don't connect to existing sidewalks on both ends. A variance will be required for installing only one sidewalk along Quinhagak Street from E. 64<sup>th</sup> Avenue to Askeland Drive.
- Curb Type – DCM Section 1.9.F requires Type 2 (rolled) curb on local roadways. Type 1 (barrier) curb is recommended along the east side of the roadway where the sidewalk is proposed. A variance will be required for installing Type 1 curb.
- Driveway Width – the DCM allows for driveway widths (up to 7-plexes) of 28 feet, with restrictions; commercial driveways can be up to 34 feet wide. Some of the existing driveways exceed these maximum widths and will require a variance.
- Driveway Curb Cuts – Driveway curb cuts are only allowed at residential driveways that access up to 7-plexes. Commercial driveways including 8-plexes or greater require curb returns. To maintain the flow line of the curb across the driveway to promote positive drainage to the drainage structures and match the current layout which no driveway has curb returns currently, Type 2 curb or driveway curb cuts are proposed for all driveways. A variance will be required for providing curb cuts to commercial driveways.
- Driveway landings and grades – The DCM requires that residential driveways have a minimum 12-foot landing length and a maximum grade of  $\pm 12\%$ ; commercial driveways must have a 20-foot landing length or 30-foot landing length for semi-tractors or trailers with a maximum driveway grade of  $\pm 8\%$ . The grade of the landings must be 2% maximum. Some of the driveways will not be able to meet these landing or grade requirements due to existing infrastructure/grades and will require a variance.
- Driveway Corner Clearance – The DCM recommends that the minimum distance from the nearest face of curb of an intersecting public roadway to the nearest edge of driveway is 40 feet for a local roadway (with less than 10 vehicles per hour). A few existing driveways do

not currently meet this requirement. Driveways will typically be replaced in the same location because existing improvements on property restrict relocating the driveways. A variance from not adhering to the driveway corner clearance requirements will be required.

**\*\*\* End Report \*\*\***

Existing Utilities Drawings



# Appendix A



## Roadway Plan & Profile Drawings

# Appendix B

File: I:\LabData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Roadway - Alternative 2.dwg



**RECORD DRAWING**

1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.

CONTRACTOR: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.

DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV.	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							

**CRW ENGINEERING GROUP, LLC**

3940 ARCTIC BLVD. SUITE 300  
ANCHORAGE, ALASKA 99503  
PHONE: (907) 562-3252  
FAX: (907) 562-3252

SEAL



**PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT**

21-13 QUINHAGAK STREET RECONSTRUCTION SCHED A

**ROADWAY PLAN & PROFILE**

QUINHAGAK STREET - BOP TO STA 14+60

SCALE: HOR. 1"=20' VER. 1"=5'


GRID: SW2033

DATE: NOV 2023


STATUS: DSR

SHEET: B1.1 of B1.3

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Roadway - Alternative 2.dwg



ALTERNATIVE #2



**RECORD DRAWING**

1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.

CONTRACTOR: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.

DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV.	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							

**CRW ENGINEERING GROUP, LLC**

3940 ARCTIC BLVD. SUITE 300  
ANCHORAGE, ALASKA 99503  
PHONE: (907) 562-3252  
FAX: (907) 562-3252

CONSULTANT



**PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT**

21-13 QUINHAGAK STREET RECONSTRUCTION SCHED A

**ROADWAY PLAN & PROFILE**


QUINHAGAK STREET - STA 14+60 TO STA 19+60

SCALE: HOR. 1"=20'  
VER. 1"=5'


GRID: SW2033  
DATE: NOV 2023  
STATUS: DSR

SHEET B1.2 of B1.3

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 Civil\10155.00 Plan & Profile - Roadway - Alternative 2.dwg



ALTERNATIVE #2



**RECORD DRAWING**

1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.

CONTRACTOR: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.

DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							
CONSULTANT							
SEAL							

**CRW**  
ENGINEERING GROUP, LLC

3940 ARCTIC BLVD. SUITE 300  
ANCHORAGE, ALASKA 99503  
PHONE: (907) 562-3252  
FAX: (907) 562-3252



**PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT**

21-13 QUINHAGAK STREET RECONSTRUCTION SCHED A


**ROADWAY PLAN & PROFILE**

QUINHAGAK STREET - STA 19+60 TO EOP

SCALE HOR. 1"=20'  
VER. 1"=5'


GRID SW2033  
DATE NOV 2023 STATUS DSR SHEET B1.3 of B1.3

ALTERNATIVE #3  
*PREFERRED ALTERNATIVE*




PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT				
21-13		QUINHAGAK STREET RECONSTRUCTION		SCHED A
ROADWAY PLAN & PROFILE				
QUINHAGAK STREET – BOP TO STA 14+60				
SCALE	HOR. 1"=20'	GRID SW2033		SHEET <b>B2.1</b> of <b>B2.5</b>
	VER. 1"=5'	DATE NOV 2023	STATUS DSR	

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Roadway - Alternative 3.dwg



ALTERNATIVE #3  
**PREFERRED ALTERNATIVE**



**RECORD DRAWING**  
1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.  
CONTRACTOR: \_\_\_\_\_  
BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_  
2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.  
DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK


FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							

**CRW ENGINEERING GROUP, LLC**  
3940 ARCTIC BLVD. SUITE 300  
ANCHORAGE, ALASKA 99503  
PHONE: (907) 562-3252  
FAX: (907) 562-3252




PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT					
21-13		QUINHAGAK STREET RECONSTRUCTION		SCHED A	
ROADWAY PLAN & PROFILE					
QUINHAGAK STREET - STA 14+60 TO STA 19+60					
SCALE		GRID SW2033		B2.2 of B2.5	
HOR. 1"=20'		DATE NOV 2023		SHEET	
VER. 1"=5'		STATUS DSR			

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Roadway - Alternative 3.dwg



ALTERNATIVE #3  
PREFERRED ALTERNATIVE



**RECORD DRAWING**  
1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.  
CONTRACTOR: \_\_\_\_\_  
BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_  
2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.  
DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							

GRAPHIC SCALE: 40 20 0 20 40



**CRW**  
ENGINEERING GROUP, LLC

3940 ARCTIC BLVD. SUITE 300  
ANCHORAGE, ALASKA 99503  
PHONE: (907) 562-3252  
#AEC0882-AK





PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT					
21-13		QUINHAGAK STREET RECONSTRUCTION		SCHED A	
ROADWAY PLAN & PROFILE					
QUINHAGAK STREET - STA 19+60 TO EOP					
SCALE		HOR. 1"=20'		VER. 1"=5'	
		GRID SW2033		DATE NOV 2023	
		STATUS DSR		SHEET	
				B2.3 of B2.5	

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Roadway - Sidestreets- Alternative 3.dwg



ALTERNATIVE #3  
PREFERRED ALTERNATIVE



**RECORD DRAWING**

1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.

CONTRACTOR: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.


DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							



**PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT**

21-13 QUINHAGAK STREET RECONSTRUCTION SCHED A

**ROADWAY PLAN & PROFILE**


ASKELAND DRIVE & E. 64TH AVENUE

SCALE HOR. 1"=20'  
VER. 1"=5'


GRID SW2033

DATE NOV 2023 STATUS DSR

SHEET B2.4 of B2.5



ALTERNATIVE #3  
*PREFERRED ALTERNATIVE*



**RECORD DRAWING**  
1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.  
CONTRACTOR: \_\_\_\_\_  
BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_  
2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.  
DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE		
TOPOGRAPHY		
PROFILE		
STORM SEWER		
WATER/SANITARY SEWER		
GAS		
TELEPHONE		
ELECTRIC		
DESIGN		
QUANTITIES		
PRELIMINARY/FINAL		
MUNICIPAL/STATE		

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
GRAPHIC SCALE 40 20 0 20 40							
PLAN CHECK CONSTRUCTION RECORD VERTICAL DATUM REVISIONS							




PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT					
21-13		QUINHAGAK STREET RECONSTRUCTION		SCHED A	
ROADWAY PLAN & PROFILE					
E. 63RD AVENUE					
SCALE HOR. 1"=20' VER. 1"=5'		GRID SW2033 DATE NOV 2023		STATUS DSR	
				SHEET B2.5 of B2.5	

Storm Drain Plan & Profile Drawings


# Appendix C

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Storm Drain - Alternative 2.dwg



MATCH LINE - STA 14+60

ALTERNATIVE #2



**RECORD DRAWING**

1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.  
CONTRACTOR: \_\_\_\_\_  
BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.  
DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
BY: \_\_\_\_\_


DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							




PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT			
21-13	QUINHAGAK STREET RECONSTRUCTION		SCHED B
STORM DRAIN PLAN & PROFILE			
QUINHAGAK STREET - BOP TO STA 14+60			
SCALE	HOR. 1"=20' VER. 1"=5'	GRID SW2033 DATE NOV 2023	STATUS DSR
SHEET			C1.1 of C1.3

File: I:\LabData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Storm Drain - Alternative 2.dwg




ALTERNATIVE #2



**RECORD DRAWING**  
1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.  
CONTRACTOR: \_\_\_\_\_  
BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_  
2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.  
DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
BY: \_\_\_\_\_


DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV.	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							




PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT				
21-13		QUINHAGAK STREET RECONSTRUCTION		SCHED B
STORM DRAIN PLAN & PROFILE				
QUINHAGAK STREET - STA 14+60 TO STA 19+60				
SCALE	HOR. 1"=20'	GRID SW2033		C1.2 of C1.3
	VER. 1"=5'	DATE NOV 2023	STATUS DSR	
SHEET				

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 Civil\10155.00 Plan & Profile - Storm Drain - Alternative 2.dwg



ALTERNATIVE #2



**RECORD DRAWING**

1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.

CONTRACTOR: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.


DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							



**PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT**


21-13 QUINHAGAK STREET RECONSTRUCTION SCHED B

**STORM DRAIN PLAN & PROFILE**


QUINHAGAK STREET - STA 19+60 TO EOP

SCALE HOR. 1"=20' VER. 1"=5'

GRID SW2033 DATE NOV 2023 STATUS DSR SHEET C1.3 of C1.3



ALTERNATIVE #3  
**PREFERRED ALTERNATIVE**



**RECORD DRAWING**  
1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.  
CONTRACTOR: \_\_\_\_\_  
BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_  
2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.  
DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK


FIELD BOOKS		BM NO.	LOCATION	ELEV.	REV.	DATE	DESCRIPTION	BY
DESIGN								
STAKING								
ASBUILT								
CONTRACTOR								
INSPECTOR								
BASIS OF THIS DATUM								
PLAN CHECK			CONSTRUCTION RECORD			VERTICAL DATUM		
						REVISIONS		
						CONSULTANT		
						SEAL		

**CRW ENGINEERING GROUP, LLC**  
3940 ARCTIC BLVD. SUITE 300  
ANCHORAGE, ALASKA 99503  
PHONE: (907) 562-3252  
FAX: (907) 562-3252




PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT			
21-13	QUINHAGAK STREET RECONSTRUCTION		SCHED B
STORM DRAIN PLAN & PROFILE			
QUINHAGAK STREET – BOP TO STA 14+60			
SCALE	HOR. 1"=20'	GRID SW2033	C2.1 of C2.3
	VER. 1"=5'	DATE NOV 2023	
		STATUS DSR	SHEET

File: I:\LabData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Storm Drain - Alternative 3.dwg



ALTERNATIVE #3  
**PREFERRED ALTERNATIVE**



**RECORD DRAWING**  
1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.  
CONTRACTOR: \_\_\_\_\_  
BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_  
2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.  
DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_  
COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_  
BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK



GRAPHIC SCALE 40 20 0 20 40					
FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE
DESIGN					
STAKING					
ASBUILT					
CONTRACTOR					
INSPECTOR					
BASIS OF THIS DATUM					
PLAN CHECK					
CONSTRUCTION RECORD					
VERTICAL DATUM					
REVISIONS					

**CRW ENGINEERING GROUP, LLC**  
3940 ARCTIC BLVD. SUITE 300  
ANCHORAGE, ALASKA 99503  
PHONE: (907) 562-3252  
FAX: (907) 562-3253



PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT			
21-13	QUINHAGAK STREET RECONSTRUCTION		SCHED B
STORM DRAIN PLAN & PROFILE			
QUINHAGAK STREET - STA 14+60 TO STA 19+60			
SCALE	HOR. 1"=20'	GRID SW2033	C2.2 of C2.3 SHEET
	VER. 1"=5'	DATE NOV 2023	
STATUS DSR			

File: I:\JobData\10155.00 Quinhagak Street Reconstruction\00 CADD 2019\01 Working Set\01 CADD\10155.00 Plan & Profile - Storm Drain - Alternative 3.dwg



**RECORD DRAWING**

1. DATA PROVIDED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

THIS WILL SERVE TO CERTIFY THAT THESE RECORD DRAWINGS ARE A TRUE AND ACCURATE REPRESENTATION OF THE PROJECT AS CONSTRUCTED.

CONTRACTOR: \_\_\_\_\_

BY: \_\_\_\_\_ TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

2. DATA TRANSFERRED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

3. BASED ON PERIODIC FIELD OBSERVATIONS BY THE ENGINEER (OR AN INDIVIDUAL UNDER HIS/HER DIRECT SUPERVISION), THE CONTRACTOR-PROVIDED DATA APPEARS TO REPRESENT THE PROJECT AS CONSTRUCTED.


DATA TRANSFER CHECKED BY: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_ DATE: \_\_\_\_\_

BY: \_\_\_\_\_

DATA	DRAWN BY	CHECKED BY
BASE	CB	BW
TOPOGRAPHY	CB	BW
PROFILE	RB	JK
STORM SEWER	KW	JH
WATER/SANITARY SEWER	CK	JK
GAS	CB	BW
TELEPHONE	CB	BW
ELECTRIC	JH	TK
DESIGN	RB	JK
QUANTITIES	RB	JK
PRELIMINARY/FINAL	RB	JK
MUNICIPAL/STATE	RB	JK

FIELD BOOKS	BM NO.	LOCATION	ELEV.	REV	DATE	DESCRIPTION	BY
DESIGN							
STAKING							
ASBUILT							
CONTRACTOR							
INSPECTOR							
BASIS OF THIS DATUM							
PLAN CHECK							
CONSTRUCTION RECORD							
VERTICAL DATUM							
REVISIONS							



**PROJECT MANAGEMENT AND ENGINEERING DEPARTMENT**

21-13 QUINHAGAK STREET RECONSTRUCTION SCHED B

**STORM DRAIN PLAN & PROFILE**

QUINHAGAK STREET - STA 19+60 TO EOP

SCALE HOR. 1"=20'  
VER. 1"=5'

GRID SW2033  
DATE NOV 2023 STATUS DSR

C2.3 of C2.3  
SHEET

CCTV Pipeline Inspection Report from MOA  
Street Maintenance Department

# Appendix D



# Municipality of Anchorage

Maintenance & Operations Department

Street Maintenance Division

Stormwater Drainage System (SDS)

## SDS CCTV PIPELINE & STRUCTURE INSPECTIONS

### OPERATOR'S REPORT

Performed By: Ryan A Frise

Supervisor Review: Steven N. Rupp

PM&E Project: 21-13

CCTV Request: #22-14

Project Name: Quinhagak Street Upgrade-E Dowling Road to Askeland Drive


Requested From: Ryan Kim, P.E.

Completion Date: 9/7/2022

### Inspection Information


#### Summary

This inspection consists of seven pipes to be inspected on Quinhagak between Askeland and 63<sup>rd</sup>



**Asset 38980 – 18" CPEP –**

This inspection was performed against the flow from the structure 2033-359 this pipe appears to be in fair condition with normal function and grade. This inspection noted **multiple areas of infiltration**. This survey noted **deformed** areas in the pipe approx. 8', 129', and 210' in pipe. This main is approx. 300' in length. *Pictured to the right is the DUC flat image of the entire pipe run of this asset. Highlighted in yellow indicated the two more prominent deformities. Red lines indicate the more prominent joint infiltration.*




**Asset 38981 – 18" CPEP –** This inspection was performed with the flow from structure 2033-359 This pipe appears to be in good working condition with normal function and grade. This inspection noted **minor infiltration**. This survey noted **deformed** areas approx. 7', 26' in pipe. This main is approx. 46' in length. *Pictured to the right is a snippet of the DUC video at 6.5' showing a deformity prior to any cracking. Appears predisposed to hinge fracturing in the CPEP at 3 and 6 o'clock positions.*



**Asset 10259 – 18" CMP –** This inspection was performed with the flow from structure 2033-048. This pipe was found with **heavy deposits**; the camera was unable to proceed to complete inspection. There was a small joint separation visible. A reversal was attempted, similar presents of deposits was noted. A **separation with soil visible** was noted. This **survey was abandoned**, camera could not proceed through deposits. The length of this main is approx. and undetermined.

*Pictured to the right is a screenshot of the DUC video footage upon camera launch where the survey had to be abandoned of the DS attempt.*



*Pictured to the left is a screenshot of the DUC video footage of the reversal attempt headed against the flow. Also abandoned survey on this reversal attempt due to heavy deposits just downstream of the broken/separated pipe (with soil visible).*


**Asset 19737** – 10" CMP – This inspection was performed Upstream from structure 2033-048 This pipe was found with **heavy deposits**. This **survey was abandoned**, camera was unable to proceed to complete inspection. The length of this pipe is approx. and undetermined.

*Pictured to the right is a screenshot of the TV footage at 6' into the assessment where the survey was abandoned due to heavy deposits in the pipe.*



**Asset 26454** – 15" CMP – This inspection was performed against the flow from structure 2033-048 This **survey was abandoned heavy deposits** noted, camera was unable to proceed. The length of this pipe is approx. and undetermined.


*Pictured to the right is a screenshot of the TV footage 0' into the assessment where the DUC and transporter were unable to be launched due to severe deposits in the pipe. The pipe is surcharged in this photo.*



**Asset 33051** – 36" CMP – This inspection was performed Upstream from structure 2033-050 This pipe appears to be in good condition with normal function and grade. The inspection noted **joint separation** approx. 136' and 197' with **light infiltration**. This survey noted the pipe was **deformed** approx. 200' in pipe. This main is approx. 220' in length.

**Asset 26756** – 48" CMP – This inspection was performed Downstream from structure 2033-050. This pipe appears to be in good working condition with normal function and grade. This inspection noted the pipe was **deformed** in multiple areas approx. 13', 32', 106', and 200'. This survey noted **joint separation** near the Downstream structure. This **separation occurs in the flow line obstructing flow**. This main is approx. 218' in length.

*Pictured to the right is a screenshot of the TV footage 12.5' into the assessment where the deformities and small sags are visible in the CMP. This defect was the most notable from reviewing the footage.*




### **Additional Information**

The mains at Askeland and Quinhagak have heavy sediment with minimal flow. The integrity of the pipes is undetermined due to being unable to view under the water level and sediment in the assessments as well as being unable to run the transporter through the entirety of the pipe. The structures entered and viewed during the inspections appeared to be in fair condition. Pipes downstream from the requested assessments were visibly surcharged from a surface manhole assessment done previously showing that the further you proceed downstream the more surcharged the system is on a high level overview.

Storm Drain Modeling Data

# Appendix E

File Path: J:\JobsData\10155\_00 Quinhagak Street Reconstruction\00 CADD 2019\04 GIS\07 HH Working\Figure1\_BasinMap.aprx



W IZW :Wp:} ' i pññXii YµVZ P I ^i ° i Z ° }v' i µ }vpñi ~ ñiõpiõ '/^piõ .. t µ ]vPpYµVZ P I z^ }o' D pYµVZ P I z^ }o' D X µ Æ

,Ç^„}o}P] ^}}o' „}µ„'




K



ïõðì Z d/ > s' X ^h/d' ñi  
E ,KZ 'U > ^< ððñi  
W,KE" ~ðio ñòir iñi  
~ >ððir <

,z~ZK>K'/ ^K/> 'ZKhW^  
Yh/E, ' < ^dZ""d Z" KE^dZh d/KE r "X ~Kt>/E' Z  
DK WDÿ" WZK:" d ·îirîi  
E ,KZ 'U > ^<


W„}i° iWiiññXii  
~ „ Äv ÇW <~t  
X o dK ^s ~ E°  
~ i°W NOV 2023  
&]Pµ„°W î




**OROGRAPHIC FACTOR MAP (ANCHORAGE)**

**FIGURE 3**

File Path: J:\JobsData\10155-00 Quinhagak Street Reconstruction\00 CADD 2019\04 GIS\07 HH Working\Figure4.aprx



File Path: J:\JobsData\10155-00 Quinhagak Street Reconstruction\00 CADD 2019\04 GIS\07 HH Working\Figure5.aprx



## Existing Stormwater System SSA Report & Results

Project Description

File Name ..... Quinhagak\_SSA\_Existing.SPF

Project Options

Flow Units ..... CFS  
Elevation Type ..... Elevation  
Hydrology Method ..... SCS TR-55  
Time of Concentration (TOC) Method ..... SCS TR-55  
Link Routing Method ..... Hydrodynamic  
Enable Overflow Ponding at Nodes ..... YES  
Skip Steady State Analysis Time Periods ..... NO

Analysis Options

Start Analysis On ..... 00:00:00      0:00:00  
End Analysis On ..... 00:00:00      0:00:00  
Start Reporting On ..... 00:00:00      0:00:00  
Antecedent Dry Days ..... 0      days  
Runoff (Dry Weather) Time Step ..... 0 01:00:00      days hh:mm:ss  
Runoff (Wet Weather) Time Step ..... 0 00:05:00      days hh:mm:ss  
Reporting Time Step ..... 0 00:05:00      days hh:mm:ss  
Routing Time Step ..... 30      seconds

Number of Elements

Qty  
Rain Gages ..... 1  
Subbasins..... 16  
Nodes..... 28  
    *Junctions* ..... 15  
    *Outfalls* ..... 2  
    *Flow Diversions* ..... 0  
    *Inlets* ..... 10  
    *Storage Nodes* ..... 1  
Links..... 36  
    *Channels* ..... 10  
    *Pipes* ..... 26  
    *Pumps* ..... 0  
    *Orifices* ..... 0  
    *Weirs* ..... 0  
    *Outlets* ..... 0  
Pollutants ..... 0  
Land Uses ..... 0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
1	MOA	Time Series	MOA Design Storm Distribution	Cumulative	inches				0.00	

Subbasin Summary

SN	Subbasin ID	Area	Peak Rate	Weighted Curve	Total Rainfall	Total Runoff	Total Runoff	Peak Runoff	Time of Concentration
		(ac)	Factor	Number	(in)	(in)	Volume (ac-in)	(cfs)	(days hh:mm:ss)
1	B-2033-022	1.06	484.00	75.00	2.46	0.63	0.67	0.21	0 00:36:45
2	B-2033-049	0.33	484.00	75.00	2.46	0.63	0.20	0.14	0 00:06:00
3	B-2033-082	3.35	484.00	88.00	2.46	1.35	4.52	2.26	0 00:19:09
4	B-2033-083	0.64	484.00	88.00	2.46	1.35	0.86	0.48	0 00:15:12
5	B-2033-084	1.27	484.00	88.00	2.46	1.35	1.71	0.72	0 00:27:12
6	B-2033-085	12.55	484.00	88.00	2.46	1.35	16.93	6.90	0 00:28:50
7	B-2033-086	0.88	484.00	88.00	2.46	1.35	1.18	0.62	0 00:17:07
8	B-2033-087	5.84	484.00	92.00	2.46	1.66	9.68	4.06	0 00:26:47
9	B-2033-088	1.19	484.00	92.00	2.46	1.66	1.97	0.90	0 00:22:50
10	B-2033-101	1.04	484.00	88.00	2.46	1.35	1.40	0.76	0 00:16:18
11	B-2033-116	1.11	484.00	92.00	2.46	1.66	1.84	0.75	0 00:28:26
12	B-2033-144	0.69	484.00	92.00	2.46	1.66	1.15	0.55	0 00:20:37
13	B-2033-341	0.39	484.00	89.00	2.46	1.42	0.55	0.20	0 00:37:05
14	B-2033-342	4.60	484.00	88.00	2.46	1.35	6.21	2.48	0 00:30:00
15	B-2033-360	0.37	484.00	92.00	2.46	1.66	0.61	0.28	0 00:23:14
16	B-2033-369	1.97	484.00	88.00	2.46	1.35	2.66	1.29	0 00:20:17

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	S-2033-045	Junction	118.66	124.60	118.66	0.00	0.00	0.31	119.03	0.00	6.04	0 00:00	0.00	0.00
2	S-2033-048	Junction	119.01	126.73	119.01	0.00	0.00	0.31	120.02	0.00	6.71	0 00:00	0.00	0.00
3	S-2033-051	Junction	119.93	131.82	119.93	0.00	0.00	9.36	121.39	0.00	10.43	0 00:00	0.00	0.00
4	S-2033-101	Junction	122.24	136.78	122.24	0.00	0.00	0.72	123.38	0.00	13.40	0 00:00	0.00	0.00
5	S-2033-110	Junction	126.34	136.07	126.34	0.00	0.00	4.56	136.07	0.00	0.00	0 12:16	0.00	0.00
6	S-2033-111	Junction	130.03	140.14	130.03	0.00	0.00	2.89	140.14	0.00	0.00	0 12:20	0.09	15.00
7	S-2033-112	Junction	132.85	142.82	132.85	0.00	0.00	1.37	140.15	0.00	2.67	0 00:00	0.00	0.00
8	S-2033-143	Junction	125.92	136.25	125.92	0.00	0.00	2.37	136.13	0.00	0.12	0 00:00	0.00	0.00
9	S-2033-144	Junction	128.23	136.00	128.23	0.00	0.00	2.11	136.00	0.00	0.00	0 12:20	1.03	54.00
10	S-2033-341	Junction	123.72	130.72	123.72	0.00	0.00	0.20	125.29	0.00	5.43	0 00:00	0.00	0.00
11	S-2033-342	Junction	124.26	131.49	124.26	0.00	0.00	2.47	126.18	0.00	5.31	0 00:00	0.00	0.00
12	S-2033-359	Junction	129.79	137.01	129.79	0.00	0.00	1.61	136.11	0.00	0.89	0 00:00	0.00	0.00
13	S-2033-360	Junction	131.80	140.54	131.80	0.00	0.00	1.75	140.53	0.00	0.00	0 12:09	0.00	0.00
14	S-2033-368	Junction	123.52	134.20	123.52	0.00	0.00	4.01	133.62	0.00	0.58	0 00:00	0.00	0.00
15	S-2033-369	Junction	124.66	135.06	124.66	0.00	10.00	1.29	133.69	0.00	1.37	0 00:00	0.00	0.00
16	Outfall-64th	Outfall	120.20					9.33	121.12					
17	Outfall-Askeland	Outfall	118.62					0.31	118.95					
18	S-2033-050	Storage Node	121.56	131.74	121.56		0.00	8.41	122.74				0.00	0.00

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Reported Surcharged	Condition
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)		(min)	
1	P-022-048	Pipe	I-2033-022	S-2033-048	29.40	122.60	121.26	4.5600	10.000	0.0240	0.27	2.53	0.11	2.94	0.19	0.23	0.00	Calculated
2	P-048-045	Pipe	S-2033-048	S-2033-045	258.54	119.73	118.66	0.4100	18.000	0.0240	0.31	3.66	0.08	1.07	0.33	0.22	0.00	Calculated
3	P-049-048	Pipe	I-2033-049	S-2033-048	35.04	122.60	121.23	3.9100	10.000	0.0240	0.12	2.35	0.05	2.20	0.13	0.15	0.00	Calculated
4	P-050-051	Pipe	S-2033-050	S-2033-051	217.73	122.06	120.38	0.7700	38.000	0.0240	8.41	62.17	0.14	2.61	0.84	0.27	0.00	Calculated
5	P-050-082	Pipe	I-2033-082	S-2033-050	41.71	126.85	122.41	10.6600	10.000	0.0240	1.27	3.87	0.33	6.07	0.34	0.41	0.00	Calculated
6	P-050-101	Pipe	S-2033-050	S-2033-101	232.53	122.41	122.89	-0.2100	36.000	0.0240	0.73	19.79	0.04	1.26	0.41	0.14	0.00	Calculated
7	P-050-341	Pipe	S-2033-050	S-2033-341	40.80	122.41	125.19	-6.8300	12.000	0.0120	0.20	10.08	0.02	2.86	0.21	0.21	0.00	Calculated
8	P-060-342	Pipe	S-2033-050	S-2033-342	35.05	122.41	125.67	-9.3100	12.000	0.0240	2.47	5.89	0.42	6.65	0.48	0.48	0.00	Calculated
9	P-083-110	Pipe	I-2033-083	S-2033-110	18.00	131.89	130.68	6.7200	10.000	0.0240	0.80	3.08	0.26	2.53	0.83	1.00	111.00	SURCHARGED
10	P-084-110	Pipe	I-2033-084	S-2033-110	42.97	132.19	128.64	8.2500	10.000	0.0240	1.83	3.41	0.54	4.39	0.83	1.00	110.00	SURCHARGED
11	P-085-110	Pipe	I-2033-085	S-2033-110	38.71	132.06	130.10	5.0600	10.000	0.0240	2.03	2.67	0.76	20.94	0.83	1.00	113.00	SURCHARGED
12	P-086-111	Pipe	I-2033-086	S-2033-111	14.99	136.64	134.30	15.6100	10.000	0.0240	0.79	4.69	0.17	4.88	0.83	1.00	39.00	SURCHARGED
13	P-087-111	Pipe	I-2033-087	S-2033-111	11.20	136.11	134.30	16.1600	10.000	0.0240	2.14	4.77	0.45	8.09	0.83	1.00	58.00	SURCHARGED
14	P-088-112	Pipe	I-2033-088	S-2033-112	15.18	138.44	137.34	7.2400	1.000	0.0240	0.02	0.01	2.19	2.76	0.08	1.00	1150.00	SURCHARGED
15	P-110-368	Pipe	S-2033-110	S-2033-368	113.90	126.74	125.11	1.4300	12.000	0.0240	3.41	2.31	1.48	4.34	1.00	1.00	243.00	SURCHARGED
16	P-111-143	Pipe	S-2033-111	S-2033-143	259.46	130.54	127.43	1.2000	12.000	0.0240	2.37	2.11	1.12	3.02	1.00	1.00	143.00	SURCHARGED
17	P-112-111	Pipe	S-2033-112	S-2033-111	255.00	133.56	130.64	1.1500	12.000	0.0240	1.34	2.07	0.65	1.70	1.00	1.00	100.00	SURCHARGED
18	P-116-112	Pipe	I-2033-116	S-2033-112	12.67	138.52	137.60	7.2600	1.000	0.0240	0.02	0.01	2.33	2.95	0.08	1.00	1139.00	SURCHARGED
19	P-143-110	Pipe	S-2033-143	S-2033-110	45.46	127.24	126.78	1.0100	14.000	0.0240	1.29	2.93	0.44	1.61	1.17	1.00	204.00	SURCHARGED
20	P-144-143	Pipe	S-2033-144	S-2033-143	29.35	129.78	129.58	0.6800	12.000	0.0120	1.56	3.19	0.49	1.99	1.00	1.00	148.00	SURCHARGED
21	P-359-110	Pipe	S-2033-359	S-2033-110	46.47	130.80	130.42	0.8200	18.000	0.0120	1.61	10.29	0.16	1.54	1.50	1.00	117.00	SURCHARGED
22	P-360-359	Pipe	S-2033-360	S-2033-359	296.33	133.50	130.85	0.9000	18.000	0.0120	1.61	10.77	0.15	1.68	1.50	1.00	78.00	SURCHARGED
23	P-368-050	Pipe	S-2033-368	S-2033-050	234.41	125.11	122.41	1.1500	12.000	0.0240	4.01	2.07	1.94	5.29	0.92	0.92	0.00	> CAPACITY
24	P-369-368	Pipe	S-2033-369	S-2033-368	24.40	126.32	125.32	4.1000	12.000	0.0120	1.29	7.81	0.16	1.64	1.00	1.00	182.00	SURCHARGED
25	P-Outfall1	Pipe	S-2033-051	Outfall-64th	59.86	120.38	120.20	0.3000	38.000	0.0240	9.33	38.81	0.24	2.45	0.96	0.30	0.00	Calculated
26	P-Outfall2	Pipe	S-2033-045	Outfall-Askeland	25.21	118.66	118.62	0.1600	16.000	0.0240	0.31	2.28	0.13	1.04	0.35	0.26	0.00	Calculated
27	022-Bypass	Channel	I-2033-022	I-2033-049	62.37	122.60	121.10	2.4100	5.640	0.0320	0.00	53.96	0.00	0.01	0.24	0.52	0.00	
28	049-Bypass	Channel	I-2033-049	S-2033-045	226.83	126.59	124.60	0.8800	5.640	0.0320	0.01	17.64	0.00	1.11	0.03	0.07	0.00	
29	082-Bypass	Channel	I-2033-082	S-2033-051	189.59	131.23	129.28	1.0300	5.640	0.0320	1.00	19.10	0.05	2.69	0.19	0.41	0.00	
30	083-Bypass	Channel	I-2033-083	I-2033-082	345.58	136.10	131.23	1.4100	5.640	0.0320	0.03	22.36	0.00	1.66	0.06	0.12	0.00	
31	084-Bypass	Channel	I-2033-084	I-2033-022	475.80	135.57	127.00	1.8000	5.640	0.0320	0.08	25.28	0.00	4.43	0.08	0.16	0.00	
32	085-Bypass	Channel	I-2033-085	I-2033-084	81.18	136.39	135.57	1.0100	5.640	0.0320	4.50	18.93	0.24	2.49	0.39	0.83	0.00	
33	086-Bypass	Channel	I-2033-086	I-2033-083	312.43	140.72	136.10	1.4800	5.640	0.0320	0.04	22.90	0.00	2.61	0.06	0.12	0.00	
34	087-Bypass	Channel	I-2033-087	I-2033-085	275.03	140.42	136.39	1.4700	5.640	0.0320	2.31	22.80	0.10	2.69	0.35	0.74	0.00	
35	088-Bypass	Channel	I-2033-088	I-2033-086	260.08	142.83	140.72	0.8100	5.640	0.0320	0.22	16.96	0.01	2.28	0.13	0.27	0.00	
36	116-Bypass	Channel	I-2033-116	I-2033-087	260.51	142.84	140.42	0.9300	5.640	0.0320	0.16	18.13	0.01	2.13	0.23	0.49	0.00	

Inlet Summary

SN	Element	Inlet	Manufacturer	Inlet	Number of	Catchbasin	Max (Rim)	Initial	Ponded	Peak	Peak Flow	Peak Flow	Inlet	Allowable	Max Gutter	Max Gutter
ID		Manufacturer	Part	Location	Inlets	Invert	Elevation	Water	Area	Flow	Intercepted	Bypassing	Efficiency	Spread	Spread	Water Elev.
			Number			Elevation		Elevation			by	Inlet	during Peak		during Peak	during Peak
						(ft)	(ft)	(ft)	(ft²)	(cfs)	Inlet	(cfs)	Flow	(ft)	Flow	Flow
											(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)
1	I-2033-022	FHWA HEC-22 GENERIC	N/A	On Grade	1	121.92	127.00	121.92	N/A	0.21	0.21	0.00	99.99	7.00	1.48	127.12
2	I-2033-049	FHWA HEC-22 GENERIC	N/A	On Grade	1	121.88	126.59	121.88	N/A	0.12	0.12	0.00	100.00	7.00	1.63	126.69
3	I-2033-082	FHWA HEC-22 GENERIC	N/A	On Grade	1	126.31	131.23	126.31	N/A	2.24	1.24	1.00	55.48	7.00	8.36	131.52
4	I-2033-083	FHWA HEC-22 GENERIC	N/A	On Grade	1	131.19	136.10	131.19	N/A	0.46	0.24	0.22	52.67	7.00	2.26	136.15
5	I-2033-084	FHWA HEC-22 GENERIC	N/A	On Grade	1	132.19	135.57	132.19	N/A	0.72	0.15	0.57	20.31	7.00	2.36	135.62
6	I-2033-085	FHWA HEC-22 GENERIC	N/A	On Grade	1	131.28	136.39	131.28	N/A	6.89	2.42	4.47	35.10	7.00	14.38	136.80
7	I-2033-086	FHWA HEC-22 GENERIC	N/A	On Grade	1	136.09	140.72	136.09	N/A	0.60	0.05	0.55	8.19	7.00	2.05	140.76
8	I-2033-087	FHWA HEC-22 GENERIC	N/A	On Grade	1	135.45	140.42	135.45	N/A	4.03	0.00	4.03	0.00	7.00	8.99	140.73
9	I-2033-088	FHWA HEC-22 GENERIC	N/A	On Grade	1	137.77	142.83	137.77	N/A	0.89	0.68	0.21	76.06	7.00	5.38	143.06
10	I-2033-116	FHWA HEC-22 GENERIC	N/A	On Grade	1	137.79	142.84	137.79	N/A	0.75	0.60	0.14	80.99	7.00	4.77	143.06

Junction Input

SN	Element ID	Invert Elevation  (ft)	Ground/Rim (Max) Elevation (ft)	Ground/Rim (Max) Offset (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Surcharge Elevation (ft)	Surcharge Depth (ft)	Ponded Area (ft²)	Minimum Pipe Cover (in)
1	S-2033-045	118.66	124.60	5.94	118.66	0.00	0.00	-124.60	0.00	0.00
2	S-2033-048	119.01	126.73	7.72	119.01	0.00	0.00	-126.73	0.00	0.00
3	S-2033-051	119.93	131.82	11.89	119.93	0.00	0.00	-131.82	0.00	0.00
4	S-2033-101	122.24	136.78	14.54	122.24	0.00	0.00	-136.78	0.00	0.00
5	S-2033-110	126.34	136.07	9.73	126.34	0.00	0.00	-136.07	0.00	0.00
6	S-2033-111	130.03	140.14	10.11	130.03	0.00	0.00	-140.14	0.00	0.00
7	S-2033-112	132.85	142.82	9.97	132.85	0.00	0.00	-142.82	0.00	0.00
8	S-2033-143	125.92	136.25	10.33	125.92	0.00	0.00	-136.25	0.00	0.00
9	S-2033-144	128.23	136.00	7.77	128.23	0.00	0.00	-136.00	0.00	0.00
10	S-2033-341	123.72	130.72	7.00	123.72	0.00	0.00	-130.72	0.00	0.00
11	S-2033-342	124.26	131.49	7.23	124.26	0.00	0.00	-131.49	0.00	0.00
12	S-2033-359	129.79	137.01	7.22	129.79	0.00	0.00	-137.01	0.00	0.00
13	S-2033-360	131.80	140.54	8.74	131.80	0.00	0.00	-140.54	0.00	0.00
14	S-2033-368	123.52	134.20	10.68	123.52	0.00	0.00	-134.20	0.00	0.00
15	S-2033-369	124.66	135.06	10.40	124.66	0.00	0.00	-135.06	10.00	0.00

Junction Results

SN	Element ID	Peak Inflow	Peak Lateral Inflow	Max HGL Elevation Attained	Max HGL Depth Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Average HGL Elevation Attained	Average HGL Depth Attained	Time of Max HGL Occurrence	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
		(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:mm)	(days hh:mm)	(ac-in)	(min)
1	S-2033-045	0.31	0.00	119.03	0.37	0.00	6.04	118.79	0.13	0 12:29	0 00:00	0.00	0.00
2	S-2033-048	0.31	0.00	120.02	1.01	0.00	6.71	119.69	0.68	0 12:26	0 00:00	0.00	0.00
3	S-2033-051	9.36	0.00	121.39	1.46	0.00	10.43	120.83	0.90	0 12:21	0 00:00	0.00	0.00
4	S-2033-101	0.72	0.72	123.38	1.14	0.00	13.40	123.07	0.83	0 12:18	0 00:00	0.00	0.00
5	S-2033-110	4.56	0.00	136.07	9.73	0.00	0.00	128.25	1.91	0 12:16	0 12:16	0.00	0.00
6	S-2033-111	2.89	0.00	140.14	10.11	0.00	0.00	131.37	1.34	0 12:16	0 12:20	0.09	15.00
7	S-2033-112	1.37	0.00	140.15	7.30	0.00	2.67	133.88	1.03	0 12:16	0 00:00	0.00	0.00
8	S-2033-143	2.37	0.00	136.13	10.21	0.00	0.12	128.48	2.56	0 12:16	0 00:00	0.00	0.00
9	S-2033-144	2.11	0.55	136.00	7.77	0.00	0.00	130.36	2.13	0 12:10	0 12:20	1.03	54.00
10	S-2033-341	0.20	0.20	125.29	1.57	0.00	5.43	125.17	1.45	0 12:30	0 00:00	0.00	0.00
11	S-2033-342	2.47	2.47	126.18	1.92	0.00	5.31	125.78	1.52	0 12:25	0 00:00	0.00	0.00
12	S-2033-359	1.61	0.00	136.11	6.33	0.00	0.89	131.19	1.41	0 12:09	0 00:00	0.00	0.00
13	S-2033-360	1.75	0.28	140.53	8.74	0.00	0.00	133.64	1.85	0 12:09	0 12:09	0.00	0.00
14	S-2033-368	4.01	0.00	133.62	10.10	0.00	0.58	126.53	3.01	0 12:20	0 00:00	0.00	0.00
15	S-2033-369	1.29	1.29	133.69	9.03	0.00	1.37	126.97	2.31	0 12:20	0 00:00	0.00	0.00

Channel Input

SN	Element ID	Length	Inlet Invert Elevation	Inlet Invert Offset	Outlet Invert Elevation	Outlet Invert Offset	Total Drop	Average Slope	Shape	Height	Width	Manning's Roughness	Entrance Losses	Exit/Bend Losses	Additional Losses	Initial Flow	Flap Gate
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(%)		(ft)	(ft)					(cfs)	
1	022-Bypass	62.37	122.60	0.68	121.10	-0.78	1.50	2.4100	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
2	049-Bypass	226.83	126.59	4.71	124.60	5.94	1.99	0.8800	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
3	082-Bypass	189.59	131.23	4.92	129.28	9.35	1.95	1.0300	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
4	083-Bypass	345.58	136.10	4.91	131.23	4.92	4.87	1.4100	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
5	084-Bypass	475.80	135.57	3.39	127.00	5.08	8.57	1.8000	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
6	085-Bypass	81.18	136.39	5.11	135.57	3.39	0.82	1.0100	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
7	086-Bypass	312.43	140.72	4.63	136.10	4.91	4.62	1.4800	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
8	087-Bypass	275.03	140.42	4.97	136.39	5.11	4.03	1.4700	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
9	088-Bypass	260.08	142.83	5.06	140.72	4.63	2.11	0.8100	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No
10	116-Bypass	260.51	142.84	5.05	140.42	4.97	2.42	0.9300	User-Defined	0.470	20.500	0.0320	0.5000	0.5000	0.0000	0.00	No

Channel Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/Total Depth Ratio	Total Time Surcharged	Froude Number	Reported Condition
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)		
1	022-Bypass	0.00	0 12:30	53.96	0.00	0.01	103.95	0.24	0.52	0.00		
2	049-Bypass	0.01	0 12:10	17.64	0.00	1.11	3.41	0.03	0.07	0.00		
3	082-Bypass	1.00	0 12:19	19.10	0.05	2.69	1.17	0.19	0.41	0.00		
4	083-Bypass	0.03	0 12:15	22.36	0.00	1.66	3.47	0.06	0.12	0.00		
5	084-Bypass	0.08	0 12:25	25.28	0.00	4.43	1.79	0.08	0.16	0.00		
6	085-Bypass	4.50	0 12:25	18.93	0.24	2.49	0.54	0.39	0.83	0.00		
7	086-Bypass	0.04	0 12:19	22.90	0.00	2.61	2.00	0.06	0.12	0.00		
8	087-Bypass	2.31	0 12:24	22.80	0.10	2.69	1.70	0.35	0.74	0.00		
9	088-Bypass	0.22	0 12:20	16.96	0.01	2.28	1.90	0.13	0.27	0.00		
10	116-Bypass	0.16	0 12:25	18.13	0.01	2.13	2.04	0.23	0.49	0.00		

Pipe Input

SN	Element ID	Length	Inlet Invert	Inlet Invert	Outlet Invert	Outlet Invert	Total Drop	Average Slope	Pipe Shape	Pipe Diameter or Height	Pipe Width	Manning's Roughness	Entrance Losses	Exit/Bend Losses	Additional Losses	Initial Flow	Flap Gate	No. of Barrels
		(ft)	Elevation (ft)	Offset (ft)	Elevation (ft)	Offset (ft)	(ft)	(%)		(in)	(in)					(cfs)		
1	P-022-048	29.40	122.60	0.68	121.26	2.25	1.34	4.5600	CIRCULAR	9.960	9.960	0.0240	0.5000	0.9000	0.0000	0.00	No	1
2	P-048-045	258.54	119.73	0.72	118.66	0.00	1.07	0.4100	CIRCULAR	18.000	18.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
3	P-049-048	35.04	122.60	0.72	121.23	2.22	1.37	3.9100	CIRCULAR	9.960	9.960	0.0240	0.5000	0.9000	0.0000	0.00	No	1
4	P-050-051	217.73	122.06	0.50	120.38	0.45	1.68	0.7700	Arch	38.040	57.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
5	P-050-082	41.71	126.85	0.54	122.41	0.85	4.44	10.6600	CIRCULAR	9.960	9.960	0.0240	0.5000	1.0000	0.0000	0.00	No	1
6	P-050-101	232.53	122.41	0.85	122.89	0.65	-0.48	-0.2100	CIRCULAR	36.000	36.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
7	P-050-341	40.80	122.41	0.85	125.19	1.47	-2.79	-6.8300	CIRCULAR	12.000	12.000	0.0120	0.5000	1.0000	0.0000	0.00	No	1
8	P-060-342	35.05	122.41	0.85	125.67	1.41	-3.27	-9.3100	CIRCULAR	12.000	12.000	0.0240	0.5000	1.0000	0.0000	0.00	No	1
9	P-083-110	18.00	131.89	0.70	130.68	4.34	1.21	6.7200	CIRCULAR	9.960	9.960	0.0240	0.5000	1.0000	0.0000	0.00	No	1
10	P-084-110	42.97	132.19	0.00	128.64	2.30	3.55	8.2500	CIRCULAR	9.960	9.960	0.0240	0.5000	1.0000	0.0000	0.00	No	1
11	P-085-110	38.71	132.06	0.78	130.10	3.76	1.96	5.0600	CIRCULAR	9.960	9.960	0.0240	0.5000	1.0000	0.0000	0.00	No	1
12	P-086-111	14.99	136.64	0.55	134.30	4.27	2.34	15.6100	CIRCULAR	9.960	9.960	0.0240	0.5000	0.6000	0.0000	0.00	No	1
13	P-087-111	11.20	136.11	0.66	134.30	4.27	1.81	16.1600	CIRCULAR	9.960	9.960	0.0240	0.5000	0.6000	0.0000	0.00	No	1
14	P-088-112	15.18	138.44	0.67	137.34	4.49	1.10	7.2400	CIRCULAR	0.960	0.960	0.0240	0.5000	0.6000	0.0000	0.00	No	1
15	P-110-368	113.90	126.74	0.40	125.11	1.59	1.63	1.4300	CIRCULAR	12.000	12.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
16	P-111-143	259.46	130.54	0.51	127.43	1.51	3.10	1.2000	CIRCULAR	12.000	12.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
17	P-112-111	255.00	133.56	0.71	130.64	0.61	2.92	1.1500	CIRCULAR	12.000	12.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
18	P-116-112	12.67	138.52	0.74	137.60	4.75	0.92	7.2600	CIRCULAR	0.960	0.960	0.0240	0.5000	0.6000	0.0000	0.00	No	1
19	P-143-110	45.46	127.24	1.32	126.78	0.44	0.46	1.0100	CIRCULAR	14.040	14.040	0.0240	0.5000	0.5000	0.0000	0.00	No	1
20	P-144-143	29.35	129.78	1.55	129.58	3.66	0.20	0.6800	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
21	P-359-110	46.47	130.80	1.02	130.42	4.08	0.38	0.8200	CIRCULAR	18.000	18.000	0.0120	0.5000	1.0000	0.0000	0.00	No	1
22	P-360-359	296.33	133.50	1.71	130.85	1.06	2.66	0.9000	CIRCULAR	18.000	18.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
23	P-368-050	234.41	125.11	1.59	122.41	0.85	2.71	1.1500	CIRCULAR	12.000	12.000	0.0240	0.5000	1.0000	0.0000	0.00	No	1
24	P-369-368	24.40	126.32	1.66	125.32	1.80	1.00	4.1000	CIRCULAR	12.000	12.000	0.0120	0.5000	0.7000	0.0000	0.00	No	1
25	P-Outfall1	59.86	120.38	0.45	120.20	0.00	0.18	0.3000	Arch	38.040	57.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
26	P-Outfall2	25.21	118.66	0.00	118.62	0.00	0.04	0.1600	CIRCULAR	15.960	15.960	0.0240	0.5000	0.5000	0.0000	0.00	No	1

Pipe Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Surcharged	Froude Number	Reported Condition
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)		
1	P-022-048	0.27	0 12:25	2.53	0.11	2.94	0.17	0.19	0.23	0.00		Calculated
2	P-048-045	0.31	0 12:26	3.66	0.08	1.07	4.03	0.33	0.22	0.00		Calculated
3	P-049-048	0.12	0 12:10	2.35	0.05	2.20	0.27	0.13	0.15	0.00		Calculated
4	P-050-051	8.41	0 12:22	62.17	0.14	2.61	1.39	0.84	0.27	0.00		Calculated
5	P-050-082	1.27	0 12:20	3.87	0.33	6.07	0.11	0.34	0.41	0.00		Calculated
6	P-050-101	0.73	0 12:20	19.79	0.04	1.26	3.08	0.41	0.14	0.00		Calculated
7	P-050-341	0.20	0 12:30	10.08	0.02	2.86	0.24	0.21	0.21	0.00		Calculated
8	P-060-342	2.47	0 12:25	5.89	0.42	6.65	0.09	0.48	0.48	0.00		Calculated
9	P-083-110	0.80	0 12:09	3.08	0.26	2.53	0.12	0.83	1.00	111.00		SURCHARGED
10	P-084-110	1.83	0 12:09	3.41	0.54	4.39	0.16	0.83	1.00	110.00		SURCHARGED
11	P-085-110	2.03	0 12:09	2.67	0.76	20.94	0.03	0.83	1.00	113.00		SURCHARGED
12	P-086-111	0.79	0 12:20	4.69	0.17	4.88	0.05	0.83	1.00	39.00		SURCHARGED
13	P-087-111	2.14	0 12:25	4.77	0.45	8.09	0.02	0.83	1.00	58.00		SURCHARGED
14	P-088-112	0.02	0 06:56	0.01	2.19	2.76	0.09	0.08	1.00	1150.00		SURCHARGED
15	P-110-368	3.41	0 13:09	2.31	1.48	4.34	0.44	1.00	1.00	243.00		SURCHARGED
16	P-111-143	2.37	0 12:31	2.11	1.12	3.02	1.43	1.00	1.00	143.00		SURCHARGED
17	P-112-111	1.34	0 12:10	2.07	0.65	1.70	2.50	1.00	1.00	100.00		SURCHARGED
18	P-116-112	0.02	0 05:23	0.01	2.33	2.95	0.07	0.08	1.00	1139.00		SURCHARGED
19	P-143-110	1.29	0 13:55	2.93	0.44	1.61	0.47	1.17	1.00	204.00		SURCHARGED
20	P-144-143	1.56	0 12:20	3.19	0.49	1.99	0.25	1.00	1.00	148.00		SURCHARGED
21	P-359-110	1.61	0 12:08	10.29	0.16	1.54	0.50	1.50	1.00	117.00		SURCHARGED
22	P-360-359	1.61	0 12:08	10.77	0.15	1.68	2.94	1.50	1.00	78.00		SURCHARGED
23	P-368-050	4.01	0 12:20	2.07	1.94	5.29	0.74	0.92	0.92	0.00		> CAPACITY
24	P-369-368	1.29	0 12:20	7.81	0.16	1.64	0.25	1.00	1.00	182.00		SURCHARGED
25	P-Outfall1	9.33	0 12:21	38.81	0.24	2.45	0.41	0.96	0.30	0.00		Calculated
26	P-Outfall2	0.31	0 12:29	2.28	0.13	1.04	0.40	0.35	0.26	0.00		Calculated

Inlet Input

SN	Element ID	Inlet Manufacturer	Manufacturer Part Number	Inlet Location	Number of Inlets	Catchbasin Invert Elevation (ft)	Max (Rim) Elevation (ft)	Inlet Depth (ft)	Initial Water Elevation (ft)	Initial Water Depth (ft)	Ponded Area (ft²)	Grate Clogging Factor (%)
1	I-2033-022	FHWA HEC-22 GENERIC	N/A	On Grade	1	121.92	127.00	5.08	121.92	0.00	N/A	0.00
2	I-2033-049	FHWA HEC-22 GENERIC	N/A	On Grade	1	121.88	126.59	4.71	121.88	0.00	N/A	0.00
3	I-2033-082	FHWA HEC-22 GENERIC	N/A	On Grade	1	126.31	131.23	4.92	126.31	0.00	N/A	0.00
4	I-2033-083	FHWA HEC-22 GENERIC	N/A	On Grade	1	131.19	136.10	4.91	131.19	0.00	N/A	0.00
5	I-2033-084	FHWA HEC-22 GENERIC	N/A	On Grade	1	132.19	135.57	3.39	132.19	0.00	N/A	0.00
6	I-2033-085	FHWA HEC-22 GENERIC	N/A	On Grade	1	131.28	136.39	5.11	131.28	0.00	N/A	0.00
7	I-2033-086	FHWA HEC-22 GENERIC	N/A	On Grade	1	136.09	140.72	4.63	136.09	0.00	N/A	0.00
8	I-2033-087	FHWA HEC-22 GENERIC	N/A	On Grade	1	135.45	140.42	4.97	135.45	0.00	N/A	0.00
9	I-2033-088	FHWA HEC-22 GENERIC	N/A	On Grade	1	137.77	142.83	5.06	137.77	0.00	N/A	0.00
10	I-2033-116	FHWA HEC-22 GENERIC	N/A	On Grade	1	137.79	142.84	5.05	137.79	0.00	N/A	0.00

Roadway & Gutter Input

SN	Element ID	Roadway Longitudinal Slope (ft/ft)	Roadway Cross Slope (ft/ft)	Roadway Manning's Roughness	Gutter Cross Slope (ft/ft)	Gutter Width (ft)	Gutter Depression (in)	Allowable Spread (ft)
1	I-2033-022	0.0178	0.0200	0.0160	0.0830	2.00	0.0000	7.00
2	I-2033-049	0.0100	0.0200	0.0160	0.0620	2.00	0.0656	7.00
3	I-2033-082	0.0110	0.0200	0.0160	0.0830	2.00	0.0000	7.00
4	I-2033-083	0.0091	0.0200	0.0160	0.0830	2.00	0.0000	7.00
5	I-2033-084	0.0177	0.0200	0.0160	0.0830	2.00	0.0000	7.00
6	I-2033-085	0.0091	0.0200	0.0160	0.0830	2.00	0.0000	7.00
7	I-2033-086	0.0264	0.0200	0.0160	0.0830	2.00	0.0000	7.00
8	I-2033-087	0.0264	0.0200	0.0160	0.0830	2.00	0.0000	7.00
9	I-2033-088	0.0083	0.0200	0.0160	0.0830	2.00	0.0000	7.00
10	I-2033-116	0.0083	0.0200	0.0160	0.0830	2.00	0.0000	7.00

Inlet Results

SN	Element ID	Peak Flow	Peak Lateral Inflow	Peak Flow Intercepted by Inlet	Peak Flow Bypassing Inlet	Inlet Efficiency during Peak Flow	Max Gutter Spread during Peak Flow	Max Gutter Water Elev. during Peak Flow	Max Gutter Water Depth during Peak Flow	Time of Max Depth Occurrence	Total Flooded Volume	Total Time Flooded
		(cfs)	(cfs)	(cfs)	(cfs)	(%)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	I-2033-022	0.21	0.21	0.21	0.00	99.99	1.48	127.12	0.12	0 12:25	0.00	0.00
2	I-2033-049	0.12	0.12	0.12	0.00	100.00	1.63	126.69	0.10	0 12:10	0.00	0.00
3	I-2033-082	2.24	2.24	1.24	1.00	55.48	8.36	131.52	0.29	0 12:20	0.00	0.00
4	I-2033-083	0.46	0.46	0.24	0.22	52.67	2.26	136.15	0.05	0 12:20	0.00	0.00
5	I-2033-084	0.72	0.72	0.15	0.57	20.31	2.36	135.62	0.05	0 12:09	2.58	67.00
6	I-2033-085	6.89	6.89	2.42	4.47	35.10	14.38	136.80	0.41	0 12:09	1.19	45.00
7	I-2033-086	0.60	0.60	0.05	0.55	8.19	2.05	140.76	0.04	0 12:20	0.00	0.00
8	I-2033-087	4.03	4.03	0.00	4.03	0.00	8.99	140.73	0.31	0 12:25	0.00	0.00
9	I-2033-088	0.89	0.89	0.68	0.21	76.06	5.38	143.06	0.23	0 05:08	1.46	1132.00
10	I-2033-116	0.75	0.75	0.60	0.14	80.99	4.77	143.06	0.22	0 05:23	1.33	1117.00

Storage Nodes

Storage Node : S-2033-050

Input Data

Invert Elevation (ft) .....	121.56
Max (Rim) Elevation (ft) .....	131.74
Max (Rim) Offset (ft) .....	10.18
Initial Water Elevation (ft) .....	121.56
Initial Water Depth (ft) .....	0.00
Ponded Area (ft²) .....	0.00
Evaporation Loss .....	0.00

Output Summary Results

Peak Inflow (cfs) .....	8.41
Peak Lateral Inflow (cfs) .....	0
Peak Outflow (cfs) .....	8.41
Peak Exfiltration Flow Rate (cfm) .....	0
Max HGL Elevation Attained (ft) .....	122.74
Max HGL Depth Attained (ft) .....	1.18
Average HGL Elevation Attained (ft) .....	122.39
Average HGL Depth Attained (ft) .....	0.83
Time of Max HGL Occurrence (days hh:mm) .....	0 12:22
Total Exfiltration Volume (1000-ft³) .....	0
Total Flooded Volume (ac-in) .....	0
Total Time Flooded (min) .....	0
Total Retention Time (sec) .....	0

## Proposed Stormwater System SSA Report & Results

Project Description

File Name ..... Quinhagak\_SSA\_Proposed\_V1Test.SPF

Project Options

Flow Units ..... CFS  
Elevation Type ..... Elevation  
Hydrology Method ..... SCS TR-55  
Time of Concentration (TOC) Method ..... SCS TR-55  
Link Routing Method ..... Hydrodynamic  
Enable Overflow Ponding at Nodes ..... YES  
Skip Steady State Analysis Time Periods ..... NO

Analysis Options

Start Analysis On ..... 00:00:00      0:00:00  
End Analysis On ..... 00:00:00      0:00:00  
Start Reporting On ..... 00:00:00      0:00:00  
Antecedent Dry Days ..... 0      days  
Runoff (Dry Weather) Time Step ..... 0 01:00:00      days hh:mm:ss  
Runoff (Wet Weather) Time Step ..... 0 00:05:00      days hh:mm:ss  
Reporting Time Step ..... 0 00:05:00      days hh:mm:ss  
Routing Time Step ..... 30      seconds

Number of Elements

Qty  
Rain Gages ..... 1  
Subbasins..... 22  
Nodes..... 32  
    *Junctions* ..... 28  
    *Outfalls* ..... 2  
    *Flow Diversions* ..... 0  
    *Inlets* ..... 0  
    *Storage Nodes* ..... 2  
Links..... 30  
    *Channels* ..... 0  
    *Pipes* ..... 30  
    *Pumps* ..... 0  
    *Orifices* ..... 0  
    *Weirs* ..... 0  
    *Outlets* ..... 0  
Pollutants ..... 0  
Land Uses ..... 0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
1	MOA	Time Series	MOA Design Storm Distribution	Cumulative	inches				0.00	

Subbasin Summary

SN Subbasin ID	Area	Peak Rate	Weighted	Total	Total	Total	Peak	Time of
		Factor	Curve	Rainfall	Runoff	Runoff	Runoff	Concentration
	(ac)		Number	(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1 1	0.04	484.00	88.00	2.46	1.32	0.05	0.04	0 00:08:43
2 4	0.59	484.00	88.00	2.46	1.35	0.80	0.38	0 00:20:51
3 63rd_Island	0.37	484.00	88.00	2.46	1.35	0.50	0.23	0 00:23:14
4 E1	0.56	484.00	88.00	2.46	1.35	0.75	0.33	0 00:25:41
5 E10	1.04	484.00	88.00	2.46	1.35	1.40	0.75	0 00:16:18
6 E10A	3.83	484.00	88.00	2.46	1.35	5.16	2.06	0 00:29:58
7 E11	1.08	484.00	75.00	2.46	0.63	0.68	0.21	0 00:36:45
8 E12	0.38	484.00	89.00	2.46	1.42	0.53	0.19	0 00:37:05
9 E2	0.09	484.00	88.00	2.46	1.34	0.13	0.08	0 00:13:00
10 E4	0.51	484.00	88.00	2.46	1.35	0.69	0.38	0 00:15:25
11 E5	12.55	484.00	88.00	2.46	1.35	16.93	6.90	0 00:28:50
12 E8	1.30	484.00	88.00	2.46	1.35	1.76	0.76	0 00:25:58
13 E9	0.81	484.00	88.00	2.46	1.35	1.09	0.54	0 00:19:35
14 Quinhagak_63rd_Island	0.71	484.00	88.00	2.46	1.35	0.96	0.46	0 00:20:37
15 Quinhagak_Sag_East	5.82	484.00	88.00	2.46	1.35	7.85	3.31	0 00:26:58
16 Quinhagak_Sag_West	0.86	484.00	88.00	2.46	1.35	1.16	0.63	0 00:15:59
17 W4	0.62	484.00	88.00	2.46	1.35	0.83	0.37	0 00:23:40
18 W5	0.78	484.00	88.00	2.46	1.35	1.05	0.59	0 00:14:47
19 W6	0.12	484.00	88.00	2.46	1.34	0.16	0.09	0 00:14:25
20 W7	1.76	484.00	88.00	2.46	1.35	2.37	1.23	0 00:17:49
21 W8	3.17	484.00	88.00	2.46	1.35	4.27	2.14	0 00:19:06
22 W9	0.33	484.00	75.00	2.46	0.63	0.21	0.07	0 00:30:48

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	S-63A	Junction	126.34	136.07	126.34	0.00	0.00	7.86	131.91	0.00	4.16	0 00:00	0.00	0.00
2	S-63B	Junction	131.80	140.54	131.80	0.00	0.00	0.22	133.65	0.00	6.89	0 00:00	0.00	0.00
3	S-64B	Junction	120.23	133.90	120.23	0.00	0.00	2.79	123.34	0.00	10.56	0 00:00	0.00	0.00
4	S-64C	Junction	122.24	136.78	122.24	0.00	0.00	0.72	123.35	0.00	13.43	0 00:00	0.00	0.00
5	S-AE	Junction	123.00	127.99	123.00	127.99	0.00	0.21	124.62	0.00	3.37	0 00:00	0.00	0.00
6	S-AW	Junction	120.25	127.77	121.75	127.77	0.00	0.28	121.90	0.00	5.87	0 00:00	0.00	0.00
7	S-B1	Junction	128.23	136.00	128.23	0.00	0.00	0.46	131.75	0.00	4.25	0 00:00	0.00	0.00
8	S-B2	Junction	124.66	135.06	124.66	0.00	0.00	1.20	128.38	0.00	6.68	0 00:00	0.00	0.00
9	S-B3	Junction	124.26	131.47	124.26	0.00	0.00	2.06	126.20	0.00	5.27	0 00:00	0.00	0.00
10	S-B4	Junction	123.72	130.72	125.19	1.10	0.00	0.19	125.29	0.00	5.43	0 00:00	0.00	0.00
11	S-E1	Junction	140.45	144.19	140.45	144.19	0.00	0.32	142.07	0.00	2.12	0 00:00	0.00	0.00
12	S-E2	Junction	138.98	144.10	138.98	144.10	0.00	0.08	139.04	0.00	5.06	0 00:00	0.00	0.00
13	S-E3	Junction	135.70	142.87	135.70	142.87	0.00	3.30	138.71	0.00	4.16	0 00:00	0.00	0.00
14	S-E4	Junction	133.28	140.28	133.28	140.28	0.00	0.37	134.94	0.00	5.34	0 00:00	0.00	0.00
15	S-E5	Junction	129.12	137.12	129.12	137.12	0.00	0.46	130.78	0.00	6.34	0 00:00	0.00	0.00
16	S-E6	Junction	129.36	135.69	130.86	135.69	0.00	0.00	130.86	0.00	4.83	0 00:00	0.00	0.00
17	S-E7	Junction	127.60	122.16	127.60	122.16	0.00	0.54	128.37	0.00	0.80	0 00:00	0.00	0.00
18	S-OGS2	Junction	118.88	131.29	118.88	0.00	0.00	19.82	122.52	0.00	8.76	0 00:00	0.00	0.00
19	S-Q1	Junction	127.15	136.16	127.15	0.00	0.00	13.70	130.19	0.00	5.97	0 00:00	0.00	0.00
20	S-Q2	Junction	126.62	135.48	126.62	0.00	0.00	13.70	129.48	0.00	6.00	0 00:00	0.00	0.00
21	Structure - (67)	Junction	119.53	121.26	119.53	121.26	0.00	0.28	119.90	0.00	2.35	0 00:00	0.00	0.00
22	S-W1	Junction	136.70	144.19	136.70	144.19	0.00	0.34	138.38	0.00	5.81	0 00:00	0.00	0.00
23	S-W2	Junction	135.00	144.09	135.00	144.09	0.00	0.77	136.76	0.00	7.32	0 00:00	0.00	0.00
24	S-W3	Junction	133.30	142.87	133.30	142.87	0.00	4.52	135.42	0.00	7.45	0 00:00	0.00	0.00
25	S-W4	Junction	130.52	140.05	130.52	140.05	0.00	5.20	132.65	0.00	7.40	0 00:00	0.00	0.00
26	S-W5	Junction	127.74	136.89	127.74	136.89	0.00	6.15	130.29	0.00	6.60	0 00:00	0.00	0.00
27	S-W6	Junction	125.73	134.20	125.73	134.20	0.00	14.73	128.37	0.00	5.82	0 00:00	0.00	0.00
28	S-W7	Junction	123.74	132.20	123.74	132.20	0.00	17.15	126.78	0.00	5.42	0 00:00	0.00	0.00
29	Outfall-64th	Outfall	120.38					19.82	121.36					
30	Outfall-Askeland	Outfall	118.66					0.28	118.85					
31	S-64A	Storage Node	119.90	131.22	119.90		0.00	19.82	123.33				0.00	0.00
32	S-OGS1	Storage Node	119.75	131.17	119.75		0.00	19.82	122.98				0.00	0.00

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Surcharged	Reported Condition
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)		(min)	
1	0.28x	Pipe	Structure - (67)	Outfall-Askeland	238.57	119.53	118.66	0.3600	18.000	0.0240	0.28	3.44	0.08	1.22	0.28	0.19	0.00	Calculated
2	P-63B	Pipe	S-63A	S-Q1	74.02	130.72	129.98	1.0000	18.000	0.0120	7.82	11.38	0.69	5.90	1.05	0.70	0.00	Calculated
3	P-63C	Pipe	S-63B	S-63A	300.33	133.50	130.85	0.8800	18.000	0.0120	0.22	10.70	0.02	0.73	0.61	0.41	0.00	Calculated
4	P-64A	Pipe	S-OGS2	Outfall-64th	166.57	121.10	120.38	0.4300	38.000	0.0240	19.82	46.53	0.43	4.04	1.20	0.38	0.00	Calculated
5	P-64B	Pipe	S-64B	S-64A	44.44	121.73	121.50	0.5200	42.000	0.0240	2.89	39.21	0.07	1.14	1.72	0.49	0.00	Calculated
6	P-64C	Pipe	S-64C	S-64B	213.07	122.89	121.83	0.5000	36.000	0.0240	0.71	25.48	0.03	0.72	0.98	0.33	0.00	Calculated
7	P-A2	Pipe	S-AW	Structure - (67)	50.16	121.75	120.75	1.9900	18.000	0.0120	0.28	16.07	0.02	3.27	0.14	0.10	0.00	Calculated
8	P-A3	Pipe	S-AE	S-AW	33.80	124.50	123.10	4.1400	12.000	0.0120	0.21	7.86	0.03	4.14	0.12	0.12	0.00	Calculated
9	P-B1	Pipe	S-B1	S-E5	23.85	131.55	130.80	3.1400	12.000	0.0120	0.46	6.84	0.07	4.44	0.19	0.19	0.00	Calculated
10	P-B2	Pipe	S-B2	S-W6	16.05	128.04	127.40	4.0000	12.000	0.0150	1.20	6.17	0.19	3.26	0.65	0.65	0.00	Calculated
11	P-B3	Pipe	S-B3	S-64B	17.35	125.67	124.80	5.0100	12.000	0.0120	2.06	8.64	0.24	6.33	0.43	0.43	0.00	Calculated
12	P-B4	Pipe	S-B4	S-64B	27.40	125.19	123.00	7.9900	12.000	0.0120	0.19	10.91	0.02	4.88	0.21	0.21	0.00	Calculated
13	PC-1	Pipe	S-E1	S-W1	34.00	141.95	138.50	10.1500	12.000	0.0120	0.32	12.29	0.03	6.40	0.12	0.12	0.00	Calculated
14	PC-2	Pipe	S-E2	S-W2	35.00	138.98	136.26	7.7700	12.000	0.0120	0.08	10.76	0.01	0.44	0.28	0.28	0.00	Calculated
15	PC-3	Pipe	S-W3	S-E3	34.00	137.20	134.56	7.7600	12.000	0.0150	3.30	6.49	0.51	5.20	0.75	0.75	0.00	Calculated
16	PC-4	Pipe	S-E4	S-W4	34.00	134.78	133.42	4.0000	12.000	0.0120	0.37	7.72	0.05	4.73	0.15	0.15	0.00	Calculated
17	PC-5	Pipe	S-E5	S-W5	33.80	130.62	129.34	3.7900	15.000	0.0120	0.46	13.62	0.03	2.23	0.55	0.44	0.00	Calculated
18	PC-6	Pipe	S-E6	S-Q2	34.51	130.86	129.48	4.0000	12.000	0.0120	0.00	7.72	0.00	0.00	0.00	0.00	0.00	Calculated
19	PC-7	Pipe	S-E7	S-W7	34.00	128.17	126.81	4.0000	12.000	0.0120	0.54	7.72	0.07	5.22	0.19	0.19	0.00	Calculated
20	P-OGS1	Pipe	S-64A	S-OGS1	10.00	121.40	121.35	0.5000	42.000	0.0120	19.82	77.07	0.26	4.68	1.78	0.51	0.00	Calculated
21	P-OGS2	Pipe	S-OGS1	S-OGS2	10.00	121.25	121.20	0.5000	42.000	0.0120	19.82	77.07	0.26	4.91	1.53	0.44	0.00	Calculated
22	PW-1	Pipe	S-W1	S-W2	159.38	138.20	136.61	1.0000	18.000	0.0120	0.33	11.38	0.03	2.82	0.18	0.12	0.00	Calculated
23	P-W2	Pipe	S-W2	S-W3	159.76	136.50	134.90	1.0000	18.000	0.0120	0.77	11.39	0.07	2.16	0.39	0.26	0.00	Calculated
24	P-W3	Pipe	S-W3	S-W4	267.89	134.80	132.12	1.0000	24.000	0.0120	4.51	24.51	0.18	5.71	0.60	0.30	0.00	Calculated
25	P-W4	Pipe	S-W4	S-W5	267.86	132.02	129.34	1.0000	24.000	0.0120	5.20	24.51	0.21	5.16	0.78	0.39	0.00	Calculated
26	P-W5	Pipe	S-W5	S-Q1	48.18	129.24	128.76	1.0000	24.000	0.0120	6.06	24.46	0.25	3.28	1.24	0.62	0.00	Calculated
27	P-W6	Pipe	S-Q1	S-Q2	42.64	128.65	128.22	1.0000	24.000	0.0120	13.70	24.50	0.56	5.84	1.40	0.70	0.00	Calculated
28	P-W7	Pipe	S-Q2	S-W6	78.91	128.12	127.33	1.0000	24.000	0.0120	13.70	24.51	0.56	6.85	1.22	0.61	0.00	Calculated
29	P-W8	Pipe	S-W6	S-W7	188.51	127.23	125.35	1.0000	30.000	0.0120	14.73	44.43	0.33	5.82	1.28	0.52	0.00	Calculated
30	PW-9	Pipe	S-W7	S-64A	41.35	125.24	124.83	1.0000	30.000	0.0120	17.14	44.44	0.39	6.58	1.30	0.52	0.00	Calculated

Junction Input

SN	Element ID	Invert Elevation	Ground/Rim (Max) Elevation	Ground/Rim (Max) Offset	Initial Water Elevation	Initial Water Depth	Surcharge Elevation	Surcharge Depth	Ponded Area	Minimum Pipe Cover
		(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft²)	(in)
1	S-63A	126.34	136.07	9.73	126.34	0.00	0.00	-136.07	0.00	0.00
2	S-63B	131.80	140.54	8.74	131.80	0.00	0.00	-140.54	0.00	0.00
3	S-64B	120.23	133.90	13.67	120.23	0.00	0.00	-133.90	0.00	0.00
4	S-64C	122.24	136.78	14.54	122.24	0.00	0.00	-136.78	0.00	0.00
5	S-AE	123.00	127.99	4.99	123.00	0.00	127.99	0.00	0.00	0.00
6	S-AW	120.25	127.77	7.52	121.75	1.50	127.77	0.00	0.00	0.00
7	S-B1	128.23	136.00	7.77	128.23	0.00	0.00	-136.00	0.00	0.00
8	S-B2	124.66	135.06	10.40	124.66	0.00	0.00	-135.06	0.00	0.00
9	S-B3	124.66	131.47	7.21	124.26	0.00	0.00	-131.47	0.00	0.00
10	S-B4	123.72	130.72	7.00	125.19	1.47	1.10	-129.62	0.00	0.00
11	S-E1	140.45	144.19	3.74	140.45	0.00	144.19	0.00	0.00	0.00
12	S-E2	138.98	144.10	5.12	138.98	0.00	144.10	0.00	0.00	0.00
13	S-E3	135.70	142.87	7.17	135.70	0.00	142.87	0.00	0.00	0.00
14	S-E4	133.28	140.28	7.00	133.28	0.00	140.28	0.00	0.00	0.00
15	S-E5	129.12	137.12	8.00	129.12	0.00	137.12	0.00	0.00	0.00
16	S-E6	129.36	135.69	6.33	130.86	1.50	135.69	0.00	0.00	0.00
17	S-E7	127.60	122.16	-5.44	127.60	0.00	122.16	0.00	0.00	0.00
18	S-OGS2	118.88	131.29	12.41	118.88	0.00	0.00	-131.29	0.00	0.00
19	S-Q1	127.15	136.16	9.01	127.15	0.00	0.00	-136.16	0.00	0.00
20	S-Q2	126.62	135.48	8.86	126.62	0.00	0.00	-135.48	0.00	0.00
21	Structure - (67)	119.53	121.26	1.73	119.53	0.00	121.26	0.00	0.00	0.00
22	S-W1	136.70	144.19	7.49	136.70	0.00	144.19	0.00	0.00	0.00
23	S-W2	135.00	144.09	9.09	135.00	0.00	144.09	0.00	0.00	0.00
24	S-W3	133.30	142.87	9.57	133.30	0.00	142.87	0.00	0.00	0.00
25	S-W4	130.52	140.05	9.53	130.52	0.00	140.05	0.00	0.00	0.00
26	S-W5	127.74	136.89	9.15	127.74	0.00	136.89	0.00	0.00	0.00
27	S-W6	125.73	134.20	8.47	125.73	0.00	134.20	0.00	0.00	0.00
28	S-W7	123.74	132.20	8.46	123.74	0.00	132.20	0.00	0.00	0.00

Junction Results

SN	Element ID	Peak Inflow	Peak Lateral Inflow	Max HGL Elevation Attained	Max HGL Depth Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Average HGL Elevation Attained	Average HGL Depth Attained	Time of Max HGL Occurrence	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
		(cfs)	(cfs)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(days hh:mm)	(days hh:mm)	(ac-in)	(min)
1	S-63A	7.86	7.64	131.91	5.57	0.00	4.16	131.04	4.70	0 12:25	0 00:00	0.00	0.00
2	S-63B	0.22	0.22	133.65	1.86	0.00	6.89	133.50	1.71	0 12:21	0 00:00	0.00	0.00
3	S-64B	2.79	0.00	123.34	3.11	0.00	10.56	122.19	1.96	0 12:24	0 00:00	0.00	0.00
4	S-64C	0.72	0.72	123.35	1.11	0.00	13.43	123.02	0.78	0 12:24	0 00:00	0.00	0.00
5	S-AE	0.21	0.21	124.62	1.62	0.00	3.37	124.42	1.42	0 12:30	0 00:00	0.00	0.00
6	S-AW	0.28	0.07	121.90	1.65	0.00	5.87	121.83	1.58	0 12:30	0 00:00	0.00	0.00
7	S-B1	0.46	0.46	131.75	3.52	0.00	4.25	131.49	3.26	0 12:20	0 00:00	0.00	0.00
8	S-B2	1.20	1.20	128.38	3.72	0.00	6.68	128.04	3.38	0 12:23	0 00:00	0.00	0.00
9	S-B3	2.06	2.06	126.20	1.94	0.00	5.27	125.83	1.57	0 12:25	0 00:00	0.00	0.00
10	S-B4	0.19	0.19	125.29	1.57	0.00	5.43	125.24	1.52	0 12:34	0 00:00	0.00	0.00
11	S-E1	0.32	0.32	142.07	1.62	0.00	2.12	141.94	1.49	0 12:25	0 00:00	0.00	0.00
12	S-E2	0.08	0.08	139.04	0.06	0.00	5.06	139.01	0.03	0 12:15	0 00:00	0.00	0.00
13	S-E3	3.30	3.30	138.71	3.01	0.00	4.16	137.62	1.92	0 12:25	0 00:00	0.00	0.00
14	S-E4	0.37	0.37	134.94	1.66	0.00	5.34	134.79	1.51	0 12:15	0 00:00	0.00	0.00
15	S-E5	0.46	0.00	130.78	1.66	0.00	6.34	130.62	1.50	0 12:20	0 00:00	0.00	0.00
16	S-E6	0.00	0.00	130.86	1.50	0.00	4.83	130.86	1.50	0 00:00	0 00:00	0.00	0.00
17	S-E7	0.54	0.54	128.37	0.77	0.00	0.80	128.23	0.63	0 12:20	0 00:00	0.00	0.00
18	S-OGS2	19.82	0.00	122.52	3.64	0.00	8.76	121.64	2.76	0 12:24	0 00:00	0.00	0.00
19	S-Q1	13.70	0.00	130.19	3.04	0.00	5.97	129.20	2.05	0 12:25	0 00:00	0.00	0.00
20	S-Q2	13.70	0.00	129.48	2.86	0.00	6.00	128.62	2.00	0 12:25	0 00:00	0.00	0.00
21	Structure - (67)	0.28	0.00	119.90	0.37	0.00	2.35	119.73	0.20	0 12:32	0 00:00	0.00	0.00
22	S-W1	0.34	0.04	138.38	1.68	0.00	5.81	138.22	1.52	0 12:22	0 00:00	0.00	0.00
23	S-W2	0.77	0.38	136.76	1.76	0.00	7.32	136.56	1.56	0 12:20	0 00:00	0.00	0.00
24	S-W3	4.52	0.60	135.42	2.12	0.00	7.45	135.02	1.72	0 12:21	0 00:00	0.00	0.00
25	S-W4	5.20	0.37	132.65	2.13	0.00	7.40	132.26	1.74	0 12:21	0 00:00	0.00	0.00
26	S-W5	6.15	0.57	130.29	2.55	0.00	6.60	129.56	1.82	0 12:23	0 00:00	0.00	0.00
27	S-W6	14.73	0.09	128.37	2.64	0.00	5.82	127.66	1.93	0 12:23	0 00:00	0.00	0.00
28	S-W7	17.15	2.12	126.78	3.04	0.00	5.42	125.83	2.09	0 12:22	0 00:00	0.00	0.00

Pipe Input

SN	Element ID	Length (ft)	Inlet Invert Elevation (ft)	Inlet Invert Offset (ft)	Outlet Invert Elevation (ft)	Outlet Invert Offset (ft)	Total Drop (ft)	Average Slope (%)	Pipe Shape	Pipe Diameter or Height (in)	Pipe Width (in)	Manning's Roughness	Entrance Losses	Exit/Bend Losses	Additional Losses	Initial Flow (cfs)	Flap Gate	No. of Barrels
1	0.28x	238.57	119.53	0.00	118.66	0.00	0.87	0.3600	CIRCULAR	18.000	18.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
2	P-63B	74.02	130.72	4.38	129.98	2.83	0.74	1.0000	CIRCULAR	18.000	18.000	0.0120	0.5000	0.7000	0.0000	0.00	No	1
3	P-63C	300.33	133.50	1.71	130.85	4.51	2.66	0.8800	CIRCULAR	18.000	18.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
4	P-64A	166.57	121.10	2.22	120.38	0.00	0.72	0.4300	Arch	38.040	57.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
5	P-64B	44.44	121.73	1.50	121.50	1.60	0.23	0.5200	CIRCULAR	42.000	42.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
6	P-64C	213.07	122.89	0.65	121.83	1.60	1.06	0.5000	CIRCULAR	36.000	36.000	0.0240	0.5000	0.5000	0.0000	0.00	No	1
7	P-A2	50.16	121.75	1.50	120.75	1.22	1.00	1.9900	CIRCULAR	18.000	18.000	0.0120	0.5000	0.8000	0.0000	0.00	No	1
8	P-A3	33.80	124.50	1.50	123.10	2.85	1.40	4.1400	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
9	P-B1	23.85	131.55	3.32	130.80	1.68	0.75	3.1400	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
10	P-B2	16.05	128.04	3.38	127.40	1.67	0.64	4.0000	CIRCULAR	12.000	12.000	0.0150	0.5000	0.6000	0.0000	0.00	No	1
11	P-B3	17.35	125.67	1.41	124.80	4.57	0.87	5.0100	CIRCULAR	12.000	12.000	0.0120	0.5000	1.0000	0.0000	0.00	No	1
12	P-B4	27.40	125.19	1.47	123.00	2.77	2.19	7.9900	CIRCULAR	12.000	12.000	0.0120	0.5000	1.0000	0.0000	0.00	No	1
13	PC-1	34.00	141.95	1.50	138.50	1.80	3.45	10.1500	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
14	PC-2	35.00	138.98	0.00	136.26	1.26	2.72	7.7700	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
15	PC-3	34.00	137.20	3.90	134.56	-1.14	2.64	7.7600	CIRCULAR	12.000	12.000	0.0150	0.5000	0.6000	0.0000	0.00	No	1
16	PC-4	34.00	134.78	1.50	133.42	2.90	1.36	4.0000	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
17	PC-5	33.80	130.62	1.50	129.34	1.60	1.28	3.7900	CIRCULAR	15.000	15.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
18	PC-6	34.51	130.86	1.50	129.48	2.86	1.38	4.0000	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
19	PC-7	34.00	128.17	0.57	126.81	3.07	1.36	4.0000	CIRCULAR	12.000	12.000	0.0120	0.5000	0.6000	0.0000	0.00	No	1
20	P-OGS1	10.00	121.40	1.50	121.35	1.60	0.05	0.5000	CIRCULAR	42.000	42.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
21	P-OGS2	10.00	121.25	1.50	121.20	2.32	0.05	0.5000	CIRCULAR	42.000	42.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
22	PW-1	159.38	138.20	1.50	136.61	1.61	1.59	1.0000	CIRCULAR	18.000	18.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
23	P-W2	159.76	136.50	1.50	134.90	1.60	1.60	1.0000	CIRCULAR	18.000	18.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
24	P-W3	267.89	134.80	1.50	132.12	1.60	2.68	1.0000	CIRCULAR	24.000	24.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
25	P-W4	267.86	132.02	1.50	129.34	1.60	2.68	1.0000	CIRCULAR	24.000	24.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
26	P-W5	48.18	129.24	1.50	128.76	1.61	0.48	1.0000	CIRCULAR	24.000	24.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
27	P-W6	42.64	128.65	1.50	128.22	1.60	0.43	1.0000	CIRCULAR	24.000	24.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
28	P-W7	78.91	128.12	1.50	127.33	1.60	0.79	1.0000	CIRCULAR	24.000	24.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
29	P-W8	188.51	127.23	1.50	125.35	1.61	1.89	1.0000	CIRCULAR	30.000	30.000	0.0120	0.5000	0.5000	0.0000	0.00	No	1
30	PW-9	41.35	125.24	1.50	124.83	4.93	0.41	1.0000	CIRCULAR	30.000	30.000	0.0120	0.5000	0.7000	0.0000	0.00	No	1

Pipe Results

SN	Element ID	Peak Flow	Time of Peak Flow Occurrence	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Travel Time	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Surcharged	Froude Number	Reported Condition
		(cfs)	(days hh:mm)	(cfs)		(ft/sec)	(min)	(ft)		(min)		
1	0.28x	0.28	0 12:32	3.44	0.08	1.22	3.26	0.28	0.19	0.00		Calculated
2	P-63B	7.82	0 12:25	11.38	0.69	5.90	0.21	1.05	0.70	0.00		Calculated
3	P-63C	0.22	0 12:21	10.70	0.02	0.73	6.86	0.61	0.41	0.00		Calculated
4	P-64A	19.82	0 12:24	46.53	0.43	4.04	0.69	1.20	0.38	0.00		Calculated
5	P-64B	2.89	0 12:29	39.21	0.07	1.14	0.65	1.72	0.49	0.00		Calculated
6	P-64C	0.71	0 12:19	25.48	0.03	0.72	4.93	0.98	0.33	0.00		Calculated
7	P-A2	0.28	0 12:30	16.07	0.02	3.27	0.26	0.14	0.10	0.00		Calculated
8	P-A3	0.21	0 12:30	7.86	0.03	4.14	0.14	0.12	0.12	0.00		Calculated
9	P-B1	0.46	0 12:20	6.84	0.07	4.44	0.09	0.19	0.19	0.00		Calculated
10	P-B2	1.20	0 12:20	6.17	0.19	3.26	0.08	0.65	0.65	0.00		Calculated
11	P-B3	2.06	0 12:25	8.64	0.24	6.33	0.05	0.43	0.43	0.00		Calculated
12	P-B4	0.19	0 12:30	10.91	0.02	4.88	0.09	0.21	0.21	0.00		Calculated
13	PC-1	0.32	0 12:25	12.29	0.03	6.40	0.09	0.12	0.12	0.00		Calculated
14	PC-2	0.08	0 12:15	10.76	0.01	0.44	1.33	0.28	0.28	0.00		Calculated
15	PC-3	3.30	0 12:25	6.49	0.51	5.20	0.11	0.75	0.75	0.00		Calculated
16	PC-4	0.37	0 12:15	7.72	0.05	4.73	0.12	0.15	0.15	0.00		Calculated
17	PC-5	0.46	0 12:20	13.62	0.03	2.23	0.25	0.55	0.44	0.00		Calculated
18	PC-6	0.00	0 00:00	7.72	0.00	0.00		0.00	0.00	0.00		Calculated
19	PC-7	0.54	0 12:20	7.72	0.07	5.22	0.11	0.19	0.19	0.00		Calculated
20	P-OGS1	19.82	0 12:24	77.07	0.26	4.68	0.04	1.78	0.51	0.00		Calculated
21	P-OGS2	19.82	0 12:24	77.07	0.26	4.91	0.03	1.53	0.44	0.00		Calculated
22	PW-1	0.33	0 12:22	11.38	0.03	2.82	0.94	0.18	0.12	0.00		Calculated
23	P-W2	0.77	0 12:20	11.39	0.07	2.16	1.23	0.39	0.26	0.00		Calculated
24	P-W3	4.51	0 12:22	24.51	0.18	5.71	0.78	0.60	0.30	0.00		Calculated
25	P-W4	5.20	0 12:21	24.51	0.21	5.16	0.87	0.78	0.39	0.00		Calculated
26	P-W5	6.06	0 12:22	24.46	0.25	3.28	0.24	1.24	0.62	0.00		Calculated
27	P-W6	13.70	0 12:25	24.50	0.56	5.84	0.12	1.40	0.70	0.00		Calculated
28	P-W7	13.70	0 12:25	24.51	0.56	6.85	0.19	1.22	0.61	0.00		Calculated
29	P-W8	14.73	0 12:23	44.43	0.33	5.82	0.54	1.28	0.52	0.00		Calculated
30	PW-9	17.14	0 12:22	44.44	0.39	6.58	0.10	1.30	0.52	0.00		Calculated

Storage Nodes

Storage Node : S-64A

Input Data

Invert Elevation (ft)	119.90
Max (Rim) Elevation (ft)	131.22
Max (Rim) Offset (ft)	11.32
Initial Water Elevation (ft)	119.90
Initial Water Depth (ft)	0.00
Ponded Area (ft²)	0.00
Evaporation Loss	0.00

Output Summary Results

Peak Inflow (cfs)	19.82
Peak Lateral Inflow (cfs)	0
Peak Outflow (cfs)	19.82
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	123.33
Max HGL Depth Attained (ft)	3.43
Average HGL Elevation Attained (ft)	122.14
Average HGL Depth Attained (ft)	2.24
Time of Max HGL Occurrence (days hh:mm)	0 12:24
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

**Storage Node : S-OGS1**

**Input Data**

Invert Elevation (ft) .....	119.75
Max (Rim) Elevation (ft) .....	131.17
Max (Rim) Offset (ft) .....	11.42
Initial Water Elevation (ft) .....	119.75
Initial Water Depth (ft) .....	0.00
Ponded Area (ft²) .....	0.00
Evaporation Loss .....	0.00

**Output Summary Results**

Peak Inflow (cfs) .....	19.82
Peak Lateral Inflow (cfs) .....	0
Peak Outflow (cfs) .....	19.82
Peak Exfiltration Flow Rate (cfm) .....	0
Max HGL Elevation Attained (ft) .....	122.98
Max HGL Depth Attained (ft) .....	3.23
Average HGL Elevation Attained (ft) .....	121.94
Average HGL Depth Attained (ft) .....	2.19
Time of Max HGL Occurrence (days hh:mm) .....	0 12:24
Total Exfiltration Volume (1000-ft³) .....	0
Total Flooded Volume (ac-in) .....	0
Total Time Flooded (min) .....	0
Total Retention Time (sec) .....	0